

AGENDA

PLANNING COMMISSION

of the

CITY OF HANFORD

COUNCIL CHAMBERS
400 N. Douty St.
7:00 PM, Tuesday, May 14, 2019

CALL TO ORDER

ROLL CALL

INVOCATION

FLAG SALUTE

PUBLIC COMMENT

*This is the time for citizens to comment on subject matters not on the agenda and that are within the jurisdiction of the Commission. This is also the public's opportunity to request an item from the Consent Calendar be pulled for discussion purposes or to comment on any item on the agenda. Comments related to Public Hearing items will be heard at the time the item is discussed. A maximum of **three minutes** is allowed for each speaker. Please begin your comments by stating your name and providing your city of residence.*

CONSENT CALENDAR

Consent Calendar items are considered routine and will be enacted in one motion. There will be no separate discussion of these matters unless a request is made and then the item will be removed from the Consent Calendar to be discussed and voted upon by a separate motion.

- 1. Approval of the Minutes of the April 23, 2019 Meeting**
- 2. TIME EXTENSION 2019-01, a request to extend the life of Tentative Tract 919 Unit II for 24 months. The project applies to property located south of Fargo Avenue, west of Centennial Drive (APN 009-030-154).**

PUBLIC HEARING

Continued item from Tuesday, April 23, 2019 -MUNICIPAL CODE AMENDMENT NO. 2019-01: a request by 198-43, LLC to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; furniture stores; and food catering.

DIRECTOR'S COMMENTS

COMMISSIONERS' ITEMS OF INTEREST

ADJOURNMENT

Materials related to an item on this Agenda submitted to the Planning Commission after distribution of the agenda packet are available to public inspection in the Planning Division Office located at 317 N. Douty Street, Hanford, California 93230, during normal business hours. Such documents are also available at the city's website, www.cityofhanfordca.com subject to staff's ability to post documents before the meeting.

If you need a disability-related modification or accommodation, including auxiliary aids or services, to participate in this meeting, please contact the Planning Division's office, 559-585-2580, 317 N. Douty Street, Hanford, California 93230, at least 2 days prior to the meeting {28 CFR 35.102.35.104 ADA Title II}

APPEALS:

Any action of the Planning Commission, which is a final project decision, may be appealed to the City Council by the applicant or any adversely affected person. To file an appeal, an appeal application and filing fee of \$1,000.00 must be submitted to the Community Development Department, 317 N. Douty Street, Hanford, California, within ten (10) days following the date of the final decision of the Planning Commission.



**AGENDA
STAFF REPORT**

MEETING DATE: 5/14/2019	AGENDA SECTION: 1
--------------------------------	--------------------------

SUBJECT:

Approval of the Minutes of the April 23, 2019 Meeting

RECOMMENDATION:


Approve the Minutes of the April 23, 2019 meeting.

BACKGROUND:

FISCAL IMPACT:

ATTACHMENTS:

04-23-19 Minutes



MINUTES
PLANNING COMMISSION
of the
CITY OF HANFORD

COUNCIL CHAMBERS
400 N. Douty St.
7:00 PM, Tuesday, April 23, 2019

CALL TO ORDER

Chairperson PADEN called the meeting to order at 7:00 p.m.

ROLL CALL

Attendee Name	Title	Status	Arrived
Richard Douglas		Present	6:53 PM
Michael Johnston		Present	6:49 PM
Travis Paden		Present	6:41 PM
Savino Perico		Present	6:57 PM
Angel Vee Galvan		Present	6:56 PM
Jacob Sanchez		Present	6:49 PM
Jason Kemp Van Ee		Present	6:49 PM

INVOCATION

Pastor Robert Hayden, Howard Chapel AME Zion Church

FLAG SALUTE

Commissioner SANCHEZ led the flag salute.

PUBLIC COMMENT

*This is the time for citizens to comment on subject matters not on the agenda and that are within the jurisdiction of the Commission. This is also the public's opportunity to request an item from the Consent Calendar be pulled for discussion purposes or to comment on any item on the agenda. Comments related to Public Hearing items will be heard at the time the item is discussed. A maximum of **three minutes** is allowed for each speaker. Please begin your comments by stating your name and providing your city of residence.*

Attachment: 04-23-19 Minutes (04-23-19 Minutes)

Prior to Public Comment, City Attorney Mizote announced that he would be recused from this meeting, due to conflicts of interest. He introduced Attorney Ray Carlson, also with the Griswold, LaSalle firm, who would be the City Attorney for the meeting.

CONSENT CALENDAR

Consent Calendar items are considered routine and will be enacted in one motion. There will be no separate discussion of these matters unless a request is made and then the item will be removed from the Consent Calendar to be discussed and voted upon by a separate motion.

Motion to approve the Consent Calendar.

RESULT:	APPROVED [UNANIMOUS]
MOVER:	Richard Douglas
SECONDER:	Michael Johnston
AYES:	Douglas, Johnston, Paden, Perico, Galvan, Sanchez, Kemp Van Ee

Approval of the Minutes of the March 12, 2019 Meeting

PUBLIC HEARING

- 1. Municipal Code Amendment No. 2019-01: a request by 198-43, LLC to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; government offices; furniture stores; landscape nurseries; banks and credit unions – secondary branch; food catering; payday lenders; and tailoring. (Staff recommends continuance of the item to May 14, 2019).**

Per Community Development Director Mata, staff recommended that the Public Hearing be continued to the May 14, 2019 meeting.

Hanford resident Diane Sharp encouraged the Commission and staff to open this item to extensive review and broad-based comment before referring it to City Council. She suggested that City staff meet with downtown business owners, at the owners' convenience, to get their input.

Motion to continue the Public Hearing for Municipal Code Amendment No. 2019-01 to the next Planning Commission meeting on May 14, 2019.

RESULT:	APPROVED [UNANIMOUS]
MOVER:	Michael Johnston
SECONDER:	Richard Douglas
AYES:	Douglas, Johnston, Paden, Perico, Galvan, Sanchez, Kemp Van Ee

- 2. Conditional Use Permit No. 2019-03: is a request to allow a furniture store, under 20,000 square feet, to be located within the Hanford Mall in the C-R Regional Commercial zone district. The project is located at 1673 W. Lacey Boulevard, Suite 109 (APN 011-060-037).**

Chairperson PADEN opened the Public Hearing at 7:11 p.m. and called for the Staff Report.

Senior Planner Myers presented the staff report, recommended approval, and invited questions of staff.

Chairperson PADEN opened Public Comment:

FAVOR

None.

OPPOSED

David Ayers, Hanford - He expressed concern that, with the C-R zone being open to furniture sales at the mall, with a Conditional Use Permit (CUP), downtown will experience a mass exodus of businesses, resulting in blight. He encouraged the Commissioners to deny the CUP.

Director Mata addressed Mr. Ayers' concerns, stating that staff was able to support all the required findings for approval. She noted that, if the Commission decides to deny the CUP, they must make the findings for denial, by showing that these conditions cannot be met.

Joe Serrano, owner (with his father) of Serrano's Furniture, stated that his business is growing, and they need more room. If his location were larger, he would remain downtown; but, he had to look for a larger space. Serrano's owns the building at their current location, and they are looking for a tenant to rent the space. Mr. Serrano responded to Commissioners' questions.

Chairperson PADEN closed the Public Hearing at 7:41 p.m. and called for a motion.

Motion to adopt Resolution No. 2019-05, approving Conditional Use Permit 2019-03.

RESULT:	APPROVED [6 TO 1]
MOVER:	Richard Douglas
SECONDER:	Jason Kemp Van Ee
AYES:	Douglas, Johnston, Paden, Perico, Sanchez, Kemp Van Ee
NAYS:	Galvan

- 3. MUNICIPAL CODE AMENDMENT NO. 2019-02 is a request to amend Title 17, Section 17.08.030 of the Hanford Municipal Code by adding to the line D8 “dispensaries (non-storefront retail)” as a conditional use in the IH zone, amending line I23 to allow storefront retail dispensaries as a conditional use in the MX-D zone and amend Section 17.69 to allow medical and adult use commercial operations and to allow dispensaries.**

Chairperson PADEN opened the Public Hearing at 7:44 p.m. and called for the staff report.

Director Mata presented the staff report, recommended approval, and invited questions of staff.

She and Police Chief Parker addressed Commissioners' questions.

Chairperson PADEN opened Public Comment:

FAVOR

Larry Thacker, San Jose, representing Caliva (cannabis dispensaries) - He stated that legal cannabis dispensaries are necessary, in order to combat illegal cannabis business. He would like to bring Caliva to downtown Hanford.

OPPOSED

John Lehn, Hanford - Mr. Lehn expressed concern over possible odor and suggested the addition of strict odor control.

Director Mata replied to Mr. Lehn's concern, stating that the City's ordinance prohibits allowing it to become a nuisance. Chief Sever added that the products are already in sealed packages and that most odor issues occur with outdoor or greenhouse cultivation.

Following considerable discussion, Chairperson PADEN closed the Public Hearing at 8:27 p.m. and called for a motion.

Motion to approve Resolution 2019-06 recommending approval of Municipal Code Amendment 2019-02 to the City Council, amending Section 17.69.030 B.1. by adding colleges to the list of schools.

RESULT:	APPROVED [6 TO 1]
MOVER:	Michael Johnston
SECONDER:	Jacob Sanchez
AYES:	Douglas, Johnston, Paden, Perico, Galvan, Sanchez
NAYS:	Kemp Van Ee

DIRECTOR'S COMMENTS

Director Mata announced: 1) Aldi's grand opening will be Thursday, May 2, 8:00 a.m.; 2) Gabrielle Myers has been promoted from Associate Planner to Senior Planner. She thanked Ms. Myers for her hard work and congratulated her on the promotion.

COMMISSIONERS' ITEMS OF INTEREST

Commissioner GALVAN referred to Page 57 of the agenda packet and noted that it contained an incorrect Notice of Exemption. Director Mata assured her that staff would include the correct Notice.

Commissioner JOHNSTON reported a very large hole in the sidewalk in front of Serrano's Furniture at Sixth and Douty Streets. Staff will check on that right away.

Commissioners DOUGLAS and KEMP VAN EE congratulated Ms. Myers on her promotion.

Chairperson PADEN commented that Amazon's free shipping on furniture purchases might present challenges for our furniture stores.

ADJOURNMENT

Chairperson PADEN adjourned the meeting at 8:34 p.m.

Respectfully submitted,

Diana Black
Recording Secretary



AGENDA STAFF REPORT

MEETING DATE: 5/14/2019	AGENDA SECTION: 2
--------------------------------	--------------------------

SUBJECT:

TIME EXTENSION 2019-01, a request to extend the life of Tentative Tract 919 Unit II for 24 months. The project applies to property located south of Fargo Avenue, west of Centennial Drive (APN 009-030-154).

See staff report, attached.

FISCAL IMPACT:

ATTACHMENTS:

Staff Report - Time Extension 2019-01
 Resolution No. 2019-08
 Attachment 1 -Tentative Tract 919
 Attachment 2 - Original PC staff report for 919
 Attachment 3 - City Council Resolution 17-29-R
 Attachment 4 -Tract 919 Final Map Recorded (Unit I)

**CITY OF HANFORD PLANNING COMMISSION
STAFF REPORT**

MEETING DATE: Tuesday, May 14, 2019

PROJECT: **TIME EXTENSION 2019-01**, a request to extend the life of Tentative Tract 919 Unit II for 24 months.

LOCATION: The property is located south of Fargo Avenue, west of Centennial Drive (APN 009-030-154).

PROJECT PLANNER: Gabrielle de Silva, Senior Planner

STAFF RECOMMENDATION

Staff recommends that the Planning Commission:

1. Adopt Resolution No. 2019-08, approving Time Extension No. 2019-01.

RECOMMENDED MOTION

1. I move to adopt Resolution No. 2019-08, approving Time Extension No. 2019-01.

PROJECT PROPOSAL

Time Extension No. 2019-01 is a request by San Joaquin Valley Homes to extend the life of Tentative Tract Map 919 for 24 months, in order to record the second and final phase of Tract 919. If approved, the time extension would extend the expiration of the project until May 16, 2020.

Tentative Tract Map 919 is attached – **Attachment 1**.

BACKGROUND INFORMATION

On May 16, 2017, the City Council approved Tentative Tract Map 919, filed by San Joaquin Valley Homes, subdividing 31.77 acres into 125 residential lots. The project is applicable to the property located south of Fargo Avenue, west of Centennial Drive.

Note: Typically, tentative tract map approvals are granted by the Planning Commission, however, since the project also involved a general plan amendment, rezone, and annexation, the project was forwarded to the City Council.

Figure 1: Land Use




Figure 2: General Plan Designation
Low-Density Residential





Figure 3: Zoning Designation
R-L-5 Low-Density Residential



Tentative Tract 919 is a subdivision of 31.77 acres into 125 single-family, low-density residential lots, in accordance with the General Plan designation for the area, Low-Density Residential. Although Tentative Tract 919 was submitted under the 2002 General Plan and Zoning Ordinance, staff evaluated the map for consistency with both the 2002 General Plan and 2035 General Plan and Zoning Ordinance. The project satisfies all standards required for the 2035 General Plan and R-L-5 Low-Density Residential zoning designation.

A full analysis of Tentative Tract Map 919 appears in the original Planning Commission staff report – **Attachment 2**, for the Commission’s review. The City Council approved Tentative Tract 919 for two years, May 16, 2017 to May 16, 2019 under Resolution 17-29-R – **Attachment 3**.

On April 26, 2019, Unit I of Tract 919 was recorded. A copy of the recorded final map is attached – **Attachment 4**.

PROJECT EVALUATION

Due to the need to record the final phase of Tract 919, the applicant is requesting a 24-month time extension, thus extending the expiration of Tract 919 to May 16, 2020.

In accordance with Section 16.32.090 of the Subdivision Ordinance, “an approved or conditionally approved vesting tentative map shall expire at the end of the same time period, and shall be subject to the same extensions established by the California Government Code (Section 66452.6), as amended for non-vesting tentative maps. The total of all time extensions for vesting tentative maps shall not exceed three years, except when automatically extended, as provided by California Government Code Section 66452.6, as amended.”

Analysis:

The map is consistent with the current General Plan Designation – Low-Density Residential and the applicable zoning designation – R-L-5 Low-Density Residential. The Planning Commission may grant a total time extension of three years. The map has not been extended previously; therefore, the map is eligible for the 24-month requested extension.

No automatic State map extensions are applicable to this project.

The applicant has been diligent in recording the map and recorded Unit I of Tract 919 on April 26, 2019.

ENVIRONMENTAL ASSESSMENT

Mitigated Negative Declaration No. 2016-06 was adopted for the project on May 16, 2017, certifying that the project would not have a significant adverse impact on the environment with the incorporation of mitigation measures.

CONDITIONS OF APPROVAL

All conditions of the original approval, outlined in Resolution No. 17-29-R, shall apply. Additionally, all new conditions of Resolution No. 2019-08 shall apply, including the increase in impact fees to reflect the City’s current fees.

Applicant/Owner

San Joaquin Valley Homes
222 N Garden Street; Suite 100
Visalia, CA 93291

RESOLUTION NO. 2019-08

**A RESOLUTION OF THE PLANNING COMMISSION OF THE CITY OF HANFORD
 APPROVING TIME EXTENSION NO. 2019-01, A REQUEST TO EXTEND THE LIFE OF
 TENTATIVE TRACT 919 FOR 24-MONTHS. THE PROJECT PERTAINS TO PROPERTY
 LOCATED SOUTH OF FARGO AVENUE, WEST OF CENTENNIAL DRIVE (APN 009-030-
 154).**

At a regular meeting of the Planning Commission of the City of Hanford duly called and held on May 14, 2019, by motion of Commissioner _____, seconded by Commissioner _____, and duly carried, the following resolution was adopted:

WHEREAS, Time Extension No. 2019-01, filed by San Joaquin Valley Homes, proposing to extend the life of Tentative Tract 919, for 24 months, has been reviewed by the Planning Commission of the City of Hanford as an advisory agency, in accordance with Title 16 of the Hanford Municipal Code;

WHEREAS, the project pertains to property south of Fargo Avenue, west of Centennial Drive; and

WHEREAS, a time extension was requested by the applicant pursuant to City Council Resolution No. 17-29-R and Section 66463.5(c) of the Subdivision Map Act; and

WHEREAS, in accordance with Section 16.32.090 of the Subdivision Ordinance, a vesting tentative map may be extended for a total time of three years, except when automatically extended, as provided by California Government Code Section 66452.6; and

WHEREAS, findings were made pursuant to Section 66474 of the Subdivision Map Act in City Council Resolution No. 17-29-R; and

THEREFORE, BE IT RESOLVED, that a one-year time extension for Tentative Tract Map 919 be approved, in accordance with the existing conditions in Resolution No. 17-29-R, adopted May 16, 2017, and with the addition of the following conditions:

1. That the new expiration date of Tentative Tract Map 919 be May 16, 2020.
2. That all subdivision improvements shall conform to the City of Hanford Construction Standards, Specifications, Ordinances and Policies in effect on the date of the extension approval and shall be subject to fees currently in effect at time of development.

PASSED AND ADOPTED at a regular meeting of the Planning Commission of the City of Hanford on May 14, 2019 by the following vote:


AYES: Commissioners
 NOES: Commissioners
 ABSTAIN: Commissioners
 ABSENT: Commissioners

STATE OF CALIFORNIA)
 COUNTY OF KINGS) ss
 CITY OF HANFORD)

Attachment: Resolution No. 2019-08 (Time Extension No. 2019-01)

I, **Darlene R. Mata**, Secretary of the Planning Commission of the City of Hanford, do hereby certify the foregoing Resolution was duly passed and adopted by the Planning Commission of the City of Hanford at a regular meeting thereof held on the 14th day of May, 2019.

Darlene R. Mata, Secretary



TENTATIVE SUBDIVISION MAP
COUNTY TRACT NO. 919
CITY OF HANFORD, COUNTY OF KINGS, STATE OF CALIFORNIA

LEGAL DESCRIPTION

PARCEL 1 OF PARCEL MAP RECORDED IN BOOK 20 AT PAGE 2 OF PARCEL MAPS, KINGS COUNTY RECORDS, ALSO BEING A PORTION OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 22, T. 18 S., R. 21 E., M.D.B. & M., IN THE COUNTY OF KINGS, STATE OF CALIFORNIA.

LOT INFORMATION

TOTAL LOTS: 125 LOTS
LOTS PER ACRE: 3.93

MINIMUM LOT SIZE: 6,023 S.F. (LOT 25)
MAXIMUM LOT SIZE: 15,393 S.F. (LOT 48)
AVERAGE LOT SIZE: 7,322.4 S.F.

AREA

TOTAL AREA: 31.77 AC. GR.
STREET DEDICATION
CENT.DR./FARGO AVE.: 2.32 AC.
STREET DEDICATION
INTERIOR STREETS: 8.44 AC.

APPLICANT

SAN JOAQUIN VALLEY HOMES
222 NORTH GARDEN ST., #100
VISALIA, CA 93291
TEL: (559) 732-2660

OWNER

MADRUGA FAMILY
(SEE PRELIMINARY TITLE REPORT FOR DETAILED INFORMATION)


C/O JANICE L. MADRUGA
12581 FARGO AVENUE
HANFORD, CA 93230

GENERAL INFORMATION

EXISTING ZONE	AL-10 (KINGS COUNTY)
PROPOSED ZONE	R-1-6
EXISTING USE	AGRICULTURE
PROPOSED USE	SINGLE FAMILY RESIDENTIAL
SEWER	CITY OF HANFORD, @NORTH END OF CENTENNIAL DRIVE
WATER	CITY OF HANFORD
STORM DRAIN	ON-SITE DRAINAGE BASIN
A.P.N.	009-030-148
ELECTRIC	SCE
GAS	GAS COMPANY
TELEPHONE	SBC

VICINITY MAP

Not to Scale



SAN JOAQUIN VALLEY HOMES
222 NORTH GARDEN ST., #100
VISALIA, CA 93291



TENTATIVE SUBDIVISION MAP
COUNTY TRACT No. 919

CIVIL ENGINEERS
ZUMWALT HANSEN
LAND SURVEYORS
609 N. Irvin St.
Hanford, CA 93230
Office: (559) 582-1056
Fax: (559) 584-4143

DRAWN BY: JRJ
CHECKED BY: Z
INDEXED BY:
DATE: SEE BELOW
JOB NO.: 0762111
SHEET: 1 OF 1

**CITY OF HANFORD PLANNING COMMISSION
STAFF REPORT
Tuesday, March 28, 2017**

PROJECT: **ANNEXATION/REORGANIZATION No. 152 and PREZONE NO. 2016-01:** A request to annex 80.86 acres into the City of Hanford and prezone the annexed area as “R-1-6” Low-Density Residential, in accordance with the General Plan. The project involves simultaneous detachment of the property from the Kings River Conservation District and the Excelsior-Kings River Conservation District.

TENTATIVE TRACT NO. 918: A request to subdivide 47.51 acres into 130 single-family, low-density residential lots, a two-acre park, and a 5.02-acre basin.

TENTATIVE TRACT NO. 919: A request to subdivide 31.77 acres into 125 single-family, low-density residential lots.

TENTATIVE PARCEL MAP NO. 2016-02: A request to divide a 47.51-acre parcel into two parcels (Parcel A: 27.48 acres; Parcel B: 20.03 acres) in an area proposed to be prezoned “R-1-6” Low-Density Residential.

MITIGATED NEGATIVE DECLARATION NO. 2016-06: A request to certify that the project will not have a significant effect on the environment with the incorporation of mitigation measures.

LOCATION: The project is located south of Fargo Avenue, between 12th Avenue and 13th Avenue, west of the future Centennial Drive (APN 009-030-041, 009-030-148, and 009-030-149).

PLANNER: Gabrielle de Silva, Associate Planner

STAFF RECOMMENDATION

Staff recommends that the Planning Commission:

1. Recommend adoption of Mitigated Negative Declaration No. 2016-06 for the project to the City Council.
2. Adopt Resolution 2017-05 recommending approval of Prezone No. 2016-01 to the City Council.
3. Find that the proposed Annexation No. 152 is consistent with the Hanford General Plan Policies LU 24.1 and LU 25.2, based on the following findings and forward Annexation/Reorganization No. 152 to the City Council with a recommendation that an application be made to the Local Agency Formation Commission (LAFCO) of Kings County.

- a. The annexation supports Kings County General Plan objectives and policies which require new residential development to be contiguous to urban development and to annex to the City.
 - b. The proposed annexation site is within the City's Sphere of Influence in the General Plan and planned for inclusion into the City limits.
 - c. The annexation will ensure that any future development within the project area will be developed to City standards.
 - d. The project's rezoning is consistent with the General Plan designation of Low-Density Residential.
- 4. Adopt Resolution No. 2017-06, recommending approval of Tentative Tract Map 918 to the City Council.
 - 5. Adopt Resolution No. 2017-07, recommending approval of Tentative Tract Map 919 to the City Council.
 - 6. Adopt Resolution No. 2017-08, recommending approval of Tentative Parcel Map No. 2016-02 to the City Council.

RECOMMENDED MOTION

- 1. I move that the Planning Commission recommend certification of Mitigated Negative Declaration No. 2016-06 for the project to the City Council.
- 2. I move to adopt Resolution No. 2017-05, recommending approval of Prezone No. 2016-01 to the City Council.
- 3. I move to find Annexation/Reorganization No. 152 consistent with the Hanford General Plan Policies LU 24.1 and LU 25.2 and forward Annexation/Reorganization No. 152 to the City Council with a recommendation that an application be made to the Local Agency Formation Commission (LAFCO) of Kings County.
- 4. I move to adopt Resolution No. 2017-06, recommending approval of Tentative Tract 918 to the City Council.
- 5. I move to adopt Resolution No. 2017-07, recommending approval of Tentative Tract 919 to the City Council.
- 6. I move to adopt Resolution No. 2017-08, recommending approval of Tentative Parcel Map No. 2016-02 to the City Council.

PROJECT DESCRIPTION

Annexation/Reorganization 152 and Prezone No. 2016-01:

The project is a request to annex 80.86 acres and prezone the area "R-1-6" Low Density Residential, in accordance with the General Plan. The project involves simultaneous detachment

of the property from the Kings River Conservation District and the Excelsior-Kings River Conservation District.

See proposed annexation, attached as **Exhibit A**.

Tentative Tract 918:

The project is a request to subdivide 47.51 acres into 130 single-family, low-density residential lots, a two-acre park, and a 5.02-acre basin, in accordance with the General Plan designation for the area, Low-Density Residential.

See proposed subdivision, attached as **Exhibit B**.

Tentative Tract 919:

The project is a request to subdivide 31.77 acres into 125 single-family, low-density residential lots, in accordance with the General Plan designation for the area, Low-Density Residential.

See proposed subdivision, attached as **Exhibit C**.

Tentative Parcel Map No. 2016-02:

The project is a request to divide a 47.51-acre parcel into two parcels (Parcel A: 27.48 acres; Parcel B: 20.03 acres) in an area proposed to be rezoned "R-1-6" Low-Density Residential.

See proposed parcel split, attached as **Exhibit D**.

Project Location

The projects are applicable to the property located south of Fargo Avenue, between 12th Avenue and 13th Avenue, west of the future Centennial Drive (APN 009-030-041, 009-030-148, and 009-030-149).

Existing Land Use

The majority of the project area is comprised of vacant land and land used for agricultural purposes. There is a large lot, single-family residence located at 12581 Fargo Avenue, APN 009-030-149.

Figure 1: Land Use
(Property outlined in red)





Figure 2: General Plan Designation
Low- Density Residential and Public Facility
(Property outlined in red)



Attachment: Attachment 2 - Original PC staff report for 919 (Time Extension No. 2019-01)

BACKGROUND INFORMATION

General Plan Designation and County Zoning:

The General Plan designates the property as Low-Density, with six acres of Public Facility. The rezoning of the property is proposed as “R-1-6” Low-Density Residential for the entire 80.86 acres; however, the six acres of public facility will be accommodated through the design of Tentative Tract 918, which allocates two acres for park space and 5.02 acres for a storm drainage basin for the residential development, which will also be utilized by Tentative Tract 919.

Adjacent Land Use and Zoning:

	Land Use	Zoning	General Designation	Plan
North:	Vacant	County AL-10	Agriculture	
South:	Vacant (Future Residential)	R-1-6	Low-Density Residential	
East:	Vacant (Future Residential)	R-1-6	Low-Density Residential	
West:	Agriculture and Vacant	County AL-10	Low-Density Residential	

Utilities/Public Services:

The private utility companies have been contacted for comments concerning this project and one comment has been received and is addressed under pre-consultation. City, County and State agencies have also reviewed the proposal. Services such as water, storm drain, sewer, fire and police can be provided to the annexation territory in accordance with the General Plan and Sewer Master Plan. A Plan for Services has been prepared for the annexation and is attached as **Exhibit E**.

Land Owners & Values:

APN	OWNER	REGISTERED VOTERS	ACRES	LAND VALUE
009-030-041	Miya	0	47.51	\$ 400,722.00
009-030-148	Madrugá	0	31.77	\$ 535,807.00
009-030-149	Madrugá	1	1.58	\$ 205,214.00

Comments:

An area is considered uninhabited if there are less than 12 registered voters within the annexation area. With one registered voter, this is considered an uninhabited annexation. If there are property owners who do not consent to the annexation, there is an opportunity for them to protest the property being included in the annexation. They can do this by submitting a written protest prior to the LAFCO hearing to state their opposition. However, this is a 100% consent annexation; therefore, LAFCO will not hold a protest hearing. LAFCO is the governing body, with the ultimate authority to make the determination of whether a property will be annexed.

Since the annexation involves a simultaneous detachment of the property from the Kings River Conservation District and Excelsior-Kings River Conservation District, the proposal is considered a reorganization, rather than an annexation by LAFCO.

PROJECT EVALUATION

Annexation/Reorganization No. 152

The project is a request to annex 80.86 acres and involves simultaneous detachment of the property from the Kings River Conservation District and the Excelsior-Kings River Conservation District.

See proposed annexation, attached as **Exhibit A**.

The Hanford Planning Commission is charged with reviewing proposed annexation and making a finding of consistency with the Hanford General Plan to forward to the City Council. The Planning Commission will need to find that Annexation 152 is consistent with the Hanford General Plan Policies LU 24.1 and LU 25.2.

Policy LU 24.1

The City supports Kings County General Plan objectives and policies which direct new industrial and commercial development to cities and require new residential development to be contiguous to urban development and to annex to the City, and to maintain limited agriculture land use designations within the City's General Plan Planning Area boundary.

Analysis:

1. The annexation area is proposed for future residential development and is contiguous to urban development.
2. The annexation does not propose agricultural land use designations within the City limits.

Policy LU 25.2

All new development shall be restricted to the interior boundaries of the Planning Area Boundary. Where the Planning Area Boundary is a street or road right-of-way (existing or future), no development will be allowed to cross that street or road to the opposite side of the Planning Area Boundary.

Analysis:

1. All future residential development is planned to be developed within the Planning Area Boundary.

Favorable and unfavorable factors for annexation have been adopted by LAFCO. The existence of favorable or unfavorable factors should not decide approval or denial; however, a substantial number of favorable or unfavorable factors may determine approval or denial of the proposal.

Favorable Factors for Annexation


1. The proposed area is close to urban development and municipal-type services and would enhance its potential for full development.
2. The proposed annexation conforms to the adopted General Plan.
3. The proposed area is consistent with the sphere of influence.
4. The proposed annexation comes with 100% consent of all landowners.

Prezone No. 2016-01

As required for all annexations, the property that is proposed for annexation shall be prezoned. Prezone No. 2016-01 proposes to designate the entire 80.86 acres of Annexation 152 for “R-1-6” Low-Density Residential. Although the General Plan designates the six acres of the southeast corner of the area to be annexed as Public Facility, the prezoning of the property is proposed as “R-1-6” Low-Density Residential. However, the six acres of public facility will be accommodated through the design of Tentative Tract 918, which allocates two acres for park space and 5.02 acres for a storm drainage basin for the residential development.

The property will be prezoned as shown in Figure 3, below.

Figure 3: Prezoning
 “R-1-6” Low-Density Residential
 (property outlined in red)



Tentative Tract Map 918

The project is a request to subdivide 47.51 acres into 130 single-family, low-density residential lots, a two-acre park, and a 5.02-acre basin, in accordance with the General Plan designation for the area, Low-Density Residential.

See proposed subdivision, attached as **Exhibit B**.

Project Design:

Project applicable to: **APN 009-030-041** (the southern-most parcel)

Total Area: **47.51 acres**

Number of Lots: **130 single-family residences; one two-acre park; one 5.02-acre storm water drainage basin**

Number of Dwelling Units: **130 single-family residences**

Units per acre: **2.736 dwelling units/acre**

Potential population increase: **3.11 persons per household x 130 households = 404 persons**

Lot Sizes

Smallest	Largest	Average	Required
8,399 sq. ft.	22,450 sq. ft.	9,908 sq. ft.	6,000 sq. ft.

All proposed lots meet or exceed minimum depth, width, and area requirements of the “R-1-6” Low-Density Residential Zone District.

Streets/Circulation

Street improvements will include the installation of concrete curb and gutter, sidewalk, landscaping, street lights, and street striping. All improvements will be installed within public street right-of-way or utility easements, in accordance with the requirements of Chapter 16.24 “Improvements”, of the Hanford Municipal Code, Public Works Standards and Specifications, and the resolution pertaining to the subdivision.

The project will be served by the future extension of Centennial Drive and Devon Street. Both are major collector streets and will be developed along the development frontages of the subdivision, in conformance with City Standard ST-17 and ST-23.

All other streets within the subdivision will be developed to residential street standard ST-32.

Easements and Dedications

Easements will be designated on the final subdivision map, as required by the utility companies, and where needed for providing service to streetlights and landscape improvements, as designated by the Public Works Department.

All proposed streets, street extensions, opposite travel lanes on boundary streets, and offsite pavement transitions with right-of-way, as shown on the tentative subdivision map, will be dedicated to the City as public rights-of-way; and any alteration of existing utilities will be the responsibility of the developer.

The proposed drainage basin, as shown on the tentative subdivision map, will be dedicated to the City for drainage purposes, concurrent with the recording of the subdivision final map for the first phase of the development.

The proposed neighborhood park, located as shown on the tentative subdivision map, will be dedicated to the City or otherwise conveyed to the City, concurrent with the recording of the subdivision final map for the first phase of the development.

Backup Parkway Improvements

A minimum six-foot-high decorative masonry block wall with continuous reinforced concrete footings will be constructed along the development frontage of Centennial Drive and Devon Street.

A 4 ½-foot-wide detached sidewalk along the development frontages of Centennial Drive and Devon Street will be constructed.

Landscape and irrigation system improvements will be installed along the development frontages of Centennial Drive, Devon Street, and the park.

Sewer Improvements

The developer's engineer will provide a sanitary sewer master plan, complete with calculations for the entire subdivision, for City Public Works Department review and approval prior to recording a subdivision final map. Provisions will be made to provide service for future areas of development located adjacent to the subdivision.

Storm Drainage Improvements

The developer's engineer will provide a storm drainage master plan, complete with calculations for the entire subdivision, for City Public Works Department review and approval prior to recording a subdivision final map. Provisions shall be made for service to future areas of development located adjacent to the subdivision.

All drainage from the proposed development will be retained in a retention drainage basin, located as shown on the tentative subdivision map.

Water System

The developer's engineer will provide a water system master plan, complete with calculations for the entire subdivision, for City review and approval prior to recording a subdivision final map. Provisions will be made for service to future areas of development located adjacent to the subdivision.

Public Services

City services, including fire, police, and general services (planning, building, and recreation) can adequately be provided for the increase in population from this subdivision, as noted in the initial study conducted for the project.

Tentative Tract Map 919

The project is a request to subdivide 31.77 acres into 125 single-family, low-density residential lots, in accordance with the General Plan designation for the area, Low-Density Residential.

See proposed subdivision, attached as **Exhibit C**.

Project Design:

Project applicable to: **APN 009-030-048** (north of Tentative Tract 918)

Total Area: **31.77 acres**

Number of Dwelling Units: **125 single-family residences**

Units per acre: **3.93 dwelling units/acre**

Potential population increase: **3.11 persons per household x 125 households = 389 persons**

Lot Sizes

Smallest	Largest	Average	Required
6,023 sq. ft.	15,393 sq. ft.	7,322 sq. ft.	6,000 sq. ft.

All proposed lots meet or exceed minimum depth, width, and area requirements of the “R-1-6” Low-Density Residential Zone District.

Streets/Circulation

Street improvements will include the installation of concrete curb and gutter, sidewalk, landscaping, street lights, and street striping. All improvements will be installed within public street right-of-way or utility easements, in accordance with the requirements of Chapter 16.24 “Improvements”, of the Hanford Municipal Code, Public Works Standards and Specifications, and the resolution pertaining to the subdivision.

The project will be served by the future extension of Centennial Drive and Fargo Avenue. Centennial Drive is a major collector street and will be developed along the development frontage of the subdivision, in conformance with City Standard ST-17 and ST-23. Fargo Avenue is a major arterial street and will be developed along the development frontage of the subdivision, in conformance with City Standards ST-17 and ST-18.

All other streets within the subdivision will be developed to residential street standard ST-32.

Easements and Dedications

Easements will be designated on the final subdivision map, as required by the utility companies, and where needed for providing service to streetlights and landscape improvements, as designated by the Public Works Department.

All proposed streets, street extensions, opposite travel lanes on boundary streets, and offsite pavement transitions with right-of-way, as shown on the tentative subdivision map, will be dedicated to the City as public rights-of-way; and any alteration of existing utilities will be the responsibility of the developer.

Backup Parkway Improvements

A minimum six-foot-high decorative masonry block wall with continuous reinforced concrete footings will be constructed along the development frontage of Centennial Drive and Fargo Avenue.

A 4 ½-foot-wide detached sidewalk along the development frontages of Centennial Drive and Fargo Avenue will be constructed.

Landscape and irrigation system improvements will be installed along the development frontages of Centennial Drive and Fargo Avenue.

Sewer Improvements

The developer's engineer will provide a sanitary sewer master plan, complete with calculations for the entire subdivision, for City Public Works Department review and approval prior to recording a subdivision final map. Provisions will be made to provide service for future areas of development located adjacent to the subdivision.

Storm Drainage Improvements

The developer's engineer will provide a storm drainage master plan, complete with calculations for the entire subdivision, for City Public Works Department review and approval prior to recording a subdivision final map. Provisions shall be made for service to future areas of development located adjacent to the subdivision.

All drainage from the proposed development will be retained in a retention drainage basin, located as shown on the tentative subdivision map for Tentative Tract 918.

Water System

The developer's engineer will provide a water system master plan, complete with calculations for the entire subdivision, for City review and approval prior to recording a subdivision final map. Provisions will be made for service to future areas of development located adjacent to the subdivision.

Public Services

City services, including fire, police, and general services (planning, building, and recreation) can adequately be provided for the increase in population from this subdivision, as noted in the initial study conducted for the project.

Tentative Parcel Map No. 2016-02

The project is a request to divide the parcel located at APN 009-030-041, a 47.51-acre parcel, into two parcels (Parcel A: 27.48 acres; Parcel B: 20.03 acres) in an area proposed to be rezoned "R-1-6" Low-Density Residential.

See proposed parcel split, attached as **Exhibit D**.

Project Design:

	<u>Entire Site</u>	<u>Parcel A</u>	<u>Parcel B</u>
Area:	47.51 acres	27.48 acres	20.03 acres
Width:	1,294.68 ft. Minimum width; 1,336.22 ft. Maximum width	524.45 ft. Minimum width; 1,336.22 ft. Maximum width	1,294.68 ft. Minimum width; 1,295.44 ft. Maximum width;
Depth:	1,322.63 ft. Minimum depth; 2,643.05 ft. Maximum depth	662.52 ft. Minimum depth; 1,200.05 ft. Maximum depth	659 ft. Minimum depth; 679 ft. Maximum depth
Sidewalk:	Non-existent along Centennial Drive or Devon Street	Non-existent along Centennial Drive or Devon Street	Non-existent along Centennial Drive or Devon Street
Existing Use:	Walnut Orchard	Walnut Orchard	Walnut Orchard
Proposed Use:	Split into two parcels	Phase I of Tentative Tract 918 - Single Family Residential lots (1-62)	Phase II of Tentative Tract 918 -Single Family Residential lots (63-130)

The tentative parcel map will physically divide Tentative Tract 918 into two phases. Parcel A corresponds to Phase I of Tentative Tract 918; Parcel B corresponds to Phase II of Tentative Tract 918.

Parcel A

Parcel A corresponds to Phase I of Tentative Tract 918. Phase I includes residential lots one through 62, the two-acre park, and the 5.02-acre drainage basin.

Phase II

Phase II corresponds to Phase II of Tentative Tract 918. Phase II includes residential lots 63 through 130.

Both of the proposed lots will meet the minimum parcel size required of the “R-1-6” Low-Density Residential Zone District, which is a minimum of 6,000 square feet per lot. Additionally, the parcels will meet the minimum requirements for the width and street-frontage of the “R-1-6” Low-Density Residential Zone District, which is 60 feet. The proposed parcels also meet the depth requirement for the “R-1-6” Low-Density Residential Zone District, which is 95 feet. Under Tentative Tract 918, Parcel A and B will be further divided into a residential subdivision.

FINDINGS FOR APPROVAL

Annexation/Reorganization No. 152:

The annexation is consistent with Policies LU 24.1 and LU 25.2 of the General Plan. This finding of consistency can be made based on the following:

1. The annexation area is proposed for future residential development and is contiguous to urban development.
2. The annexation does not propose agricultural land use designations within the City limits.
3. All future residential development is planned to be developed within the Planning Area Boundary.
4. Prezone No. 2016-01 proposes to designate 80.86 acres as “R-1-6” Low-Density Residential, in accordance with the General Plan.

Prezone No. 2016-01:

Pursuant to Section 17.66.060 and Section 17.66.070 of the Hanford Municipal Code, the following findings can be made by the Planning Commission:

1. That the public hearing for the prezone application was properly noticed, in accordance with state law and the Hanford Municipal Code.
2. The prezone of the annexation area is compatible, integrated, and internally consistent with the existing policies of the Hanford General Plan.
3. That the proposed prezone is consistent with the objectives and policies of Section 17.02.020 of the Municipal Code, as follows:
 - a) That the prezone guides the physical development of the City in such a manner as to achieve progressively the general arrangement of the land uses described and depicted in the General Plan.
 - b) That the proposed project fosters a wholesome, serviceable, and attractive living environment, the beneficial development of areas, which exhibit conflicting patterns of use, and the stability of existing land uses, which conform with the objectives, policies, principles, and standards of the General Plan.
 - c) That the proposed project does not result in excessive population densities and the overcrowding of land with structures.
 - d) That the proposed project results in a safe, effective, traffic-circulation system.
 - e) That the proposed project will protect and promote appropriately located residential activities in order to preserve and strengthen the City's economic base.

- f) That the proposed project will protect and enhance real property values and the City's natural assets.
 - g) That the proposed project will ensure unimpeded development of such new urban expansion that is logical, desirable, and in conformance with the objectives and policies of the General Plan.
 - h) That the proposed project will provide and protect open space, in accordance with the policies of the Open Space Element of the General Plan.
4. That an initial study was prepared for the project, consistent with the California Environmental Quality Act (CEQA), which disclosed that environmental impacts are determined to be less than significant with mitigation measures and that Mitigated Negative Declaration No. 2016-06 is recommended for adoption.

Tentative Tract Map 918:

Pursuant to Section 16.04.010 of the Hanford Subdivision Ordinance, Section 66474 of the Subdivision Map Act, and Hanford's Zoning Ordinance, the following findings can be made by the Planning Commission:

1. Consistency Finding:

ANALYSIS: That a consistency finding can be made, because the proposed subdivision map is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District, which is 6,000 square feet. The minimum lot size within the subdivision is 8,399 sq. ft. The average lot size is 9,908 sq. ft.

2. Design Finding:

ANALYSIS: That the design or improvement of the subdivision is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District, which is 6,000 square feet. . The minimum lot size within the subdivision is 8,399 sq. ft. The average lot size is 9,908 sq. ft. All improvements are to be developed in accordance with Public Works Construction Standards.

3. Type of Development Finding:

ANALYSIS: That the site is physically suitable for the type of development proposed under Tentative Tract 918. The lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District. All parcels have adequate street frontage on a public street and meet the minimum depth and width required for the district.

4. Density Finding:

ANALYSIS: That a density finding can be made, because the site is physically suitable for the proposed density of development. The General Plan prescribes a density range

between two and nine units per acre. The project has a density of 2.736 dwelling units per acre.

5. Environmental Finding:

ANALYSIS: That initial study was conducted; and, on the basis on the initial study, the Community Development Department has determined that the project described above would not have significant adverse impacts on the environment, with the incorporation of mitigation measures. Mitigated Negative Declaration No. 2016-06 has been prepared for the project. The initial study, Mitigated Negative Declaration No. 2016-06, and mitigation measures required of development are attached as **Exhibit F**.

6. Public Health Finding:

ANALYSIS: That the design of the subdivision and type of improvements are not likely to cause serious health problems. The City of Hanford Building Division is responsible for ensuring that future construction of the site follows adopted building codes, thus reducing exposures to accidents to the general public. Consultation was sent for Tentative Tract 918 to interested agencies, including the County Health Department, Public Works Department, Fire Department, and Building Division. Any improvements or mitigations required for public health and safety were applied to the proposal and required in the conditions of approval.

7. Improvements and Access Findings:

ANALYSIS: That the design of the subdivision and type of improvements will not conflict with easements acquired by the public at large for access through or use of the property within the proposed subdivision. The existing access easements shown on Tentative Parcel Map 918 will be quit claimed to APN 009-030-002.

Tentative Tract Map 919

Pursuant to Section 16.04.010 of the Hanford Subdivision Ordinance, Section 66474 of the Subdivision Map Act, and Hanford's Zoning Ordinance, the following findings can be made by the Planning Commission:

1. Consistency Finding:

ANALYSIS: That a consistency finding can be made, because the proposed subdivision map is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District, which is 6,000 square feet. The minimum lot size within the subdivision is 6,023 feet. The average lot size is 7,322 sq. ft.

2. Design Finding:

ANALYSIS: That the design or improvement of the subdivision is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District, which is 6,000 square feet. The minimum lot size within the

subdivision is 6,023 sq. ft. The average lot size is 7,322 sq. ft. All improvements are to be developed in accordance with Public Works Construction Standards.

3. Type of Development Finding:

ANALYSIS: That the site is physically suitable for the type of development proposed under Tentative Tract 919. The lots proposed meet the minimum lot size of the "R-1-6" Low-Density Residential Zone District. All parcels have adequate street frontage on a public street and meet the minimum depth and width required for the district.

4. Density Finding:

ANALYSIS: That a density finding can be made, because the site is physically suitable for the proposed density of development. The General Plan prescribes a density range between two and nine units per acre. The project has a density of 3.93 dwelling units per acre.

5. Environmental Finding:

ANALYSIS: That initial study was conducted; and, on the basis on the initial study, the Community Development Department has determined that the project described above would not have significant adverse impacts on the environment, with the incorporation of mitigation measures. Mitigated Negative Declaration No. 2016-06 has been prepared for the project. The initial study, Mitigated Negative Declaration No. 2016-06, and mitigation measures required of development are attached as **Exhibit F**.

6. Public Health Finding:

ANALYSIS: That the design of the subdivision and type of improvements are not likely to cause serious health problems. The City of Hanford Building Division is responsible for ensuring that future construction of the site follows adopted building codes, thus reducing exposures to accidents to the general public. Consultation was sent for Tentative Tract 919 to interested agencies, including the County Health Department, Public Works Department, Fire Department, and Building Division. Any improvements or mitigations required for public health and safety were applied to the proposal and required in the conditions of approval.

7. Improvements and Access Findings:

ANALYSIS: That the design of the subdivision and type of improvements will not conflict with easements acquired by the public at large for access through or use of the property within the proposed subdivision. The existing access easements shown on Tentative Parcel Map 919 will be quit claimed to APN 009-030-002.

Tentative Parcel Map No. 2016-02

Pursuant to Section 16.04.010 of the Subdivision Ordinance Code and Section 66474 of the Subdivision Map Act, the Planning Commission is required to make the following findings:

1. Consistency Finding:

ANALYSIS: That the proposed map is consistent with the applicable General Plan designation of Low-Density Residential. The proposed lots meet the minimum parcel size required of the "R-1-6" Low-Density Residential Zone District of 6,000 square feet. Additionally, the parcels meet the minimum requirements for the width and street-frontage of the "R-1-6" Low-Density Residential Zone District, which is 60 feet. The proposed parcels also meet the depth requirement for the "R-1-6" Low-Density Residential Zone District, which is 95 feet. Under Tentative Tract 918, Parcel A and B will be further divided into a residential subdivision.

2. Design Finding:

ANALYSIS: That the proposed lots meet the minimum parcel size required of the "R-1-6" Low-Density Residential Zone District of 6,000 square feet. Additionally, the parcels meet the minimum requirements for the width and street-frontage of the "R-1-6" Low-Density Residential Zone District, which is 60 feet. The proposed parcels also meet the depth requirement for the "R-1-6" Low-Density Residential Zone District, which is 95 feet. Both lots have a buildable lot configuration. Under Tentative Tract 918, Parcels A and B will be further divided into a residential subdivision.

3. Type of Development Finding:

ANALYSIS: That the proposed site is located on vacant flat land and is not located in a flood zone. Parcels will be within the city limits as part of the annexation and city water and services can be extended to the site. Under Tentative Tract 918, Parcels A and B will be further divided into a residential subdivision. Staff evaluated Tentative Tract 918 and determined the project to be in conformance with the requirements of the Hanford Municipal Code.

4. Density Finding:

ANALYSIS: That the parcels are of adequate size to support the guidelines of the General Plan and Zoning Ordinance. Under Tentative Tract 918, Parcels A and B will be further divided into a residential subdivision. A density finding was able to be supported for Tentative Tract 918, because the project has a gross density of 2.736 dwelling units per acre, which is within the allowable range of the "R-1-6" Low-Density Residential Zone District, between two and nine units per acre.

5. Environmental Finding:

ANALYSIS: That an initial study was conducted; and, on the basis on the initial study, the Community Development Department has determined that the project described above would not have significant adverse impacts on the environment, with the incorporation of mitigation measures. Mitigated Negative Declaration No. 2016-06 has been prepared for the project. The initial study, Mitigated Negative Declaration No. 2016-06, and mitigation measures required of development are attached as **Exhibit F**.

6. Public Health Finding:

ANALYSIS: That this application has been reviewed by County departments, utility companies, City Fire Department, City Building Department, and other involved departments. Any improvements or mitigations required for public health and safety were

applied to the proposal and required in the conditions of approval. The City of Hanford Building Division is responsible for ensuring that future construction of the site follows adopted building codes, thus reducing exposures to accidents to the general public.

7. Improvements and Access Findings:

ANALYSIS: The proposed parcels will have street frontage along public streets, Centennial Drive and Devon Street. Any off-site improvements such as curbs, gutters, sidewalks, drive approaches, and transitional paving, when installed by the developer, will be inspected and/or verified to ensure the design, material, and installation of said improvements meet or exceed standards adopted by the City of Hanford. The design of the subdivision and type of improvements will not conflict with easements acquired by the public at large for access through or use of the property within the proposed subdivision. The existing access easements shown on Tentative Parcel Map 918 and 919 will be quit claimed to APN 009-030-002.

PRE-CONSULTATION

In accordance with Section 15603(g) of the California Environmental Quality Act (CEQA) Guidelines, the project proposal was forwarded to the responsible and interested agencies for early consultation. Comments were received from the following agencies:

1. Southern California Gas Company
2. San Joaquin Valley Air Pollution Control District
3. Department of Public Health, Division of Environmental Health Services
4. Hanford Joint Union High School District

Responses to comments are addressed within the initial study and are as follows:

Southern California Gas Company

During pre-consultation, David Kemp, of Southern California Gas Company, requested that the City require a 10 ft. utility easement to be dedicated for the tentative tract. After discussion with Public Works, Southern California Gas Company agreed to the City's normal standard requirement of a six-foot utility easement.

San Joaquin Valley Air Pollution Control District

A pre-consultation response was received from the San Joaquin Valley Air Pollution Control District (SJVAPCD) determining the following:

1. Based on information provided to the District, project-specific emissions of criteria pollutants are not expected to exceed District significant thresholds of 10 tons/year NOX, 10 tons/year ROG, and 15 tons/year PM10. Therefore, the District concludes that project-specific criteria pollutant emissions would have no significant adverse impact on air quality.
2. Based on information provided to the District, at full build-out the proposed project would be equal to or greater than 50 residential dwelling units. Therefore, the District concludes that the proposed project would be subject to District Rule 9510 (indirect source review). District Rule 9510 is intended to mitigate a project's impact on air quality through project

design elements or by payment of applicable off-site mitigation fees. Any applicant subject to District Rule 9510 is required to submit an Air Impact Assessment (AIA) application to the District no later than applying for final discretionary approval. If approval of the subject project constitutes the last discretionary approval by your agency, the District recommends that demonstration of compliance with District Rule 9510 be made a condition of project approval. Information can be found online at: <http://www.valleyair.org/ISR/ISRHome.htm>.

3. The proposed project may be subject to District Rules and Regulations, including Regulation VIII (Fugitive PM10 Provisions), Rule 4102 (Nuisance), Rule 4601 (Architectural Coatings), and Rule 4641 (cutback, Slow Cure, and Emulsified Asphalt, Paving and Maintenance Operations). In the event an existing building will be renovated, partially demolished or renovated, the project may be subject to District Rule 4002 (National Emission Standards for Hazardous Air Pollutants). The above list of rules is neither exhaustive nor exclusive. To identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559) 230-5888. Current District rules can be found online at: www.valleyair.org/rules/1ruleslist.htm.
4. The District recommends that a copy of the District's comments be provided to the project proponent.

In response to the comments received from the SJVAPCD, mitigations are required to be implemented for the project, overall, including the following:

1. That the project is subject to the San Joaquin Valley Unified Air Pollution Control District's Indirect Source Review Rule 9510. An application must be filed with the District immediately upon approval of the project. Additionally, in order to identify other District rules or regulations that apply to this project, or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559)230-5888.
2. The applicant will be required to obtain permits demonstrating compliance with Rule 9510, or payment of mitigation fees to the SJVAPCD prior to issuance of a building permit. The project may also be subject to Regulation VII, Rule 4641, and Rule 4692 to further reduce air quality impacts. Although emissions resulting from the project exceed the thresholds of significance for PM10, the City of Hanford adopted a Statement of Overriding Considerations for Air Quality as part of the certification of the EIR prepared for the 2002 General Plan, which will be restated in the approval of the negative declaration. Additionally, in order to identify other District rules or regulations that apply to this project, or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559) 230-5888.

Kings County Environmental Health Department

In response to the letter received from Kings County Environmental Health Department, the following has been added as a condition of approval and mitigation measure:

“Valley Fever: As per the Kings County Public Health Officer, *Coccidioides immitis*, the fungus that causes valley fever, a serious and potentially long-term respiratory illness, is endemic in the soils of Kings County. Construction activities that disturb soils containing the spores of the fungus can put workers and the nearby public at risk. Effective dust control must be maintained on the job site at all times, in order to reduce the risk of valley fever to workers and nearby residents. More information regarding the prevention of work-related valley fever is available at www.cdph.ca.gov/programs/hesis/Documents/CocciFact.pdf and <http://www.cdph.ca.gov/programs/ohb/Documents/OccCocci.pdf>. Contact the San Joaquin Valley Air Pollution Control District for more information on dust control techniques.”

Hanford Joint Union High School District (HJUHSD)

During pre-consultation, Renee Creech, of the HJUHSD, requested that the City consider traffic signals for the project. The Public Works Department has analyzed the project and conditioned it according to their standards. The Public Works Department has not required a traffic signal to be installed for the project.

CONSULTATION

In accordance with Section 15073 of the California Environmental Quality Act Guidelines, a notice of intent to adopt a mitigated negative declaration was sent to the concerned agencies on November 18, 2016. Comments were received from the following agencies:

Responses to comments are addressed within the initial study and are as follows:

1. LAFCO of Kings County
2. Kings County Public Works
3. Tachi Yokut Tribe

Local Agency Formation Commission of Kings County

LAFCO requested that the environmental document prepared address the impacts and any necessary mitigation, including but not limited to, the annexation process. Specifically, LAFCO requested impacts to agricultural lands be analyzed in the environmental document. Impacts to agricultural lands were deemed to be less than significant with mitigation incorporation. The project will convert prime agricultural land and farmland of statewide importance to a non-agricultural use; however, impacts have been analyzed in the General Plan EIR (2002), for which a Statement of Overriding Considerations was certified. A condition of approval for the development will be that a right-to-farm provision be recorded with the recording of the final subdivision map, to insure that future residents of the homes in the project are aware of the adjacent agricultural uses and their right to continue to operate.

Kings County Public Works

During consultation, the Kings County Public Works Department recommended that at the time Centennial Drive connects to Fargo Avenue, a left-turn pocket be constructed for west bound Fargo Avenue traffic. The City's Public Works Department has evaluated the request and has conditioned Tentative Tract 919, accordingly.

Tachi Yokut Tribe

Under SB 18 and AB 52, the Tachi Yokut Tribe requested formal notification of all projects requiring an environmental review under the California Environmental Quality Act (CEQA). Meaningful consultation was initiated with the Tachi Yokut Tribe through a meeting on January 10, 2017. As a result of the meeting, the following mitigation measures have been requested to reduce the impact of development on culturally sensitive resources:

Mitigation Measure Cultural Resources 1: The site has not been identified as containing areas of human remains. Project conditions of approval will include a requirement that in the case that any human remains are discovered at any time, that construction will cease and the City is notified as well as the County Coroner pursuant to California Health and Safety Code 7050.5 and Public Resources Code 5097.98.

Mitigation Measure Cultural Resources 2: That a Burial Treatment Plan be entered to by the applicant/property owner prior to any earth disturbing activities.

Mitigation Measure Cultural Resources 3: (Project-Specific) That the Tachi Tribe have a Native American monitor on-site during tree removal and/or other ground disturbing activities; including, but not limited to, grading, trenching, etc. Monitoring to continue until released by the Tachi Tribal Cultural Department.

Mitigation Measure Cultural Resources 4: (Project-Specific) That a cultural presentation be given to the developer and all contractors and sub-contractors prior to any ground disturbing activities.

RECIRCULATION

In accordance with Section 15073.5 of the California Environmental Quality Act (CEQA) Guidelines, Recirculation of a Negative Declaration Prior to Approval (a), a lead agency is required to recirculate a negative declaration when the document must be substantially revised after public notice of its availability has previously been given pursuant to Section 15702, but prior to its adoption. (b) A “substantial revision” of the negative declaration shall mean: (1) A new, avoidable significant effect is identified and mitigation measures or project revisions must be added in order to reduce the effect to insignificance. Due to new, avoidable significant effects to Cultural Resources, identified by the Tachi Yokut Tribe, as well as mitigation measures added to the project, re-circulation of the mitigated negative declaration was required. Mitigated Negative Declaration No. 2016-06 was noticed for a period of 20 days [Comment period March 1, 2017 – March 21, 2017] in accordance with CEQA Guidelines. Comments were received from the following agencies:

1. Hanford Joint Union High School District – **Exhibit G**
2. Kings County Area Public Transit Agency – **Exhibit H**

Hanford Joint Union High School District (HJUHSD) – attached as Exhibit G

During consultation, Renee Creech, of the HJUHSD, requested that the City consider traffic impacts at 13th Avenue and Grangeville Boulevard and 13th and Fargo Avenue. Staff informed her of the traffic signal planned for 13th Avenue and Grangeville, which will alleviate traffic impacts at that intersection. The Public Works Department determined traffic impacts would be

addressed when development reaches the intersection of 13th Avenue and Fargo Avenue. This project will not bring development to that boundary.

Kings County Area Public Transit Agency (KART) – attached as Exhibit H

During consultation, Mark Pedreiro, of KART, requested the City require the applicant provide a 10' x 12' concrete pad for a proposed bus stop and shelter to be located on Centennial Drive, north of W. Dahli Way, behind Lot 40. The comment has been added to the resolution for Tentative Tract 919, as a condition of approval.

PUBLIC COMMENTS

Noticing of the project was published in the newspaper on November 18, 2016 and mailed to property owners within 500 ft. of the project site on November 17, 2016. Due to the need to recirculate the environmental document, notice of the project was published again on Wednesday, March 1, 2017 and sent to property owners within 500 ft. on February 28, 2017. No public comments have been received as of the date of the preparation of this staff report.

ENVIRONMENTAL ASSESSMENT

In accordance with CEQA, Annexation/Reorganization No. 152, Prezone No. 2016-01, Tentative Tract 918, Tentative Tract 919, and Tentative Parcel Map No. 2016-02 were evaluated in an Environmental Assessment/Initial Study. Based on the review, it was determined that the proposed project would not result in a significant adverse impact on the environment with the incorporation of mitigation measures, therefore Mitigated Negative Declaration No. 2016-06 has been prepared, attached as **Exhibit F**. A "Notice of Intent to Adopt a Mitigated Negative Declaration" was circulated for comment from November 18, 2016 – December 9, 2016 and recirculated for comment from February 17, 2017 to March 9, 2017.

ENVIRONMENTAL ASSESSMENT

In accordance with CEQA, Annexation/Reorganization No. 152, Prezone No. 2016-01, Tentative Tract 918, Tentative Tract 919, and Tentative Parcel Map No. 2016-02 were evaluated in an Environmental Assessment/Initial Study. Based on the review, it was determined that the proposed project would not result in a significant adverse impact on the environment with the incorporation of mitigation measures, therefore Mitigated Negative Declaration No. 2016-06 has been prepared, attached as **Exhibit F**. A "Notice of Intent to Adopt a Mitigated Negative Declaration" was circulated for comment from November 18, 2016 – December 9, 2016 and recirculated for comment from February 17, 2017 to March 9, 2017.

RESOLUTION NO. 17-29-R

**A RESOLUTION OF THE CITY COUNCIL OF THE CITY OF HANFORD
APPROVING TENTATIVE TRACT 919. THE PROJECT IS A REQUEST TO
SUBDIVIDE 31.77 ACRES INTO 125 SINGLE-FAMILY, LOW-DENSITY
RESIDENTIAL LOTS IN AN AREA PROPOSED TO BE PREZONED “R-1-6” LOW-
DENSITY RESIDENTIAL, IN ACCORDANCE WITH THE GENERAL PLAN, OR “R-
L-5” LOW-DENSITY RESIDENTIAL SHOULD THE NEW ZONING ORDINANCE BE
IN EFFECT PRIOR TO THE RECORDATION OF ANNEXATION 152**

At a regular meeting of the City Council of the City of Hanford duly called and held on May 16, 2017, by motion of Councilmember Sorensen, and seconded by Councilmember Ramirez, and duly carried, the following resolution was adopted:

WHEREAS, Tentative Subdivision Map No. 919, filed by John Zumwalt on behalf of San Joaquin Valley Homes, a request to subdivide 31.77 acres into 125 single-family, low-density residential lots, located on a portion of APN 009-030-148, as shown in **Exhibit A**, has been reviewed by the City Council of the City of Hanford, in accordance with Title 16 of the Hanford Municipal Code; and

WHEREAS, the City Council has carefully considered recommendations and testimony presented at the public hearing of May 16, 2017, and

WHEREAS, all affected public utility companies, various governmental department agencies, staff, and the City Council, have given careful consideration to this tentative subdivision map and have made recommendations thereon; and

WHEREAS, the Initial Study, Mitigated Negative Declaration No. 2016-06, and all notices related thereto were prepared in compliance with the California Environmental Quality Act (CEQA) and the City of Hanford Municipal Code and Policies; and

WHEREAS, the City Council has made the following findings, pursuant to Section 16.04.010 of the Hanford Subdivision Ordinance, Section 66474 of the Subdivision Map Act and Hanford’s Zoning Ordinance:

1. Consistency Finding:

ANALYSIS: That a consistency finding can be made, because the proposed subdivision map is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the “R-L-5” Low-Density Residential Zone District and the “R-1-6” Low-Density Residential Zone District. The minimum lot size within the subdivision is 6,023 ft. The average lot size is 7,322 sq. ft.

2. Design Finding:

ANALYSIS: That the design or improvement of the subdivision is consistent with the State Subdivision Map Act, General Plan, Zoning Ordinance, and Subdivision Ordinance. All lots proposed meet the minimum lot size of the “R-L-5” Low-Density Residential Zone District and the “R-1-6” Low-Density Residential Zone District. The minimum lot size within the subdivision is 6,023 ft. The average lot size is 7,322 sq. ft. All improvements are to be developed in accordance with Public Works Construction Standards.

3. Type of Development Finding:

ANALYSIS: That the site is physically suitable for the type of development proposed under Tentative Tract 919. All lots proposed meet the minimum lot size of the “R-L-5” Low-Density Residential Zone District and the “R-1-6” Low-Density Residential Zone District. All parcels have adequate street frontage on a public street and meet the minimum depth and width required for the district.

4. Density Finding:

ANALYSIS: That a density finding can be made, because the site is physically suitable for the proposed density of development. The 2002 General Plan prescribes a density range between two and nine units per acre. The 2035 General Plan prescribes a density range between two and ten units per acre. The project has a density of 3.93 dwelling units per acre.

5. Environmental Finding:

ANALYSIS: That initial study was conducted; and, on the basis on the initial study, the Community Development Department has determined that the project described above would not have significant adverse impacts on the environment, with the incorporation of mitigation measures. Mitigated Negative Declaration No. 2016-06 has been prepared for the project.

6. Public Health Finding:

ANALYSIS: That the design of the subdivision and type of improvements are not likely to cause serious health problems. The City of Hanford Building Division is responsible for ensuring that future construction of the site follows adopted building codes, thus reducing exposures to accidents to the general public. Consultation was sent for Tentative Tract 919 to interested agencies, including the County Health Department, Public Works Department, Fire Department, and Building Division. Any improvements or mitigations required for public health and safety were applied to the proposal and required in the conditions of approval.

7. Improvements and Access Findings:

ANALYSIS: That the design of the subdivision and type of improvements will not conflict with easements acquired by the public at large for access through or use of the property within the proposed subdivision. The existing access easements shown on Tentative Parcel Map 919 will be quit claimed to APN 009-030-002.

NOW, THEREFORE, BE IT RESOLVED, that the City Council finds that no significant environmental impacts would result from the proposed project with the incorporation of mitigation measures, adopts a Mitigation Monitoring and Reporting Program, attached as **Exhibit B**, and certifies that Mitigated Negative Declaration No. 2016-06 was prepared consistent with CEQA and City of Hanford Environmental Guidelines.

THEREFORE, BE IT FURTHER RESOLVED that the City Council of the City of Hanford hereby approves Tentative Tract 919 subject to the following conditions:

ADMINISTRATION DEPARTMENT

Contact the City Attorneys' Office through the Planning Division: (559) 585-2580
Concerning questions that you may have on the conditions listed below:

Defense and Indemnification Provisions:

1. That the applicant shall defend, indemnify, and hold harmless the City of Hanford ("City"), its officials, officers, employees, representatives, agents and attorneys, from and against all claims, damages, losses, judgments, liabilities, expenses and other costs, including litigation costs and attorney fees, arising out of, resulting from, or in connection with, the City's act or acts leading up to and including approval of any environmental document and/or granting of any approvals relating to the project. Applicant's obligation to defend, indemnify and hold the City harmless specifically includes, but is not limited to, any suit or challenge by any third party against the City which challenges or seeks to set aside, void or annul the legality or adequacy of any environmental document approved by the City or any approval related to the project.
2. That the applicant's obligations to defend, indemnify and hold the City, its officials, officers and employees, representatives, agents and attorneys harmless under the provisions of this paragraph shall include, but not be limited to, the cost of preparation of any administrative record by City, staff time, copying costs, court costs, the costs of any judgments or awards against the City for damages, losses, litigation costs, or attorney fees arising out of a suit or challenge contesting the adequacy of any approval of the environmental document, or any approval related to the project, and the costs of any settlement representing damages, litigation costs and attorney fees to be paid to other parties arising out of a suit or challenge contesting the adequacy of the approval of the environmental document or any other approval related to the project, if the settlement so provides.
3. That the City may, at any time, require the applicant to reimburse City for costs that have been, or which the City reasonably anticipates will be, incurred by the City during the course of any action. Applicant shall reimburse City within thirty (30) days of receipt of an

itemized written invoice from City. Failure of the applicant to timely reimburse the City shall be considered a material violation of the conditions of approval of the project.

4. That the applicant shall comply with and shall require all contractors to comply with all prevailing wage laws, rules and regulations applicable to the project. Unless otherwise advised in writing by the City of Hanford, applicant shall be solely responsible for making any and all decisions regarding whether any portion or aspect of the project, including, without limitation, any form of reimbursement by the City of Hanford to the applicant or any contractor, will require the payment of prevailing wages. Further, applicant will be solely responsible for the payment of any claims, fines, penalties, reimbursements, payments or any other actions that may be initiated against applicant or any contractor as a result of failure to pay prevailing wages.
5. That the applicant shall defend, indemnify, and hold harmless the City of Hanford, its officials, officers, employees, representatives, agents and attorneys, from and against any and all claims, damages, losses, judgments, liabilities, expenses and other costs, including, without limitation, litigation costs and attorney fees, arising out of, resulting from, or in any way in connection with any violation or claim of violation of any prevailing wage law, rule or regulation applicable to any portion or aspect of the project. Applicant's obligation to defend, indemnify and hold the City of Hanford harmless specifically includes, but is not limited to, any suit or administrative action against the City of Hanford which claims a violation of any prevailing wage law, rule or regulation applicable to any portion or aspect of the project.
6. That the applicant's obligations to defend, indemnify and hold the City of Hanford, its officials, officers, employees, representatives, agents and attorneys harmless as set forth herein, shall include, but shall not be limited to, staff time, copying costs, court costs, the costs of any judgments or awards against the City of Hanford for damages, losses, litigation costs, or attorney fees arising out of any violation or claim of violation of any prevailing wage law, rule or regulation applicable to any portion or aspect of the project and costs of any settlement representing damages, litigation costs and attorney fees to be paid to other parties arising out of any such proceeding or suit.
7. That the City of Hanford may, at any time, require the applicant to reimburse the City of Hanford for costs that have been, or which the City of Hanford reasonably anticipates will be, incurred by the City of Hanford during the course of any action. Applicant shall reimburse the City of Hanford within thirty (30) days of receipt of an itemized written invoice from the City of Hanford. Failure of the applicant to timely reimburse the City of Hanford shall be considered a material violation of the conditions of approval of the project.

PLANNING DEPARTMENT

Contact Associate Planner Gabrielle de Silva at (559)585-2578
Concerning questions that you may have on the conditions listed below:

General:

1. That the applicant hereby agrees to hold the City of Hanford and all of its departments, officers, agents, and employees free and harmless of and from all claims of any kind or nature arising out of or by reason of the approval of this project.
2. That approval of this project does not exempt compliance with all applicable sections of the Uniform Fire and Building Codes, Zoning Ordinance, Public Works Improvement Standards, and other City Ordinances.
3. That the final map be submitted to the City Engineer and Community Development Department for compliance with the Tentative Subdivision Map approval prior to recording the final map.
4. That all conditions of approval listed in this resolution by the City of Hanford be contained in the line drawing submitted for building permits.
5. That no occupancy of any building and/or structure shall be permitted which is not in substantial compliance with approved plans except upon specific review and approval of any "as built" modifications by the authorizing City body (City Council, Planning Commission, Community Development Department, or other appropriate city departments).
6. That in accordance with Title 16 of the Hanford Municipal Code, all conditions of this subdivision listed herein, and contained in subsequent improvement agreements, excluding the landscape district, must be completed and accepted for maintenance by the City Council prior to the final building inspection and occupancy permits being issued for the first house in the subdivision.
7. That all species of trees shall be selected from a list approved by the City Street Tree Commission.
8. That each lot owner within Tract 919 shall care for and maintain the trees and lawn area located in the parkway in front of their lot(s). For corner lots, the lot owner shall also care for and maintain the parkway trees and land area along the street-side of their lot. The parkway is defined as that land area located between the street curb and the public sidewalk.
9. That all mitigations cited in the Mitigation, Monitoring, and Reporting Program, attached as **Exhibit B**, are also conditions of approval of the project.
10. That any changes to the proposed phasing be approved by the Community Development and Public Works Department.
11. That the project is subject to the San Joaquin Valley Unified Air Pollution Control District's Indirect Source Review Rule 9510. An application must be filed with the District immediately upon approval of the project. For more information and instruction, contact the Districts Indirect Source Rule staff by telephone at (559) 230-6000.
12. That the proposed project may be subject to District Rules and Regulations, including: Regulation VIII (Fugitive PM10 Prohibitions), Rule 4102 (Nuisance), Rule 4601

(Architectural Coatings), and Rule 4641 (Cutback, Slow Cure, and Emulsified Asphalt, Paving and Maintenance Operations). In the event an existing building will be renovated, partially demolished or removed, the project may be subject to District Rule 4002 (National Emission Standards for Hazardous Air Pollutants). The above list of rules is neither exhaustive nor exclusive. To identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559) 230-5888. Current District rules can be found online at www.valleyair.org/rules/1ruleslist.htm.

13. That per the requirements of Kings County Area Public Transit Agency (KART), a 10' x 12' concrete pad for a proposed bus stop and shelter shall be provided as shown in attached **Exhibit D**. The pad shall be placed within the 10' landscape easement provided on Centennial Drive, north of Dahli Way, behind lot 40.

Special Requirements

1. That a right-to-farm provision be recorded with the recording of the final subdivision map to insure that future residents of the homes in the project are aware of the adjacent agricultural uses and their right to continue to operate.

Zoning

1. That all requirements of the "R-1-6" Low-Density Residential Zone District shall apply. *(Should the new zoning ordinance be in effect prior to the recordation of Annexation 152, all requirements of the "R-L-5" Low-Density Residential Zone District shall apply, instead.*

Architectural Conditions:

1. That all pipes, gutters, and chases attached to the building wall shall be painted a similar or complementary color to the existing wall to which the item is attached.
2. That no surface shall be mirrored so as to cause glare and annoyance to other adjacent properties.
3. That all mechanical equipment, including electrical and gas meters, are to be screened from view, and that all new electrical transformers are either installed underground or screened.
4. That all exterior architectural elements not detailed on the plans be finished in a style and in materials in harmony with the exterior of the building

Environmental Requirements:

1. That if cultural resources are discovered during construction or related activities, all work shall be halted and a qualified archeologist and the City of Hanford shall be notified. The find shall be properly investigated and appropriate measures are to be taken before construction may continue.

2. That if fireplaces are proposed in the residential units, natural gas fireplaces or EPA-certified wood-burning fireplaces/stoves are to be installed in every unit that has a fireplace. Conventional open-hearth fireplaces are not allowed.
3. That natural gas lines and electrical outlets be installed in backyards or patios to encourage use of gas and/or electric barbecues.
4. That electrical outlets be installed around the exterior of the residential units to encourage use of electric lawn mowers, edgers, etc.

Noise:

1. That construction equipment be muffled and construction activities be limited to the hours between 7:00 a.m. to 10:00 p.m., Monday through Friday, unless the construction is within the enclosed structure or approved by the Community Development Department.
2. That noise from fixed mechanical equipment, when measured at the property line, meets the standard of the Hanford Noise Element.

Lighting:

1. That all exterior lighting shall be focused downward to avoid point sources of light interfering with the vision of motorists. Lighting elements shall be recessed into their fixtures to prevent glare. Exterior lighting shall be installed so as not to illuminate adjacent properties.

Screening:

1. That all backflow devices and electrical transformers be screened with landscaping.
2. That all backflow devices be painted hunter green.

Fencing/Walls:

1. That all proposed fencing on the site be maintained in good repair with any graffiti at the site removed within 72 hours of occurrence.

Landscaping:

1. That four trees per lot be planted in the front yard at the time each lot is landscaped in accordance with City Ordinance 17.18.100(F). For corner lots, a minimum of two trees are to be planted between the curb and sidewalk along both street frontages located adjacent to the lot. Developer shall submit a landscape and irrigation system improvement plan for each house plan proposed within the subdivision for City Community Development Department review and approval.

2. That landscape and irrigation plans be submitted for approval by the Community Development Department prior to building permits being issued. Said plans shall conform to Ordinance No. 10-02 "Standards and Procedures for Landscaping Design and Installation."
3. That all open and unlandscaped portions of the site be maintained in good condition, free from weeds, dust, trash and debris.

Dust Control:

1. That the following dust-control practices shall be implemented:

Pre-construction:

1. That material excavated or graded be sufficiently watered to prevent excessive amounts of dust. Watering should occur at least twice a day with complete coverage, preferably in the late morning and after work is completed for the day.
2. That clearing, grading, earth moving, or excavation activities cease during periods of high winds greater than 20 mph.
3. That areas disturbed by clearing, earth moving, or excavation activities be minimized at all times.

During Construction:

1. After clearing, grading, earth moving, or excavation operations, during the construction phase, fugitive emissions should be controlled by the following methods:
 - a. That non-active portions of the construction site be restricted from vehicular movement.
 - b. That active portions of the site should be sufficiently watered to prevent excessive amounts of dust.

General Fugitive Dust:

At all times, fugitive dust emissions should be controlled using the following procedures:

1. That on-site vehicle speed should be limited to 15 mph.
2. That areas with vehicle traffic be watered periodically or have petroleum-based palliatives applied for stabilization of dust emissions.
3. That during rough grading and construction, streets next to the project site be swept at least once per day, or as required to remove silt which may have accumulated from construction activities.

4. That during rough grading and construction, access to the site should require the building of an apron into the project site from adjoining paved roadways. The apron should be paved or have a petroleum-based palliative applied.

Ozone Precursors:

At all times, ozone precursor emissions should be controlled by the following methods:

1. That all internal combustion-engine drive equipment be properly maintained and well tuned according to the manufacturer's specifications.

BUILDING DIVISION

Contact Building Official: Tom Webb (559) 585-2584

Concerning questions that you may have on the conditions listed below:

Soils:

1. That a preliminary soils report, prepared by a qualified soil's engineer, be provided to the Engineering and Building Departments prior to approval of Subdivision Improvement Plans.
2. That a final soils report, prepared by a qualified soils engineer, be provided to the Engineering Department and Building Division prior to acceptance of the subdivision improvements by the City or issuance of building permits or whichever comes first.
3. That the developer retain the design engineer to inspect and verify that grading within the subdivision was constructed as per the approved design, and a copy of the report be provided to the Building Division prior to building permit issuance.

Street Names and Addresses:

1. That street addresses for each lot, as provided by the Building Division, be included on the subdivision final map.
2. That street names, as shown on the tentative subdivision map, be included on the subdivision final maps.
3. That all single family dwellings within the subdivision have illuminated address numbers 2-¼ inches high or be within an illuminated area with 3-½ inch high address numbers installed on the front most part of the building leading to the entrance. In either case the address numbers shall be of contrasting colors with the background.
4. That all landscaping requires permits and must meet requirements at time of installation.

FIRE DEPARTMENT

Contact Fire Inspector Susan Martinez @ (559) 585-4793 or smartinez@cityofhanfordca.com concerning questions that you may have on the conditions listed below:

General:

1. **Approval of this project does not exempt compliance with all applicable sections of the City adopted fire codes and local fire ordinances.**
2. All fire protection systems must be installed and operational prior to occupying any building and/or issuance of a Certificate of Occupancy.

Emergency Access:

1. Locked gates installed across fire department access roads shall comply with the following depending on the type of situation:
 - a. **Manual gates** with a chain lock require a **Knox Padlock, Model #3770**, to be installed on them; a **Knox Box, Model 3200 Series**, shall be installed at lever-type key locking devices.
 - b. **Electric gates** shall be equipped with an electric **Knox Key Switch, Model 3502**, at the gate location.
 - c. In case of a loss of power, electrically operated gates shall have a means of back-up power or shall default in the open position for immediate fire department access.
 - d. At no time shall the width of the fire department access road be reduced below **20-feet wide through or at any gates** along the fire departments' emergency access roads due to protruding objects from gate supports, frames, signs, access booths, curbs, etc.
2. Fire apparatus emergency access roads shall not be less than **20-feet wide and 13-feet, 6-inches in height (vertically)**.
3. Traffic calming devices shall not be installed onto fire department emergency access roads unless prior approval is obtained from the Hanford Fire Department.
4. All fire department emergency access roads shall be within the Hanford Fire Department radius measurements as follows:

Calculated Turning Radii:

- | | | |
|-----------|---------------|---------------|
| a. | Inside Turn: | 20 ft., 1 in. |
| b. | Curb to Curb: | 36-ft, 3 in. |
| c. | Wall to Wall: | 44 ft., 6 in. |
5. Temporary or permanent fire department emergency access roads shall be constructed in accordance with **City Standard ST-36**. All weather access roads shall be in place prior to

any combustible construction being brought onto the premises unless approved by the fire department.

6. The fire department may require that you submit an all-weather access road plan for our review and approval prior to construction. A sign or signs may be required to be installed along temporary fire department access roads.
7. The ordering of Knox Box products can be done directly online at www.knoxbox.com or a form can be obtained from the fire department.

Storage Tanks with Flammable/Combustible Liquids or Hazardous Materials:

1. A separate permit is required for all hazardous materials and/or flammable and combustible liquids, gases, solids, etc., over the exempt amounts set forth in the latest adopted edition of the CFC.

Fire Hydrants and Underground Fire Service:

1. The fire flow and fire hydrant requirements shall comply with the City of Hanford Standards for Water Supply in new developments and the 2016 Edition of the California Fire Code. The fire department shall approve all fire hydrants prior to installation.
2. Fire hydrant protection posts shall be installed at all fire hydrants that are subject to vehicle damage.
3. A new fire hydrant flow test is required to ensure there is adequate water flow for the complete development that's proposed.

PUBLIC WORKS ENGINEERING DIVISION

Contact Samantha Long Assistant Engineer at (559)585-2556
Concerning questions you may have regarding the conditions below:

Maps and Plans:

1. That the developer shall submit to the City Engineer a set of construction plans on 24" x 36" sheets for all required improvements. Plans shall be prepared by a registered civil engineer and shall include a drainage and utility plan identifying sizes and location of sanitary sewer, storm drainage and water mains, curbs, gutters, sidewalks, masonry walls, street lights, street improvements, culverts and landscape improvements and all other infrastructure required to complete development. All plans shall be approved by the City Engineer and all other involved agencies before the release of the building permits.
2. That prior to beginning any construction or within ten (10) calendar days after the approved plans are released by the City, the developer shall submit to the City of Hanford Engineering Division one (1) reproducible and four (4) blue line copies of the approved set of construction plans and four (4) bound sets of the approved construction specifications, if any.

3. That within twenty (20) calendar days after all improvements have been constructed and accepted by the City, the developer shall submit to the City of Hanford Engineering Division one (1) reproducible and one (1) blue line copy of the approved set of construction plans revised to reflect all field revisions and marked "RECORD DRAWING."

Easements:

1. That all easements shall be designated on the subdivision final map as required by the utility companies and where needed for providing service to street lights and landscape improvements as designated by the City Public Works Department.
2. That all easements for irrigation ditches and / or irrigation pipelines shall be legally abandoned or relocated to the satisfaction of the City Engineer prior to the recording of a subdivision final map.
3. That all proposed landscape/public utility easements, located as shown on the tentative subdivision map, shall be dedicated to the City and be delineated on the final subdivision map. Landscape/public utility easement shall meet or exceed the following minimum widths:
 - a.) Centennial Drive – Ten feet (Landscape/Public Utility)
 - b.) Fargo Avenue – Ten feet (Landscape/Public Utility)
 - c.) All residential streets – Six feet (Public Utility)

Dedications:

1. That all proposed streets and street extensions, located as shown on the tentative subdivision map, shall be dedicated to the City as public right-of-way, and any alteration of existing utilities shall be the responsibility of the developer.
2. That all proposed landscape public utility easements, located as shown on the tentative subdivision map shall be dedicated to the City for landscape and public utility purposes concurrent with the recording of a subdivision final map.

Restricted Access:

1. That a one-foot reservation strip shall be established at the end or sides of all streets abutting undeveloped property and be indicated on the subdivision final map.
2. That all access shall be restricted from lots at the property lines backing onto Centennial Drive and Fargo Ave shall be indicated on the subdivision final map.

Street Improvements:

1. That all improvements consisting of sanitary sewers, storm sewers, water mains, concrete curbs, gutters, sidewalks, street lights, landscaping, street sub-grading, surfacing and striping

and all other improvements shall be installed in accordance with Chapter 16.24, "Improvements", of the Hanford Municipal Code and this resolution pertaining to subdivision improvements in effect at the time of filing the tentative subdivision map.

2. That all streets within the subdivision shall be developed to residential street standard ST-32, except the following:
 - a. Centennial Drive shall be developed as a major collector street along the entire development frontage. All improvements shall be constructed in conformance with City Standards ST-17 and ST-23 and as follows:
 1. Traffic index used for the design of the street structural section shall be a minimum of 7.0.
 2. Developer shall construct a left turn pocket at the intersection of Fargo Ave and Centennial Drive for west bound traffic along Fargo Ave.
 - b. Fargo Ave shall be developed as an arterial street, along the development frontage of the subdivision. All improvements shall be constructed in conformance with City Standards ST-17 and ST-23, and as follows:
 1. Traffic index used for the design of street structural section shall be a minimum of 10.0.
 2. A geotechnical report shall be submitted to the City Engineer identifying the existing structural section thickness of Fargo Ave, along the entire development frontage, concurrent with the submittal of development improvement plans. Reconstruction of Fargo Ave, along the entire development frontage will be required if the existing street structural section does not conform to City Standards and Specifications.
 3. Street improvements south of the Fargo Ave street centerline shall include, but not be limited to, the installation of concrete curb and gutter, sidewalk, landscaping, decorative masonry block wall, street lights, including pavement reconstruction of existing roadway if applicable, and all street signing, striping and transition paving as required. The installation of raised concrete median in Fargo Ave is not required.
 4. Street improvements north of the Fargo Ave street centerline shall include, but not be limited to, the construction of a minimum 12 foot travel lane, 4 foot paved shoulder, and 4 foot graded shoulder, including pavement reconstruction of existing roadway if applicable, and all street signing, striping and transition paving as required. The installation of raised concrete median in Fargo Ave is not required.
 5. Developer shall attempt to acquire additional street right-of-way along the "Not a Part" frontage of Fargo Ave in accordance with Section 66462.5 of the Subdivision Map Act. The additional street right-of-way is necessary to facilitate street

widening improvements along the entire development frontage of Fargo Ave. If Developer is unsuccessful, City will attempt to acquire the right-of-way.

3. That street lights shall be installed throughout the subdivision in conformance with City Standard GE-56 and Southern California Edison requirements. Street lights shall be located as designated by City Engineer.
4. That a traffic signal be installed at the intersection of Centennial Drive and Fargo Ave at the time of the construction of the development unless a focused traffic study is conducted and the analysis determines that the traffic signal does not to meet the required warrants with the development of the subdivision.
5. That development is subject to a transportation mitigation impact fee as required by City Municipal Code section 15.48 and any revisions thereof. Developer shall be entitled to a credit towards their development impact fee for permanent street improvements constructed by developer within Fargo Ave, consisting of curb & gutter, street striping, signing and street paving from gutter lip to edge of the existing Fargo Ave street sections. If applicable, developer may also be entitled to credit towards impact fees for supplemental transportation capacity improvements to the existing Fargo Ave street section. Transitional paving improvements beyond the development limits, that are not considered to be a permanent improvements and the reconstruction of the existing Fargo Ave street section, if required, will not be subject to a credit. Developer shall submit competitive bid proposals to substantiate the cost of reimbursable items for City Public Works Department review and approval prior to beginning construction. All documentation materials submitted for reimbursement consideration shall be well organized and tabulated for convenient reference by Public Works' staff. Improvement quantities and costs proposed for reimbursement must be clearly identified in the documentation provided, and not combined or aggregated with non-reimbursable subdivision improvement costs. Appropriate graphic exhibits referenced to the subdivision improvement plans shall also be provided as needed to facilitate the reimbursement review process.

Backup Parkway Improvements:

1. That the developer shall design and construct the following improvements along the development frontages of Centennial Drive and Fargo Ave for lots backing onto said streets:
 - a. A minimum six foot high decorative masonry block wall with continuous reinforced concrete footings. Masonry walls shall be treated with anti-graffiti repellent. The minimum height of the wall shall be measured from the highest elevation grade of the property located adjacent to either side of the wall. Wall heights shall be maintained at a uniform grade / slope whenever possible. If elevation changes are required, steps shall be introduced at pilaster locations and / or changes in wall direction. Wall improvement plans shall be designed to incorporate architectural, civil and structural components into one set of drawings. Wall plans shall be reviewed and approved by both the City Public Works and Community Development Departments.

- b. A 4 1/2 foot wide meandering detached sidewalk along the development frontages of Centennial Drive and Fargo Ave.
 - c. Landscaping and irrigation system improvements along the development frontages of Centennial Drive and Fargo Ave. Landscape plans shall be prepared by a licensed landscape architect. Plans shall be reviewed and approved by the City Public Works, Parks & Recreation, and Community Development Departments.
2. That a minimum of four trees per lot shall be planted in the front yards of homes at the time each lot is landscaped in accordance with City Ordinance 17.18.100(F). For corner lots, a minimum of two trees per lot are to be planted between the curb and sidewalk along both street frontages located adjacent to the lot. Trees planted in the park strip shall be located in conformance with City Standard GE-13. Developer shall submit a landscape and irrigation system improvement plan for each house plan proposed within the subdivision for City Community Development department review and approval.
 3. That all species of trees and plants shall be selected from a list approved by the City's Parks and Recreation Commission.
 4. That all new and existing electrical boxes, control boxes and other equipment boxes (excluding traffic control) cabinets along the street frontage shall be painted hunter green or be of a color compatible with the landscaping. Prior to painting, all metal surfaces shall be treated with an etching primer (zinc chromate) or equivalent. All new irrigation electrical and control cabinets shall be mounted into the masonry wall per City Standards.
 5. That a covenant including each residential lot within the subdivision and requiring care and maintenance of local street park strip landscape improvements along the individual lot frontage(s) by the homeowners thereof shall be recorded concurrent with the final map.

Sewer Improvements:

1. That the developer's engineer shall provide a sanitary sewer master plan complete with calculations for the entire subdivision for City Public Works Department review and approval prior to recording a subdivision final map for the development. Provisions shall be made to provide service for future areas of development located adjacent to the subdivision.
2. That the developer may be entitled to a refund for sewer main over-sizing in accordance with City Municipal Code Section 13.08. Developer's engineer shall be required to submit calculations to substantiate request for an over-sizing refund to the City Public Works Department for review and approval. The developer shall submit competitive bid proposals to substantiate costs for sewer main over-sizing for City Public Works Department review and approval prior to beginning construction.
3. That the developer may be entitled to enter into a reimbursement agreement in accordance with City Municipal Code section 13.08 for sewer system improvements which also provide a benefit to others. Developer shall submit competitive bid proposals to substantiate costs for

said sewer system improvements for Public Works Department review and approval prior to beginning construction.

Storm Drainage Improvements:

1. That the developer's engineer shall provide a storm drainage master plan complete with calculations for the entire subdivision for City Public Works Department review and approval prior to recording a subdivision final map for the development. Provisions shall be made to provide service for future areas of development located adjacent to the subdivision.
2. That all drainage from proposed development shall be retained in retention drainage basin located as shown on the tentative subdivision map.
3. That developer shall be required to comply with State of California Water Resources Control Board requirements specifically related to the National Pollution Elimination System Permit process.

Water System:

1. That the developer's engineer shall provide a Water System Master Plan complete with calculations for the entire subdivision for City review and approval prior to recording a subdivision final map for the development. Provisions shall be made to provide service for future areas of development located adjacent to the subdivision.
2. That the developer may be entitled to a refund for water main over-sizing in accordance with City Municipal Code Section 13.04. Developer's engineer shall be required to submit calculations to substantiate request for an over-sizing refund to the City Public Works Department for review and approval. The developer shall submit competitive bid proposals to substantiate costs for water main over-sizing for City Public Works Department review and approval prior to beginning construction.
3. That the developer may be entitled to enter into a reimbursement agreement in accordance with City Municipal Code section 13.04 for water system improvements which also provide a benefit to others. Developer shall submit competitive bid proposals to substantiate costs for said water system improvements for Public Works Department review and approval prior to beginning construction.
4. That all existing water wells located within the proposed development shall be abandoned in conformance with State of California Department of Health Standards.

Assessment District:

1. That the developer shall enter into an agreement with the City for the formation of a tax assessment district for the maintenance of interior subdivision street lighting, decorative block fencing, and landscaping located along the property frontages of Centennial Drive and Fargo Ave located as shown on the tentative subdivision map.

2. That prior to funds from the tax assessment district being obtained, the developer shall be responsible for the maintenance of all landscaping, subdivision interior street lighting and decorative fencing.

City Development Impact Fees:

1. That development is subject to a Police Development Impact Fee as required by City Ordinance No. 98-14, and any revisions thereof. Fee payable with each building permit.
2. That development is subject to a Fire Development Impact Fee as required by City Ordinance No. 98-14, and any revisions thereof. Fee payable with each building permit.
3. That development is subject to a Park Development Impact Fee as required by City Ordinance No. 90-10 and any revisions thereof. Fee payable with each building permit.
4. That development is subject to a Transportation mitigation impact fee as required by City Ordinance No. 90-09 and any revisions thereof. Fee payable with each building permit.
5. That the development is subject to a Wastewater System Development Impact fee as required by City Ordinance No. 98-14, and any revisions thereof. Fee payable with each building permit.
6. That development is subject to a Water System Development Impact Fee as required by City Ordinance No. 98-14 or any revisions thereof. Fee payable with each building permit.
7. That development is subject to a Refuse and Recycling Development Impact Fee as required by City Ordinance No. 05-16 or any revisions thereof. Fee payable with each building permit.
8. That development is subject to a Storm Drainage Development Impact Fee as required by City Ordinance No. 98-14, and any revisions thereof. Fee payable prior to recording of subdivision final map.
9. That development is subject to a 12th Avenue Sanitary Sewer area of benefit district assessment fee as required by City Ordinance No. 92-03 or any revisions thereof, if applicable. Fee shall be payable prior to recording to recording of final subdivision map.

SAN JOAQUIN VALLEY AIR POLLUTION CONTROL DISTRICT

Contact Cherie Clark Air Quality Specialist at (559)230-5940

Concerning questions you may have regarding the conditions below:

1. That the proposed project would be subject to District Rue 9510 (indirect source review).

- District Rule 9510 is intended to mitigate a project's impact on air quality through project design elements or by payment of applicable off-site mitigation fees.
 - Any applicant subject to District Rule 9510 is required to submit an Air Impact Assessment (AIA) application to the District no later than applying for final discretionary approval.
 - If approval of the subject project constitutes the last discretionary approval by your agency, the District recommends that demonstration of compliance with District Rule 9510 be made a condition of project approval. Information can be found online at: <http://www.valleyair.org/ISR/ISRHome.htm>.
2. The proposed project may be subject to District Rules and Regulations, including Regulation VIII (Fugitive PM10 Prohibitions), Rule 4102 (Nuisance), Rule 4601 (Architectural Coatings), and Rule 4641 (cutback, Slow Cure, and Emulsified Asphalt, Paving and Maintenance Operations). In the event an existing building will be renovated, partially demolished or renovated, the project may be subject to District Rule 4002 (National Emission Standards for Hazardous Air Pollutants). The above list of rules is neither exhaustive nor exclusive. To identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559)230-5888. Current District rules can be found online at: www.valleyair.org/rules/1ruleslist.htm.
 3. The District recommends that a copy of the District's comments be provided to the project proponent. Attached as **Exhibit C**.

KINGS COUNTY HEALTH DEPARTMENT

Contact Troy Hommerding at (559) 584-1411

Concerning questions that you may have on the conditions listed below:

1. Valley Fever: As per the Kings County Public Health Officer, *Coccidioides immitis*, the fungus that causes valley fever, a serious and potentially long-term respiratory illness, is endemic in the soils of Kings County. Construction activities that disturb soils containing the spores of the fungus can put workers and the nearby public at risk. Effective dust control must be maintained on the job site at all times in order to reduce the risk of valley fever to workers and nearby residents. More information regarding the prevention of work related valley fever is available at www.cdph.ca.gov/programs/hesis/Documents/CocciFact.pdf and <http://www.cdph.ca.gov/programs/ohb/Documents/OccCocci.pdf>. Contact the San Joaquin Valley Air Pollution Control District for more information on dust control techniques.

KINGS COUNTY AREA PUBLIC TRANSIT AGENCY

Contact Facilities and Fleet Specialist Mark Pederio at (559)852-2624

Concerning questions that you may have on the conditions listed below:

14. That a 10' x 12' concrete pad for a proposed bus stop and shelter shall be provided as shown

in attached **Exhibit D**. The pad shall be placed within the 10' landscape easement provided on Centennial Drive, north of Dahli Way, behind lot 40.

EXPIRATION:

That this tentative subdivision map becomes null and void after 24 months has elapsed from the date of approval, if the above conditions have not been satisfied or bonded for, and a final map recorded. A time extension may be granted by the Commission upon written request by the applicant. The time extension, if approved, will be subject to the improvement standards and fees in effect at the time the extension for the tentative subdivision map is granted.


PASSED AND ADOPTED at a regular meeting of the City Council of the City of Hanford held on the 16th day of May, 2017, by the following vote:

AYES: Sue Sorensen, Francisco Ramirez, Justin Mendes, David Ayers

NOES: _____

ABSTAIN: _____

ABSENT: Martin Devine



DAVID G. AYERS
MAYOR of the City of Hanford

Attest:



JENNIFER GOMEZ
CITY CLERK

STATE OF CALIFORNIA)
COUNTY OF KINGS) ss
CITY OF HANFORD)

I, Jennifer Gomez, City Clerk of the City of Hanford, do hereby certify the foregoing Resolution was duly passed and adopted at a regular meeting of the City Council of the City of Hanford held on the 16th day of May, 2017.

Date: 05-17-17



City Clerk

Tentative Tract 919
Page 20 of 24

Exhibit A:
Tentative Tract Map 919

Attachment: Attachment 3 - City Council Resolution 17-29-R (Time Extension No. 2019-01)




Exhibit B:
Mitigation Monitoring and Reporting Program

Annexation/Reorganization 152, Prezone No. 2016-01, Tentative Tract 918, Tentative Tract 919, and Tentative Parcel Map No. 2016-02
Mitigation Measures
Mitigated Negative Declaration 2016-06

Mitigation Number	Potential Impact	Mitigation Measure	Responsible Party
AESTHETICS			
Mitigation Measure: Aesthetics 1.	The project could potentially create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?	That all exterior lighting shall be focused downward to avoid point sources of light interfering with the vision of motorists. Lighting elements shall be recessed into their fixtures to prevent glare. Exterior lighting shall be installed so as not to illuminate adjacent properties.	Developer to provide; City to require
AGRICULTURE			
Mitigation Measure: Agriculture 1.	Involve other changes in the existing environment which, due to their location or nature, could result in conversion of Farmland, to non-agricultural use or conversion of forest land to non-forest use?	That a right-to-farm provision be recorded with the recording of the final subdivision map(s) to insure that future residents of the homes in the project are aware of the adjacent agricultural uses and their right to continue to operate.	Developer
AIR QUALITY			
Mitigation Measure: Air Quality 1.	Project could potentially conflict with or obstruct implementation of the applicable air quality plan.	That the project is subject to the San Joaquin Valley Unified Air Pollution Control District's Indirect Source Review Rule 9510. An application must be filed with the District immediately upon approval of the project. Additionally, in order to identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559)230-5888.	Developer to file application with San Joaquin Valley Air Pollution Control District
Mitigation	The project could	The applicant will be required to obtain permits demonstrating compliance	Developer to

Measure: Air Quality 2.	potentially result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)?	with Rule 9510, or payment of mitigation fees to the SJVAPCD prior to issuance of a building permit. The project may also be subject to Regulation VII, Rule 4641, and Rule 4692 to further reduce air quality impacts. Although emissions resulting from the project exceed the thresholds of significance for PM10, the City of Hanford adopted a Statement of Overriding Considerations for Air Quality as part of the certification of the EIR prepared for the 2002 General Plan, which will be restated in the approval of the negative declaration. Additionally, in order to identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559)230-5888.	obtain permits from San Joaquin Valley Air Pollution Control District.
Mitigation Measure: Air Quality 3.	Project could potentially violate any air quality standard or contribute substantially to an existing or projected air quality violation.	The proposed project will result in short term construction related emissions and operational emissions. The short term construction impacts are considered less than significant by the SJVAPCD based on compliance with the District's mandatory dust control measures. Development of the site will be subject to SJVAPCD's Indirect Source Rule (Rule 9510) procedures. The applicant will be required to obtain permits demonstrating compliance with Rule 9510, or payment of mitigation fees to the SJVAPCD prior to issuance of a building permit. The project may also be subject to Regulation VII, Rule 4641, and Rule 4692 to further reduce air quality impacts. Additionally, in order to identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559)230-5888.	Developer
CULTURAL RESOURCES			
Mitigation Measure: Cultural Resources 1.	Project could potentially disturb any human remains, including those interred outside of formal cemeteries.	Project conditions of approval will include a requirement that in the case that any human remains are discovered at any time, that construction will cease and the City is notified as well as the County Coroner pursuant to California Health and Safety Code 7050.5 and Public Resources Code 5097.98.	Developer
Mitigation Measure: Cultural	Project could potentially disturb any human	That a Burial Treatment Plan be entered to by the applicant/property owner prior to any earth disturbing activities.	City and applicant/property

Resources 2.	remains, including those interred outside of formal cemeteries.		owner.
Mitigation Measure: Cultural Resources 3.	Project could potentially disturb any human remains, including those interred outside of formal cemeteries.	(Project Specific) That the Tachi Tribe have a Native American monitor on-site during tree removal and/or other ground disturbing activities; including, but not limited to, grading, trenching, etc. Monitoring to continue until released by the Tachi Tribal Cultural Department.	City and applicant/property owner.
Mitigation Measure: Cultural Resources 4.	Project could potentially disturb any human remains, including those interred outside of formal cemeteries.	(Project Specific) That a cultural presentation be given to the developer and all contractors and sub-contractors prior to any ground disturbing activities.	City and applicant/property owner.
GEOLOGY AND SOILS			
Mitigation Measure: Geology and soils 1.	The project could potentially result in substantial soil erosion or the loss of topsoil.	Standard construction practices that comply with City of Hanford ordinances and regulations, the California Building Code, and professional engineered designs approved by the Hanford Public Works Engineering Division will mitigate any potential impacts from future development, if any. The Hanford General Plan and City of Hanford Development Standards include policies for development that would reduce the potential impact of soil erosion or the loss of topsoil.	City of Hanford must ensure conditions are set forth to mitigate impacts; Developer to comply with standards
GREENHOUSE GAS EMISSIONS			
Mitigation Measure: Greenhouse Gases 1	Project could potentially conflict with an applicable plan, policy or regulation adopted for the purpose of reducing the emissions of greenhouse gases.	Compliance with the Climate Action Plan and the rules of the San Joaquin Valley Air Pollution Control District will reduce impact to greenhouse gases to a less than significant level. With the incorporation of the above mitigation, the proposed project will not result in a conflict with any plan, policy or regulation; therefore, impacts to greenhouse gas emissions are less than significant.	Developer
HYDROLOGY AND WATER QUALITY			
Mitigation Measure:	The project could potentially violate water	The project will be required to comply with all City ordinance, standards and policies which will assure proper grading and storm water drainage	City to require; Developer to

Hydrology 1	quality standards or waste discharge requirements.	into the existing storm water system. The project will also be required to comply with all requirements of the Kings County Health Department, State, and Federal regulations regarding water quality standards or waste discharge. The project will not violate any water quality standard or waste discharge requirements.	provide
Mitigation Measure: Hydrology 2	The project could potentially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the aquifer, which will be required to comply with newly adopted State standards for landscaping as a result of the drought measures recently implemented by the State and the City of Hanford. The Urban Water Management Plan identified adequate groundwater supplies for the City of Hanford, therefore impacts are determined to be less than significant with mitigation measures for water usage associated with landscaping.	The project would not deplete groundwater supplies or interfere with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the aquifer as a result of the project. The majority of water use will be for landscaping, which will be required to comply with newly adopted State standards for landscaping as a result of the drought measures recently implemented by the State and the City of Hanford. The Urban Water Management Plan identified adequate groundwater supplies for the City of Hanford, therefore impacts are determined to be less than significant with mitigation measures for water usage associated with landscaping.	City to require; Developer to provide
Mitigation Measure: Hydrology 3	The project could potentially substantially alter the existing drainage pattern of the site or area, including through the alteration of the source of a stream or river, in a manner which could result in substantial erosion or siltation on- or off-site.	Compliance with State of California Water Resources Control Board requirements, specifically related to the National Pollution Elimination System Permit process.	Developer and City
Mitigation Measure: Hydrology 4	Otherwise substantially degrade water quality?	The project will be required to comply with all City ordinance, standards and policies which will assure proper grading and storm water drainage into the existing storm water system. The project will also be required to comply with all requirements of the Kings County Health Department, State, and Federal regulations regarding water quality standards or waste discharge. The project will not violate any water quality standard or waste discharge requirements.	
NOISE			
Mitigation	Exposure of persons to or	The project proposed and the future development of the property as a	Resident; Police

Measure: Noise 1	generation of noise levels in excess of standards established in the local general plan or noise ordinance, or applicable standards of other agencies?	residential development is consistent with the General Plan. Noise-Level performance standards will be required to meet the dB requirements prescribed by the General Plan Hazard's Element. The Hanford General Plan policies require residential development to be located in an environment where transportation noise and non-transportation noise meet City Standards. Standards for transportation noise at the property line are 60 dB and non-transportation related noise is 50 dB in the daytime and 45 dB at nighttime.	to enforce
PUBLIC FACILITIES			
Mitigation Measure: Public Facilities 1	The project may result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities. (Fire)	The project will be subject to fire impact fees.	Developer to pay
Mitigation Measure: Public Facilities 2	The project may result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities. (Police)	The project will be subject to police impact fees.	Developer to pay
Mitigation Measure: Public Facilities 3	The project may result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities,	The project will be subject to school impact fees.	Developer to pay

	need for new or physically altered governmental facilities. (school)		
Mitigation Measure: Public Facilities 4	The project may result in substantial adverse physical impacts associated with the provision of new or physically altered governmental facilities, need for new or physically altered governmental facilities. (Park)	The residential development proposes adequate park space for Tentative Tract 918. The future development of the annexed area, outside of the proposed subdivision, would be required to pay impact fees for any park space that is not accommodated on-site.	Developer to pay
RECREATION			
Mitigation Measure: Recreation 1	The project could potentially increase the use of existing neighborhood and regional parks or other recreational facilities such that substantial physical deterioration of the facility would occur or be accelerated?	The applicant will be required to provide park space or pay impact fees for park space.	City to require; developer to provide or pay
TRANSPORTATION AND TRAFFIC			
Mitigation Measure: Transportation 1	The project may cause an increase in traffic which is substantial in relation to the existing traffic load and capacity of the street system.	That the development is subject to traffic impact fees and traffic-related improvements.	Developer to pay impact fees
Mitigation Measure: Transportation 2	The project could result in inadequate parking capacity?	The applicant will be required to provide parking at the ratio prescribed by the Municipal Code for single-family residential, "b. One-family dwelling, two (2) spaces for each dwelling unit, with at least one space within a	City to require as condition of approval; developer to

		garage or carport."	provide
UTILITIES AND SERVICE SYSTEMS			
Mitigation Measure: Utilities 1	The project could affect the ability to have sufficient water supplies available to serve the project from existing entitlements and resources, or are new or expanded entitlements needed?	1. That the developer shall comply with State of California Water Resources Control Board requirements specifically related to the National Pollution Elimination System Permit process. 2. Due to the drought the project will be required to comply with all State and local regulations regarding water conservation measures and landscaping.	City to require and ensure compliance

Exhibit C:
Comments from the SJVAPCD



November 16, 2016

Melody N. Haigh
City of Hanford
Community Development Department
317 North Douty Street
Hanford, CA 93230

Project: Annexation 152, Pre-zone No. 2016-01, TPM No. 2016-02, & TTM 918

District CEQA Reference No: 20160755

Dear Ms. Haigh:

The San Joaquin Valley Unified Air Pollution Control District (District) has reviewed the project referenced above consisting of annexing 80.86 acres and pre-zoning as low-density residential with additional parcel splits and maps resulting in 127 single-family residential lots, a two-acre park, and a 5.15-acre basin, located south of Fargo Avenue between 12th and 13th Avenues, in Hanford, CA. The District offers the following comments:

1. Based on information provided to the District, project specific emissions of criteria pollutants are not expected to exceed District significance thresholds of 10 tons/year NOX, 10 tons/year ROG, and 15 tons/year PM10. Therefore, the District concludes that project specific criteria pollutant emissions would have no significant adverse impact on air quality.
2. Based on information provided to the District, at full build-out the proposed project would be equal to or greater than 50 residential dwelling units. Therefore, the District concludes that the proposed project would be subject to District Rule 9510 (Indirect Source Review).
 - District Rule 9510 is intended to mitigate a project's impact on air quality through project design elements or by payment of applicable off-site mitigation fees.
 - Any applicant subject to District Rule 9510 is required to submit an Air Impact Assessment (AIA) application to the District no later than applying for final discretionary approval.

Seyed Sadredin
Executive Director/Air Pollution Control Officer

Northern Region
4800 Enterprise Way
Modesto, CA 95356-8718
Tel: (209) 557-6400 FAX: (209) 557-6475

Central Region (Main Office)
1990 E. Gettysburg Avenue
Fresno, CA 93726-0244
Tel: (559) 230-6000 FAX: (559) 230-6061

Southern Region
34946 Flyover Court
Bakersfield, CA 93308-9725
Tel: 661-392-5500 FAX: 661-392-5585

- If approval of the subject project constitutes the last discretionary approval by your agency, the District recommends that demonstration of compliance with District Rule 9510 be made a condition of project approval. Information about how to comply with District Rule 9510 can be found online at: <http://www.valleyair.org/ISR/ISRHome.htm>.
3. The proposed project may be subject to District Rules and Regulations, including: Regulation VIII (Fugitive PM10 Prohibitions), Rule 4102 (Nuisance), Rule 4601 (Architectural Coatings), and Rule 4641 (Cutback, Slow Cure, and Emulsified Asphalt, Paving and Maintenance Operations). In the event an existing building will be renovated, partially demolished or removed, the project may be subject to District Rule 4002 (National Emission Standards for Hazardous Air Pollutants). The above list of rules is neither exhaustive nor exclusive. To identify other District rules or regulations that apply to this project or to obtain information about District permit requirements, the applicant is strongly encouraged to contact the District's Small Business Assistance Office at (559) 230-5888. Current District rules can be found online at: www.valleyair.org/rules/1ruleslist.htm.
 4. The District recommends that a copy of the District's comments be provided to the project proponent.

If you have any questions or require further information, please call Cherie Clark at (559) 230- 5940.

Sincerely,

Arnaud Marjollet
Director of Permit Services



For:
Brian Clements
Program Manager

AM: cc

Exhibit D:
KART Comments

Gabrielle deSilva

From: Pedreiro, Mark [Mark.Pedreiro@co.kings.ca.us]
Sent: Wednesday, March 22, 2017 3:52 PM
To: Darlene Mata
Cc: Gabrielle deSilva
Subject: Project Review Annexation 152
Attachments: 20170322123133584.pdf

Darlene,

KART would like a 10' x 12' concrete pad for a proposed bus stop and shelter. Pad would fit on the 10' landscape easement. Location would be on Centennial Dr. north of W. Dahli Way behind Lot 40. I attached tentative subdivision map with my handwritten notes. Thank you.

Mark Pedreiro

Facilities and Fleet Specialist
 Kings County Area Public Transit Agency
 610 W. 7th St.
 Hanford, CA 93230
 (559) 852-2624 direct line
 (559) 633-0280 cell
 (559) 582-5003 fax
mark.pedreiro@co.kings.ca.us

KART



Like us on Facebook!

RECEIVED MAR 07 2017

City of **HANFORD**
 CALIFORNIA 93230
 CITY OFFICES 317 NORTH DOUTY STREET



MAYOR
 DAVID G. AYERS
 VICE MAYOR
 SUE SORENGEN
 COUNCIL MEMBERS
 MARTIN DEVINE
 FRANCISCO RAMIREZ
 JUSTIN MENDES
 CITY MANAGER
 DARRELL L. PYLE
 CITY ATTORNEY
 ROBERT M. DOWD

March 3, 2017

PROJECT REVIEW - CONSULTATION NOTICE

For: Annexation 152, Prezone No. 2016-01, Tentative Parcel Map No. 2016-02,
 Tentative Tract Map 918, and Tentative Tract Map 919

The Community Development Department of the City of Hanford is requesting your comments regarding Annexation 152, Prezone No. 2016-01, Tentative Parcel Map No. 2016-02, Tentative Tract Map 918, and Tentative Tract 919, filed by John Zumwalt and San Joaquin Valley Homes. Annexation/Reorganization 152 and Prezone No. 2016-01: A request to annex 80.86 acres into the City of Hanford and prezone the annexed area as "R-1-6" Low-Density Residential, in accordance with the General Plan. The project involves simultaneous detachment of the property from the Kings River Conservation District and the Excelsior-Kings River Conservation District. Tentative Tract No. 918: A request to subdivide 47.51 acres into 130 single-family, low-density residential lots, a two-acre park, and a 5.02-acre basin. Tentative Tract No. 919: A request to subdivide 31.77 acres into 125 single-family, low-density residential lots. Tentative Parcel Map No. 2016-02: A request to divide a 47.51-acre parcel into two parcels (Parcel A: 27.48 acres; Parcel B: 20.03 acres) in an area proposed to be prezoned as "R-1-6" Low-Density Residential. The project is located south of Fargo Avenue, between 12th and 13th Avenue, west of the future Centennial Drive (APN 009-030-041, 009-030-148, and 009-030-149).

Based on an Initial Study, the Community Development Department has determined that the project described above would not have significant adverse impacts on the environment with the incorporation of mitigation measures. A Mitigated Negative Declaration has been prepared for the project. A public hearing pertaining to the project will be held by the City of Hanford Planning Commission on March 28, 2017 at 7:00 p.m. in the Council Chambers of the Civic Auditorium, 400 N. Douty Street. You may review the Mitigated Negative Declaration, Initial Study, mitigation measures, reference material and any comments received on the Mitigated Negative Declaration at City of Hanford, 317 N. Douty Street, Hanford, CA 93230. (Comment period March 3 – March 24, 2017).

Recommendations or suggestions for changes or mitigation measures requested by agencies having jurisdiction by law over natural resources affected by the project must be accompanied by a proposed reporting or monitoring program for those changes or measures in accordance with Public Resources Code Section 21081.6. It is requested that your comments, if any, be transmitted to this office by March 24, 2017 via mail to the address above or emailed to dmata@cityofhanfordca.com. Failure to comment will indicate approval of the project and no additional information will be sent to you. If you have any questions or concerns regarding this project please call me at (559) 585 2580.

COMMUNITY DEVELOPMENT DEPARTMENT 559-585-2580 • FACSIMILE: 559-583-1633

Attachment: Attachment 3 - City Council Resolution 17-29-R (Time Extension No. 2019-01)

Sincerely,

COMMUNITY DEVELOPMENT DEPARTMENT

Gabrielle de Silva

Gabrielle de Silva, Associate Planner

I ☒ do ☐ do not have comments regarding this Project

Marc Pedreiro


Signature


KART


Agency

3/22/17

Date







Curve Table			
Curve #	Length	Radius	Delta
C36	31.34'	20.00'	89° 46' 17"
C37	31.50'	20.00'	90° 13' 43"
C38	31.34'	20.00'	89° 46' 17"
C57	31.50'	20.00'	90° 13' 43"
C58	31.34'	20.00'	89° 46' 17"
C59	10.25'	70.00'	8° 23' 16"
C60	41.00'	70.00'	33° 33' 26"
C61	30.75'	70.00'	25° 10' 11"
C62	32.71'	50.00'	37° 29' 15"
C63	44.29'	50.00'	50° 45' 14"
C64	215.65'	50.00'	247° 06' 53"
C65	44.29'	50.00'	50° 45' 14"
C66	44.29'	50.00'	50° 45' 14"
C67	50.06'	50.00'	57° 21' 56"
C68	36.06'	70.00'	29° 31' 08"
C69	41.00'	70.00'	33° 33' 26"
C70	4.93'	70.00'	4° 02' 18"
C71	47.24'	30.02'	90° 09' 55"
C74	54.79'	600.00'	5° 13' 56"
C75	54.79'	600.00'	5° 13' 56"


Radial Table	
Line #	Bearing
L38	S00° 09' 15"E
L39	N89° 55' 32"W
L40	N89° 55' 32"W
L41	N00° 09' 15"W
L44	N89° 55' 32"W
L45	S00° 09' 15"E
L63	S89° 55' 32"E
L64	S00° 09' 15"E
L65	N00° 09' 15"W
L66	S89° 55' 32"E
L67	N89° 55' 32"W
L68	N81° 41' 13"E
L69	N56° 31' 02"E
L72	N56° 22' 05"W
L73	N60° 24' 23"W
L74	S89° 55' 32"E
L75	N00° 09' 15"W
L76	N89° 55' 32"W

COUNTY TRACT No. 919
UNIT I
CITY OF HANFORD
COUNTY OF KINGS, STATE OF CALIFORNIA

SURVEYOR'S NOTE
ALL CURVES ARE TANGENT UNLESS OTHERWISE NOTED

SPECIAL MONUMENT NOTE
SIDE AND REAR LOT CORNERS ADJACENT TO CENTENNIAL DRIVE AND FARGO AVENUE ARE MONUMENTED BY 1/2" REBAR, 30" LONG, WITH YELLOW PLASTIC TAG MARKED R.C.E. 21489, SET 6" DEEP, ON THE LOT LINE A DISTANCE OF 14.00' FROM THE SIDE OR REAR CORNER.
ALL FRONT CORNERS ADJACENT TO STREETS ARE MONUMENTED AS WITNESS CORNERS, SET ON THE P.U.E. LINE AND ARE MARKED BY 1/2" REBAR, 30" LONG WITH RED PLASTIC TAG STAMPED "CONT. PT., R.C.E. 21489", AND SET 6" ± DEEP, EXCEPT AS SHOWN OTHERWISE.

- LEGEND
- FOUND AND ACCEPTED MONUMENT AS NOTED
 - SET 1" I.P., 18" LONG, IN CONCRETE, 6" DEEP, WITH TAG R.C.E. 21489
 - ⊙ SET STEEL SPIKE WITH BRASS TAG, R.C.E. 21489, FLUSH IN PAVEMENT
 - △ SET 2"x24" GALV. I.P. WITH BRASS CAP STAMPED R.C.E. 21489 IN MONUMENT WELL, MONUMENT WELL SET FLUSH IN PAVEMENT
 - LOT CORNERS ARE MARKED WITH 1/2" REBAR, 30" LONG, TAGGED R.C.E. 21489, SET 6" DEEP
 - INDICATES 6' PUBLIC UTILITY EASEMENT
 - △ NOW OFFERED FOR DEDICATION AS PUBLIC STREETS
 - [] RECORD DATA PER PM 20-2 K.C.R.
 - [[] RECORD DATA PER PM 20-76, K.C.R.
 - () INDICATES STREET ADDRESSES
 - /// ACCESS DENIED TO CENTENNIAL DRIVE AND FARGO AVENUE
 - EXTERIOR BOUNDARY OF THE LAND WITHIN THE SUBDIVISION
 - K.C.R. KINGS COUNTY RECORDS
 - K.C.C.R. KINGS COUNTY CORNER RECORDS
- ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF



CIVIL ENGINEERS
ZUMWALT
HANSEN &
LAND SURVEYORS

SEE SHEET 4 FOR CONTINUATION

N. 1/4 COR. OF SEC. 22-18/21 FD. A
2-1/2" B.C. STAMPED LS 4375 FLUSH
& IN CONC. PER K.C.C.R. #1724

COUNTY TRACT No. 919
UNIT I
CITY OF HANFORD
COUNTY OF KINGS, STATE OF CALIFORNIA


SURVEYOR'S NOTE
ALL CURVES ARE TANGENT UNLESS OTHERWISE NOTED

SPECIAL MONUMENT NOTE
SIDE AND REAR LOT CORNERS ADJACENT TO CENTENNIAL DRIVE AND FARGO AVENUE ARE MONUMENTED BY 1/2" REBAR, 30" LONG, WITH YELLOW PLASTIC TAG MARKED R.C.E. 21489, SET 6" DEEP, ON THE LOT LINE A DISTANCE OF 14.00' FROM THE SIDE OR REAR CORNER.
ALL FRONT CORNERS ADJACENT TO STREETS ARE MONUMENTED AS WITNESS CORNERS, SET ON THE P.U.E. LINE AND ARE MARKED BY 1/2" REBAR, 30" LONG WITH RED PLASTIC TAG STAMPED "CONT. PT., R.C.E. 21489", AND SET 6" ± DEEP, EXCEPT AS SHOWN OTHERWISE.

- LEGEND
- FOUND AND ACCEPTED MONUMENT AS NOTED
 - SET 1" I.P., 18" LONG, IN CONCRETE, 6" DEEP, WITH TAG R.C.E. 21489
 - SET STEEL SPIKE WITH BRASS TAG, R.C.E. 21489, FLUSH IN PAVEMENT
 - △ SET 2"x24" GALV. I.P. WITH BRASS CAP STAMPED R.C.E. 21489 IN MONUMENT WELL, MONUMENT WELL SET FLUSH IN PAVEMENT
 - △ LOT CORNERS ARE MARKED WITH 1/2" REBAR, 30" LONG, TAGGED R.C.E. 21489, SET 6" DEEP
 - INDICATES 6' PUBLIC UTILITY EASEMENT
 - △ NOW OFFERED FOR DEDICATION AS PUBLIC STREETS
 - [] RECORD DATA PER PM 20-2 K.C.R.
 - [] RECORD DATA PER PM 20-76, K.C.R.
 - () INDICATES STREET ADDRESSES
 - /// ACCESS DENIED TO CENTENNIAL DRIVE AND FARGO AVENUE
 - EXTERIOR BOUNDARY OF THE LAND WITHIN THE SUBDIVISION
 - K.C.R. KINGS COUNTY RECORDS
 - K.C.C.R. KINGS COUNTY CORNER RECORDS


ALL DIMENSIONS ARE IN FEET AND DECIMALS THEREOF

Radial Table		Radial Table		Radial Table	
Line #	Bearing	Line #	Bearing	Line #	Bearing
L7	N89° 55' 32"W	L27	S00° 09' 15"E	L50	S89° 55' 32"E
L8	S00° 06' 24"E	L28	S84° 39' 25"E	L51	N89° 55' 32"W
L9	N00° 06' 24"W	L29	S56° 22' 05"E	L52	N88° 33' 11"W
L10	N89° 55' 32"W	L31	N89° 53' 36"E	L53	S00° 06' 24"E
L11	N89° 55' 32"W	L33	N89° 53' 36"E	L54	S88° 33' 11"E
L12	S00° 09' 15"E	L35	N56° 31' 02"E	L55	N87° 50' 25"W
L13	S89° 55' 32"E	L36	S85° 10' 37"W	L56	N81° 54' 05"W
L14	S00° 09' 15"E	L37	N89° 55' 32"W	L57	S80° 37' 57"E
L15	N00° 09' 15"W	L38	S00° 09' 15"E	L58	S00° 06' 24"E
L16	S00° 09' 15"E	L39	N89° 55' 32"W	L59	S80° 37' 57"E
L17	S03° 06' 18"W	L40	N89° 55' 32"W	L60	N79° 27' 00"W
L18	N05° 04' 41"E	L41	N00° 09' 15"W	L61	N83° 21' 25"W
L19	S05° 04' 41"W	L42	S00° 09' 15"E	L62	S84° 27' 34"E
L20	N04° 47' 46"E	L43	N89° 55' 32"W	L77	N89° 55' 32"W
L21	S00° 42' 49"W	L44	N89° 55' 32"W	L78	N82° 22' 32"W
L22	N00° 09' 15"W	L45	S00° 09' 15"E	L79	N87° 51' 18"W
L23	S00° 09' 15"E	L46	N00° 09' 15"W	L80	N89° 55' 32"W
L24	S00° 09' 15"E	L47	N89° 55' 32"W	L81	N89° 54' 23"W
L25	S89° 55' 32"E	L48	S89° 55' 32"E	L82	S89° 55' 32"E
L26	N89° 55' 32"W	L49	S00° 09' 15"E		



Curve Table			
Curve #	Length	Radius	Delta
C3	83.02'	630.00'	7° 33' 00"
C6	31.35'	20.00'	89° 49' 08"
C7	60.25'	630.00'	5° 28' 47"
C8	22.77'	630.00'	2° 04' 13"
C9	31.48'	20.00'	90° 10' 52"
C10	31.34'	20.00'	89° 46' 17"
C11	31.50'	20.00'	90° 13' 43"
C12	52.05'	570.00'	5° 13' 43"
C13	57.53'	630.00'	5° 13' 56"
C14	52.05'	570.00'	5° 13' 56"
C15	57.53'	630.00'	5° 13' 56"
C16	35.83'	630.00'	3° 15' 32"
C17	21.70'	630.00'	1° 58' 23"
C18	43.42'	570.00'	4° 21' 52"
C19	8.63'	570.00'	0° 52' 03"
C20	52.05'	570.00'	5° 13' 56"
C21	3.10'	630.00'	0° 16' 56"
C22	54.43'	630.00'	4° 57' 00"
C23	31.50'	20.00'	90° 13' 43"
C24	31.34'	20.00'	89° 46' 17"
C25	6.44'	70.00'	5° 16' 07"
C26	34.56'	70.00'	28° 17' 19"
C27	29.44'	50.00'	33° 44' 17"
C28	78.38'	50.00'	89° 49' 09"
C29	78.70'	50.00'	90° 10' 53"
C30	29.13'	50.00'	33° 22' 33"
C31	35.01'	70.00'	28° 39' 35"
C32	5.98'	70.00'	4° 53' 51"
C33	41.00'	70.00'	33° 33' 26"
C34	215.65'	50.00'	247° 06' 53"
C35	41.00'	70.00'	33° 33' 26"
C36	31.34'	20.00'	89° 46' 17"
C37	31.50'	20.00'	90° 13' 43"
C38	31.34'	20.00'	89° 46' 17"
C39	31.50'	20.00'	90° 13' 43"
C40	31.34'	20.00'	89° 46' 17"
C41	31.50'	20.00'	90° 13' 43"
C42	13.65'	570.00'	1° 22' 21"
C43	22.93'	630.00'	2° 05' 06"
C44	65.30'	630.00'	5° 56' 20"
C45	115.18'	630.00'	10° 28' 31"
C46	109.70'	600.00'	10° 28' 31"
C47	30.87'	20.00'	88° 26' 47"
C48	34.72'	20.00'	99° 28' 27"
C49	26.95'	630.00'	2° 27' 05"
C50	38.87'	570.00'	3° 54' 25"
C51	104.02'	570.00'	10° 27' 23"
C52	65.16'	570.00'	6° 32' 58"
C53	109.70'	600.00'	10° 28' 31"
C54	102.18'	630.00'	9° 17' 35"
C55	60.10'	630.00'	5° 27' 57"
C56	42.08'	630.00'	3° 49' 38"

CENTER OF SEC. 22-18/21 FD. A COTTON PICKER SPINDLE FLUSH WITH BRASS TAG STAMPED RCE 21489 PER PM 19-65 K.C.R.



SEE SHEET 4 FOR RADIAL LINE & CURVE TABLE


CIVIL ENGINEER
ZUMWALT
HANSEN &
LAND SURVEYORS

609 N. IRWIN ST. HANFORD, CA. 93230

PH. (559) 582-1056

FILE NO. 0762112

SHEET THREE OF FOUR SHEETS



OWNER'S STATEMENT

WE, THE UNDERSIGNED, DO HEREBY STATE THAT WE ARE THE OWNERS OF OR HAVE SOME RIGHT, TITLE, OR INTEREST IN AND TO THE REAL PROPERTY INCLUDED WITHIN THE SUBDIVISION SHOWN UPON THIS MAP AND THAT WE ARE THE ONLY PERSONS WHOSE CONSENT IS NECESSARY TO PASS A CLEAR TITLE TO SAID PROPERTY AND THAT WE CONSENT TO THE MAKING OF SAID MAP AND SUBDIVISION AS SHOWN ON THIS MAP AND DO HEREBY DEDICATE IN FEE TO PUBLIC USE ALL OF THE STREETS AND EASEMENTS AS SHOWN UPON THIS MAP. WE DEDICATE IN FEE TO PUBLIC USE FOR STREET PURPOSES THOSE CERTAIN STRIPS OF LAND DESIGNATED AS "FUTURE STREETS", RESERVING TO OURSELVES FOR THE USE OF OURSELVES AND THE SUCCESSIVE OWNERS, ALL ORDINARY USES OF SAID LAND UNTIL SUCH TIME AS THE PROPER LEGISLATIVE BODY SHALL ACCEPT DEDICATION OF, OR ACQUIRE ADDITIONAL RIGHT OF WAY, TO CONSTITUTE THE PERMANENT WIDTH AND/OR EXTENSIONS OF THOSE STREETS HAVING A PARTIAL WIDTH AND/OR DEAD-ENDING, AS SHOWN HEREON.

VALLEY SMALL BUSINESS DEVELOPMENT CORPORATION

BY: Debbie Raven
DEBBIE RAVEN, PRESIDENT/ CEO, BENEFICIARY

VALLEY SMALL BUSINESS DEVELOPMENT CORPORATION

BY: Debbie Raven
DEBBIE RAVEN, PRESIDENT/ CEO, BENEFICIARY

JANICE I MADRUGA SURVIVOR'S TRUST OF NOVEMBER 4, 2012

BY: Janice I. Alves
JANICE I. ALVES, TRUSTEE

LAWRENCE J MADRUGA BYPASS TRUST OF NOVEMBER 4, 2012

BY: Janice I. Alves
JANICE I. ALVES, TRUSTEE

A NOTARY PUBLIC OR OTHER OFFICER COMPLETING THIS CERTIFICATE VERIFIES ONLY THE IDENTITY OF THE INDIVIDUAL WHO SIGNED THE DOCUMENT TO WHICH THIS CERTIFICATE IS ATTACHED, AND NOT THE TRUTHFULNESS, ACCURACY, OR VALIDITY OF THAT DOCUMENT.

STATE OF CALIFORNIA

COUNTY OF TULARE

ON APRIL 4, 2019 BEFORE ME, J. STURGEON

NOTARY PUBLIC, PERSONALLY APPEARED DEBBIE RAVEN WHO PROVED TO ME ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO THE WITHIN INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE/SHE/THEY EXECUTED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPACITY(IES), AND THAT BY HIS/HER/THEIR SIGNATURE(S) ON THE INSTRUMENT THE PERSON(S), OR THE ENTITY UPON BEHALF OF WHICH THE PERSON(S) ACTED, EXECUTED THE INSTRUMENT.

I CERTIFY UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE STATE OF CALIFORNIA THAT THE FOREGOING PARAGRAPH IS TRUE AND CORRECT.

WITNESS MY HAND AND OFFICIAL SEAL

SIGNATURE J. Sturgeon

(PRINT NAME) J. STURGEON

MY COMMISSION NO. 2135614 MY COMMISSION EXPIRES 12-26-19

PRINCIPAL OFFICE IN COUNTY OF TULARE

A NOTARY PUBLIC OR OTHER OFFICER COMPLETING THIS CERTIFICATE VERIFIES ONLY THE IDENTITY OF THE INDIVIDUAL WHO SIGNED THE DOCUMENT TO WHICH THIS CERTIFICATE IS ATTACHED, AND NOT THE TRUTHFULNESS, ACCURACY, OR VALIDITY OF THAT DOCUMENT.

STATE OF CALIFORNIA

COUNTY OF TULARE

ON APRIL 4, 2019 BEFORE ME, J. STURGEON

NOTARY PUBLIC, PERSONALLY APPEARED JANICE I. ALVES WHO PROVED TO ME ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO THE WITHIN INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE/SHE/THEY EXECUTED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPACITY(IES), AND THAT BY HIS/HER/THEIR SIGNATURE(S) ON THE INSTRUMENT THE PERSON(S), OR THE ENTITY UPON BEHALF OF WHICH THE PERSON(S) ACTED, EXECUTED THE INSTRUMENT.

I CERTIFY UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE STATE OF CALIFORNIA THAT THE FOREGOING PARAGRAPH IS TRUE AND CORRECT.

WITNESS MY HAND AND OFFICIAL SEAL

SIGNATURE J. Sturgeon

(PRINT NAME) J. STURGEON

MY COMMISSION NO. 2135614 MY COMMISSION EXPIRES 12-26-19

PRINCIPAL OFFICE IN COUNTY OF TULARE

TAX COLLECTOR'S STATEMENT

THIS IS TO CERTIFY THAT THE PROVISIONS OF ARTICLE 8 OF CHAPTER 4 OF THE GOVERNMENT CODE HAVE BEEN COMPLIED WITH REGARDING DEPOSITS.

DATE: March 14, 2019

JAMES P. ERB, CPA; DIRECTOR OF FINANCE

BY: James O'Hara, Deputy

CIVIL ENGINEERS

ZUMWALT

HANSEN &

LAND SURVEYORS

609 N. IRWIN ST.

HANFORD, CA. 93230

PH. (559) 582-1056


FILE NO. 0762112

SHEET ONE OF FOUR SHEETS

COUNTY TRACT No. 919

UNIT I

CITY OF HANFORD,
COUNTY OF KINGS, STATE OF CALIFORNIA



VICINITY MAP
NOT TO SCALE

A NOTARY PUBLIC OR OTHER OFFICER COMPLETING THIS CERTIFICATE VERIFIES ONLY THE IDENTITY OF THE INDIVIDUAL WHO SIGNED THE DOCUMENT TO WHICH THIS CERTIFICATE IS ATTACHED, AND NOT THE TRUTHFULNESS, ACCURACY, OR VALIDITY OF THAT DOCUMENT.

STATE OF CALIFORNIA

COUNTY OF _____

ON _____ BEFORE ME, _____

NOTARY PUBLIC, PERSONALLY APPEARED _____ WHO PROVED TO ME ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO THE WITHIN INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE/SHE/THEY EXECUTED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPACITY(IES), AND THAT BY HIS/HER/THEIR SIGNATURE(S) ON THE INSTRUMENT THE PERSON(S), OR THE ENTITY UPON BEHALF OF WHICH THE PERSON(S) ACTED, EXECUTED THE INSTRUMENT.

I CERTIFY UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE STATE OF CALIFORNIA THAT THE FOREGOING PARAGRAPH IS TRUE AND CORRECT.

WITNESS MY HAND AND OFFICIAL SEAL

SIGNATURE _____

(PRINT NAME) _____

MY COMMISSION NO. _____ MY COMMISSION EXPIRES _____

PRINCIPAL OFFICE IN COUNTY OF _____

A NOTARY PUBLIC OR OTHER OFFICER COMPLETING THIS CERTIFICATE VERIFIES ONLY THE IDENTITY OF THE INDIVIDUAL WHO SIGNED THE DOCUMENT TO WHICH THIS CERTIFICATE IS ATTACHED, AND NOT THE TRUTHFULNESS, ACCURACY, OR VALIDITY OF THAT DOCUMENT.

STATE OF CALIFORNIA

COUNTY OF _____

ON _____ BEFORE ME, _____

NOTARY PUBLIC, PERSONALLY APPEARED _____ WHO PROVED TO ME ON THE BASIS OF SATISFACTORY EVIDENCE TO BE THE PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED TO THE WITHIN INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE/SHE/THEY EXECUTED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPACITY(IES), AND THAT BY HIS/HER/THEIR SIGNATURE(S) ON THE INSTRUMENT THE PERSON(S), OR THE ENTITY UPON BEHALF OF WHICH THE PERSON(S) ACTED, EXECUTED THE INSTRUMENT.

I CERTIFY UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE STATE OF CALIFORNIA THAT THE FOREGOING PARAGRAPH IS TRUE AND CORRECT.

WITNESS MY HAND AND OFFICIAL SEAL

SIGNATURE _____

(PRINT NAME) _____

MY COMMISSION NO. _____ MY COMMISSION EXPIRES _____

PRINCIPAL OFFICE IN COUNTY OF _____

ENGINEER'S STATEMENT

THIS MAP CONSISTING OF FOUR SHEETS WAS PREPARED BY ME OR UNDER MY DIRECTION AND IS BASED UPON A FIELD SURVEY IN CONFORMANCE WITH THE REQUIREMENTS OF THE SUBDIVISION MAP ACT AND LOCAL ORDINANCE AT THE REQUEST OF MR. JIM ROBINSON OF SAN JOAQUIN VALLEY HOMES, INC. IN THE MONTH OF AUGUST, 2018. I HEREBY STATE THAT ALL OF THE MONUMENTS ARE OF THE CHARACTER AND OCCUPY THE POSITIONS INDICATED OR THAT THEY WILL BE SET IN THOSE POSITIONS BEFORE TWO YEARS AFTER RECORDING OF THIS MAP AND THAT THE MONUMENTS ARE, OR WILL BE, SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACTED. THIS FINAL MAP SUBSTANTIALLY CONFORMS TO THE CONDITIONALLY APPROVED TENTATIVE MAP.

DATED THIS 5th DAY OF April, 2019.

John A. Zumwalt
JOHN A. ZUMWALT, R.C.E. 21489

**ACTING CITY SURVEYOR**

I, JOHN B. HARDIN, HEREBY STATE THAT I HAVE CAREFULLY EXAMINED THE ANNEXED MAP, THAT I AM SATISFIED THAT SAID MAP IS TECHNICALLY CORRECT, AND IN ACCORDANCE WITH SECTIONS 66425 THROUGH 66450, INCLUSIVE, OF THE GOVERNMENT CODE.

DATED THIS 23rd DAY OF APRIL, 2019.

John B. Hardin
JOHN B. HARDIN, R.C.E. 21753
ACTING FOR THE CITY OF HANFORD

**CITY ENGINEER'S STATEMENT**

I, JOHNATHAN L. DOVEL, HEREBY STATE THAT I HAVE CAREFULLY EXAMINED THE ANNEXED MAP, THAT THE SUBDIVISION AS SHOWN IS SUBSTANTIALLY THE SAME AS IT APPEARED ON THE TENTATIVE MAP, AND ANY APPROVED ALTERATIONS THEREOF AND THAT ALL PROVISIONS OF ANY LOCAL ORDINANCES AND SECTIONS 66425 THROUGH 66450 OF THE GOVERNMENT CODE APPLICABLE AT THE TIME OF APPROVAL OF THE TENTATIVE MAP HAVE BEEN COMPLIED WITH.

DATED THIS 25th DAY OF April, 2019.

Johnathan L. Dovel
JOHNATHAN L. DOVEL, CITY ENGINEER R.C.E. 62044

**CITY CLERK'S CERTIFICATE**

I HEREBY STATE THAT AT A REGULAR MEETING OF THE HANFORD CITY COUNCIL HELD ON THE 23 DAY OF April, 2019, AN ORDER WAS DULY AND REGULARLY MADE AND ENTERED APPROVING THIS MAP AND SUBDIVISION AND ACCEPTING, SUBJECT TO IMPROVEMENT, ON BEHALF OF THE GENERAL PUBLIC, THE STREETS AND EASEMENTS AS INCLUDED WITHIN THE BOUNDARIES OF THE SUBDIVISION SHOWN UPON THIS MAP.

DATED THIS 25 DAY OF APRIL, 2019.

Sarah Martinez
SARAH MARTINEZ, CITY CLERK

PLANNING COMMISSION CERTIFICATE

APPROVED BY THE HANFORD PLANNING COMMISSION IN ACCORDANCE WITH THE REQUIREMENTS OF

LAW IN DULY AUTHORIZED MEETING HELD March 28, 2017.

DATED THIS 25th DAY OF April, 2019.

Darlene R. Mata
DARLENE R. MATA, COMMUNITY DEVELOPMENT DIRECTOR

RECORDER'S CERTIFICATE

FEE BOOK NO. 1905933 FEE PAID \$ 14.00

RECORDED AT THE REQUEST OF ZUMWALT-HANSEN & ASSOCIATES, INC. ON THIS 26th DAY OF April, 2019, AT 41 MINUTES PAST 2 O'CLOCK IN VOLUME 710 OF LICENSED SURVEYORS' PLATS, AT PAGE 38, KINGS COUNTY RECORDS.

KRISTINE LEE, KINGS COUNTY RECORDER

BY: Michael R. Hankins
DEPUTY



AGENDA STAFF REPORT

MEETING DATE: 5/14/2019	AGENDA SECTION:
--------------------------------	------------------------

SUBJECT:

Continued item from Tuesday, April 23, 2019 -MUNICIPAL CODE AMENDMENT NO. 2019-01: a request by 198-43, LLC to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; furniture stores; and food catering.

See staff report, attached.

FISCAL IMPACT:

ATTACHMENTS:

Resolution No. 2019-07

Staff Report - MCA 2019-01.docx

Attachment 1 - Application

Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01)

Attachment 3 - Notice of Exemption 2019-19

RESOLUTION NO. 2019-07

A RESOLUTION OF THE PLANNING COMMISSION OF THE CITY OF HANFORD RECOMMENDING APPROVAL OF MUNICIPAL CODE AMENDMENT NO. 2019-01: a request by 198-43, LLC to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; furniture stores; and food catering

At a regular meeting of the Planning Commission of the City of Hanford duly called and held on May 14, 2019, on motion of Commissioner _____, seconded by Commissioner _____ and duly carried, the following resolution was adopted:

WHEREAS, a proposal to amend Title 17, Section 17.08.030 - Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; furniture stores; and food catering, **as attached in Exhibit A**, was presented to the Planning Commission; and

WHEREAS, on May 14, 2019, the Planning Commission of the City of Hanford conducted a public hearing, in accordance with Section 17.70.070 of the Hanford Municipal Code pertaining to Municipal Code Amendment 2019-01, and,

WHEREAS, comprehensive zoning regulations on the use of land and property lie within the City's police powers; and,

WHEREAS, the Planning Commission has carefully considered recommendations and testimony presented at the public hearing of May 14, 2019; and,

WHEREAS, Section 15061(b)(3) of the California Environmental Quality Act Guidelines categorically exempts the proposed project under the "General Rule"; and

THEREFORE BE IT RESOLVED, on the basis of the facts and evidence provided in the staff report and the written and oral evidence presented at the public hearing on May 14, 2019, the Planning Commission hereby is able to make the following recommendation in accordance with the required findings in Section 17.86.030:

In accordance with Section 17.86.030, before a zone change or text amendment may be approved, all of the following findings shall be made by the reviewing authority:

1. That the amendment is internally consistent with the goals, objectives, and policies of the General Plan and Zoning Ordinance;

Analysis: That each amendment request has been individually evaluated for consistency with the General Plan and recommended for approval if deemed consistent with the goals, objectives, and policies of the General Plan and Zoning Ordinance.

2. That the amendment would not be detrimental to the public health, safety, or welfare of the community;

Analysis: That each use proposed is currently permitted within the City of Hanford and would not be detrimental to the public health, safety, or welfare of the community.

3. That the amendment would maintain the appropriate balance of land uses within the City; and

Analysis: That jobs-housing balance is achieved by increasing opportunities for people to work and live in close proximity. The ratio is expressed as the number of jobs divided by the number of housing units. The jobs-housing balance is a general tool for analyzing where people work, where they live, and how effectively they can travel between the two. In the planning area, the existing jobs-housing balance ratio in 2013-2014 was 1.17. It is estimated that the implementation of the General Plan would increase the jobs-housing balance by 0.45 to 1.62, which would make the planning area a jobs-rich area. The proposed text amendments recommended for approval are all consistent with the General Plan and will not affect the City's ability to maintain an appropriate balance of land uses within the City.

4. That the anticipated land uses on the subject site would be compatible with existing and future surrounding uses.

Analysis: That each use was evaluated for consistency with the General Plan and Zoning Ordinance in order to ensure the proposed uses would be compatible with existing and future land uses within their prospective districts.

BE IT FURTHER RESOLVED that pursuant to Section 17.70 of the City of Hanford Zoning Ordinance, the Planning Commission forward to the City Council a recommendation that Municipal Code Amendment No. 2019-01, be approved.

PASSED AND ADOPTED at a regular meeting of the Planning Commission of the City of Hanford held on the 14th day of May 2019, by the following vote:

AYES:	Commissioners
NOES:	Commissioners
ABSTAIN:	Commissioners
ABSENT:	Commissioners

I, **Darlene R. Mata**, Secretary of the Planning Commission of the City of Hanford, do hereby certify the foregoing resolution was duly passed and adopted by the Planning Commission of the City of Hanford at a regular meeting thereof held on the 14th day of May 2019.

Darlene R. Mata, Secretary

Exhibit A:
Land Use Table and Definitions – amended per MCA 2019-01

Chapter 17.08

LAND USE TABLES

Sections:

- 17.08.010 Land use restriction.**
- 17.08.020 Residential land use table.**
- 17.08.030 Commercial, office, and industrial land use table.**
- 17.08.040 Addition of a use to land use tables.**

17.08.010 Land use restriction.

No structure, or any part thereof, shall be erected, enlarged, or reduced, nor shall any site or structure be used, designated, or intended to be used for any purpose or in any manner other than is included among the uses listed in the land use tables in this chapter as permitted, administratively permitted, or conditionally permitted in the zone district in which such structure, land, or site is located, except as otherwise authorized by this title.

17.08.020 Residential land use table.

A. The following table identifies which land uses are permitted by right, require a use permit, or are not allowed in the R-L-12, R-L-8, R-L-5, R-M, and R-H zones.

B. A “P” means that the use is permitted by right in that zone. A “C” means the use requires a conditional use permit in that zone. An “A” means the use requires an administrative use permit in that zone. A “T” means the use requires a temporary use permit in that zone. A blank box means the use is not allowed in that zone.

C. Land uses are grouped generally by type of use, and then listed alphabetically. The land use groups are Accessory and Support Uses; Residential Uses; and Other Uses. Use of the word “or” can mean either or both uses.

D. Land uses with specific land use standards shall meet the requirements found in the identified Section in the last column of the table.

Table 17.08.020

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
	Residential Uses						
1	Assisted living, skilled nursing, or hospice facility	C	C	C	C	C	
2	Bed and breakfast inn				C		17.60.040
3	Boarding house or rooming house			C	C	C	
4	Emergency shelter				C	C	
5	Employee housing for six (6) or fewer employees	P	P	P	P	P	
6	Hotel or motel						
7	Manufactured home on permanent foundation	A	A	A			17.60.090
8	Mobilehome, not within a mobilehome park						17.60.090
9	Mobilehome park				C		17.60.100
10	Multi-family dwelling, two (2) units per building (duplex)			C	P	P	17.10.020

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
11	Multi-family dwelling, three (3) or four (4) units per building (triplex or fourplex)			C	P	P	17.10.020
12	Multi-family dwelling, five (5) or more units per building				P	P	
13	Recreational vehicle park			C	C		
14	Residential care facility, up to six (6) persons	P	P	P	P	P	
15	Residential care facility, seven (7) or more persons	C	C	C	C	C	
16	Single-family dwelling, attached			P	P	P	
17	Single-family dwelling, detached	P	P	P	P	P	
18	Single-room occupancy (SRO)					C	
19	Supportive housing	P	P	P	P	P	
20	Transitional housing	P	P	P	P	P	
	Residential Accessory and Support Uses						

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
30	Accessory dwelling unit	A	A	A	A	A	17.60.030
31	Building ancillary to the main residential use	P	P	P	P	P	
32	Cottage food operation	A	A	A	A	A	17.60.050
33	Expansion of existing nonconforming residential use	C	C	C	C	C	
34	Guest house	P	P	P			
35	Home occupation	A	A	A	A	A	17.78
36	Keeping of household pets	P	P	P	P	P	Title 6
37	Raising of fruit, vegetables, and horticultural specialties for personal use	P	P	P	P	P	
38	Temporary caretaker's dwelling	T	T	T	T	T	
39	Temporary materials storage yard	T	T	T	T	T	
40	Temporary residential sales office	T	T	T	T	T	

Residential Zone Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
41	Other accessory or ancillary use or structure that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P	P	P	P	P	
	Other Uses						
50	Community center or facility	C	C	C	C	C	
51	Day care, up to eight (8) children	P	P	P	P	P	17.60.060
52	Day care, nine (9) to fourteen (14) children	A	A	A	A	A	17.60.060
53	Day care, over fourteen (14) children	C	C	C	C	C	17.60.060
54	Gas and electric transmission lines, electrical transmission and distribution substation, gas regulator station, communications equipment building, public service pumping station or elevated pressure tank	A	A	A	A	A	
55	Golf course or country club	C	C	C			
56	Mini-warehouse or self-storage facility		C				17.60.095

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
57	Park or playground	P	P	P	P	P	
58	Religious institution or facility	C	C	C	C	C	
59	School, private (kindergarten to 12 th grade)	C	C	C			
60	School, public (kindergarten to 12 th grade)	P	P	P			
61	Storm drainage basin, with or without a park	P	P	P	P	P	
62	Land uses listed in the Commercial, Office, and Industrial Zone Use Table (Section 17.10.040) that are not listed in this Residential Zone Use Table						

Attachment: Resolution No. 2019-07 (MCA 2019-01)

17.08.030 Commercial, Office, and Industrial Zone Use Table

A. The following table identifies which land uses are permitted by right, require a use permit, or are not allowed in the C-N, C-R, C-S, C-H, MX-N, MX-C, MX-D, O-R, O, I-L, I-H, AP, PF, and CO zones.

B. A “P” means that the use is permitted by right in that zone. A “C” means the use requires a conditional use permit in that zone. An “A” means the use requires an administrative use permit in that zone. A “T” means the use requires a temporary use permit in that zone. A blank box means the use is not allowed in that zone.

C. Land uses are grouped generally by type of use, and then listed alphabetically. The land use groups are Accessory and Support Uses; Eating and Drinking Establishment Uses; Education, Religious, and Assembly Uses; Manufacturing and Processing Uses; Office and Medical Uses; Public and Quasi-Public Uses; Recreation Uses; Residential Uses; Retail Uses; Service Uses; Transportation and Storage Uses; and Other Uses.

D. Land uses with specific land use standards shall meet the requirements found in the identified Section in the last column of the table.

Table 17.08.030

Commercial, Office, and Industrial Use Table															
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed															
Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones		
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO
	Accessory and Support Uses														
A1	Automated teller machine (ATM)	P	P	P	P	P	P	P		P	P	P		P	
A2	Caretaker residence or quarters					A	A	A	A		A	A	A		
A3	Cottage food operation					A	A	A	A						17.60.050

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A4	Day care primarily for children of employees on the same site as a permitted use	P	P	P	P	P	P	P	P	P	P	P	P	P		17.60.060
A5	Drive-thru pick-up window, not in conjunction with a restaurant	P	P	P	P	P	P	C								17.60.070
A6	Electric vehicle recharging facility	A	A	A	A	A	A	A		A	A	A		A		
A7	Food service primarily for employees on the same site as a permitted use	P	P	P	P	P	P	P		P	P	P	P	P		
A8	Games of skill or amusement, eight (8) or less	P	P	P	P	P	P	P			P			P		
A9	Games of skill or amusement, more than eight (8)	C	C	C	C	C	C	C			C			C		
A10	Home occupation					A	A	A	A				A			17.78
A11	Keeping of household pets					P	P	P	P				P			Title 6
A12	Keeping of large animals as pets												P			Title 6

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A13	Mobile vending or food truck	C	C	C	C	C	C	C		C	C	C				
A14	Outdoor advertising structure															
A15	Outdoor storage ancillary to and on the same site as a permitted use	P	P	P	P	P	P	P			P	P	P	P		17.60.120
A16	Temporary materials and/or equipment storage yard	T	T	T	T	T	T	T		T	T	T	T	P		
A17	Temporary sales office (including parking lot)					T	T	T								
A18	Vending machines	P	P	P	P	P	P	P		P	P	P	P	P		17.60.150
A19	Accessory or ancillary Office use; medical, dental, or optometry, that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P		P	P	P	P	P	P	P	P	P	P	P		

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A20	Other accessory or ancillary use or structure that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P	P	P	P	P	P	P	P	P	P	P	P	P	P	
	Eating and Drinking Establishment Uses															
B1	Artisan food and beverage production and sales	P	P	P	P	P	P	P			P					
B2	Bar, nightclub, or lounge		C	C	C		C	C								
B3	Brewpub	C	P	P	C	C	P	P								
B4	Microbrewery		C	P	C		C	C								
B5	Restaurant, full service	P	P	P	P	P	P	P								
B6	Restaurant, limited service with drive-thru pickup window	P	P	P	P	P	P	P								

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
B7	Restaurant, limited service without drive-thru pickup window	P	P	P	P	P	P	P								
	Education, Religious and Assembly Uses															
C1	Auditorium						P	P						P		
C2	Card room			C												
C3	Club, lodge, or private meeting hall			P			P	P								
C4	Carnival or circus		T	T	T		T	T								
C5	College or university, public or private		C	C			C	C						P		
C6	Convention or conference center				P		P	P								
C7	Funeral home or mortuary			P			C		P	C						
C8	Library, museum, or cultural facility						P	P								
C9	Pool hall or billiard parlor			C			C									

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
C10	Religious institution or facility			P			C	C		C	C					
C11	School, private (kindergarten to 12 th grade)													C		
C12	School, public (kindergarten to 12 th grade)													P		
C13	School; charter, trade, vocational, art, business, or professional		C	P			C	C	C	C	C			P		
C14	Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar	P	P	P		P	P	P		P	P					
C15	Theater, live or movie		P					P								
	Manufacturing and Processing Uses															
D1	Agricultural crop production											P	P	P	P	
D2	Agricultural products packing, packaging, preparing or processing										C	P	C			

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
D3	Animal raising												P			
D4	Brewery, winery, or distillery										C	C				
D5	Hazardous waste facility											C				
D6	Industrial or manufacturing facility, heavy											P				
D7	Industrial or manufacturing facility, light										P	P				
D8	Cannabis cultivation, manufacture, distribution, transportation and laboratory testing											C				See Chapters 5.56 and 17.69
D9	Meat packing or slaughterhouse											C				
D10	Mining, quarry, or sand and gravel excavation											C	C			
D11	Research and development facility			P	C					P	P	C				
	Office and Medical Uses															

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses	Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
	C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
E1 Business support service		P	P			P	P	P	P						
E2 Call center		C		C					C						
E3 Communications broadcasting or media studio			P			C	P		P	C					
E4 Laboratory; general, medical or dental		C	P	C		P	C		P	C					
E5 Hospital, general or psychiatric									P				P		
E6	Office; medical, dental, or optometry	P		P		P	P	P	P	P					
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P					
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P					
	Over 6,000 sq. ft.	P		P		P	P	P	P	P					
E7	Office; professional or commercial	P		P		P	P	P	P	P					
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P					
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P					

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
	Over 6,000 sq. ft.	P		P		P	P	P	P	P						
E8	Pharmacy	P	P	P		P	P	P		P						
E9	Urgent care center or other walk-in clinic	P	C	C		P	P	P		P						
	Public and Quasi-Public Uses															
F1	Cemetery													P		
F2	Community center or facility	P		P		P	P	P								
F3	Community garden			P		P	P	P		P			P	P		
F4	Day care, up to eight (8) persons					P	P	P	P							17.60.060
F5	Day care, nine (9) to fourteen (14) persons			C		A	A	A	A							17.60.060
F6	Day care, over fourteen (14) persons			C		C	C	C	C							17.60.060

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
F7	Electrical distribution and transmission and substation, gas regulator station, communications equipment building, public service pumping station or elevated pressure tank	A	A	A	A	A	A	A	A	A	A	A	A	A	A	
F8	Fairgrounds													P		
F9	Government office; local, state, or federal							P		P				P		
F10	Post office						P	P		P				P		
F11	Public corporation yard, utility yard, or vehicle and heavy equipment maintenance and storage yard										C	P	P	P		
F12	Public safety facility or station	P	P		P	P	P	P			P		P	P		
F13	Social service office, assistance center, or guidance center							P		C						
F14	Storm drainage basin, with or without a park	P	P	P	P	P	P			P	P	P	P	P	P	

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
F15	Wireless communication facility (WCF)		C	P	P		C	C		C	P	P		P		17.62
	Recreation Uses															
G1	Athletic complex or ball field													P		
G2	Commercial recreation facility, indoor	C	C	P	P	C	P	C			C					
G3	Commercial recreation facility, outdoor				C						C	C	C	C		
G4	Golf course or country club												C	C		
G5	Health or fitness facility, large		C	P	C		P	P		C						
G6	Health or fitness facility, small	P	P	P	P	P	P	P		P	C					
G7	Park or playground						P						P	P		
	Residential Uses															
H1	Assisted living, skilled nursing, or hospice facility					C	C	C	C							

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
H2	Bed and breakfast inn				C		C	C	C							17.60.040
H3	Boarding or rooming house				C	C	P	P								
H4	Emergency shelter								P					P		
H5	Employee housing for six (6) or fewer employees					P	P	P	P							
H6	Hotel or motel		C	C	P		P	P								
H7	Live/work facility			P		P	P	P	P							
H8	Mobile home park															17.60.100
H9	Multi-family dwelling, two (2) units per building (duplex)					P	P	P	P							
H10	Multi-family dwelling, three (3) or four (4) units per building (triplex or fourplex)					P	P	P	C							

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
H11	Multi-family dwelling, five (5) or more units per building					P	P	P								
H12	Recreational vehicle park				C						C					
H13	Residential care facility					P	P	P	P							
H14	Residential dwelling located in same building with office or commercial use			C		P	P	P	P				P			
H15	Single-family dwelling, attached					P	P	P								
H16	Single-family dwelling, detached					P	P	P	P				P			
H17	Single-room occupancy (SRO)						P	P	P							
H18	Supportive housing					P	P	P	P				P			
H19	Transitional housing					P	P	P	P				P			
	Retail Uses															
I1	Adult entertainment establishment		A	A			A									17.62

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I2	Auction or sales house			P			P	P								
I3	Auction or sales yard			C							C					
I4	Automobile and pick-up sales, new and used			P	P			P								17.60.140
I5	Automobile and pick-up sales, used only			P	P											17.60.140
I6	Boat, recreational vehicle (RV), and truck sales			P	C											
I7	Building materials and supply or home improvement store		P	P			P	P			C					
I8	Convenience store, with or without fuel sales	P	P	P	P	P	P	P			C					
I9	Farm or construction equipment sales or service			P	C											
I10	Farmers market		A	A				A						A		
I11	Feed and seed store			P							P					
I12	Food market	P	P	P	P	P	P	P								

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I13	Food produce stand	A	A	A	A	A	A			A	A	A	A	A		
I14	Fuel sales, fleet or cardlock			P	P						P	P		P		
I15	Fuel sales, retail	P	P	P	P	P	P	P			C					
I16	Furniture store		P				P	P								
I16	Furniture store with less than 15,000 sq.ft. of floor space devoted to the display and sale of furniture		P				P	P								
I17	Furniture store with 15,000 to 20,000 sq.ft. of floor space devoted to the display and sale of furniture		C				C	P								
I18	Furniture store with over than 20,000 sq.ft. of floor space devoted to the display and sale of furniture							P								
I19 I17	Garden shop		P	P			P	P								

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I20 I18	Landscape nursery			P			C				C	C	C			
I21 I19	Liquor store	P	P	P	P	P	P	P								
I22 I20	Manufactured home sales yard			C									C			
I23 I21	Cannabis dispensary or sales															See Chapters 5.56 and 17.69
I24 I22	News, magazine or flower stand, outdoor				C			P								
I25 I23	Optical retailers		P				P	P								
I26 I24	Pawn shop			P				P								
I27 I25	Pet store	P	P	P		P	P	P								
I28 I26	Retail sales store	P	P	P	P	P	P	P								Also see Lines I16, I17, and I18 related to sales of furniture

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I29 I27	Retail sales solely via internet, direct mail, or telephone			P			P		C	C						
I30 I28	Secondhand or thrift store			P				P								
I34 I29	Swap meet or flea market			C							C	C		C		
I32 I30	Tobacco or smoke shop		C	P	P		P	P								
	Service Uses															
J1	Ambulance service			P			P			C						
J2	Bank or credit union, main branch							P								
J3	Bank or credit union, secondary branch	P				P	P	P								
J4	Barber shop, hair salon, nail care, massage therapy, or day spa	P	P	P	P	P	P	P	C	C	C					
J5	Car wash, automatic or full service	C	C	P	P	C	P									
J6	Car wash, self-service			C	C		C									

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J7	Carpet cleaning and dyeing			P			C				P					
J8	Construction materials recycling											C		P		
J9	Copy, printing, or mailing service	P	P	P	P	P	P	P		P	P					
J10	Crematorium or columbarium			C			C				C					
J11	Dry cleaning or laundromat	P		P	P	P	P	P								
J12	Equipment rental yard			P							P					
J13	Exterminator or pest control service			P			P	C			P	P				
J14	Food catering	P	P	P		P	P	P	C							
J15	Fortunetelling			P							P					
J16	Fuel distributing			P							P	P				
J17	Kennel or animal boarding			P	P		C				C					
J18	Linen, diaper, or uniform supply service			P							P	P				

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J19	Motor vehicle repair or service, major			P	P		C				P	P				
J20	Motor vehicle repair or service, minor		C	P	P		P	C			P					
J21	Payday lenders or check cashing establishment			C			C	C								
J22	Pet grooming	C	C	P		C	P	C								
J23	Photography studio	P	P	P		P	P	P	C	P						
J24	Recycling, small collection facility (CRV only)	P	P	P	P	P	P	P			P			P		
J25	Recycling, large collection facility			C							P	P		P		
J26	Recycling, processing or sorting facility										C	C				
J27	Repair shop, large appliance or equipment			P			P	C								
J28	Repair shop, small appliance or equipment	C		P		C	P	P	C							
J29	Shooting range, indoor			C							C		C	C		
J30	Shooting range, outdoor															

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J31	Specialty construction or trade service			P							P	P				
J32	Tailoring or clothing alterations	P		P		P	P	P	P							
J33	Tattooing or body art			C			C	P								
J34	Veterinary clinic or office		C	P			C			P						
J35	Veterinary hospital										C		C			
	Transportation and Storage Uses															
K1	Airport or heliport												P	P		
K2	Bus, transit, or train station							P						P		
K3	Cold storage or ice house			C							P	P	P			
K4	Food locker			P							P		P	P		
K5	Junk yard, wrecking yard, or salvage facility											C				
K6	Mini-warehouse or self-storage facility			P	C		C				C					

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
K7	Parking facility, off-site		C	C				C		C						
K8	Truck stop or travel center				C											
K9	Trucking or transportation terminal											P				
K10	Vehicle impound yard			C							P	P				
K11	Warehouse or distribution center										P	P				
	Other Uses															
L1	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that is permitted in the same zone	P	P	P	P	P	P	P	P	P	P	P	P	P	P	

Attachment: Resolution No. 2019-07 (MCA 2019-01)

Commercial, Office, and Industrial Use Table																
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed																
Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
L2	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that requires an administrative use permit in the same zone	A	A	A	A	A	A	A	A	A	A	A	A	A	A	
L3	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that requires a conditional use permit in the same zone	C	C	C	C	C	C	C	C	C	C	C	C	C	C	

Attachment: Resolution No. 2019-07 (MCA 2019-01)

17.08.050 Addition of a use to land use tables.

Upon an application or on its own initiative and pursuant to Chapter 17.86, the City Council may add a use to the land use tables established in this chapter if the Council makes all of the following findings:

- A. That the addition of the use to the land use table will be in accordance with the purposes of this title and of the zone district or districts in which the use will be permitted;
- B. That the use has similar basic characteristics as the present uses allowed in the district;
- C. That the use will not generate a noticeably greater amount of odor, dirt, smoke, noise, vibration, illumination, glare, unsightliness or any other objectionable influence or hazard than

the amount normally created by any of the other uses permitted in the district or districts in which the use will be permitted.

D. That the establishment of the use in the zone district or districts in which it will be permitted will not be detrimental to the public health, safety or welfare;

Chapter 17.96

DEFINITION OF LAND USES

Sections:

17.96.010 Purpose.

17.96.020 Land use definitions.

17.96.010 Purpose.

The purpose of this chapter is to establish definitions for the identified land uses in this title.

17.96.020 Land use definitions.

The following land use definitions apply to this title. The item number in parenthesis at the end of the definition is not a part of the definition, but refers to the line item of that land use in Table 17.18.020 and Table 17.18.030.

“Accessory building or structure” means a structure which is subordinate to and the use of which is customarily incidental to, that of the main building, structure or use on the same site, including patio covers. If any accessory building is attached to the main building by a common wall or a connecting roof, such accessory building shall be deemed to be a part of the main building. (41) (A20)

“Accessory use” means a use incidental, related, appropriate and clearly subordinate to the main use of the site or building, and accessory use does not alter the principal use of the site. (41) (A20)

Adult day health care center. See Residential care facility. (H13)

“Adult entertainment establishment” means any adult bookstore, adult hotel or motel, adult motion picture arcade, adult motion picture theater, cabaret, sexual encounter establishment, adult model studio or any other business or establishment that offers its patrons services or entertainment characterized by an emphasis on matter depicting, describing or relating to "specified sexual activities" or "specified anatomical areas," but not including those uses or activities, the regulation of which is preempted by state law. (11)

“Agricultural crop production” means the use of land for farming, horticulture, floriculture, viticulture, apiaries, tree and sod farms, animal and poultry husbandry, and accessory activities, including, but not limited to, storage, associated maintenance of equipment, harvesting of crops or feeding of animals and excluding dairying, stockyards, slaughtering or commercial food processing. Pursuant to Health and Safety Code Section 17021.6, any employee housing consisting of no more than thirty-six (36) beds in a group quarters or twelve (12) units or spaces designed for use by a single family or household shall be deemed an agricultural land use for zoning purposes. (D1)

“Agricultural products packing, packaging, preparing or processing” means a facility performing any processing or packaging of crops after harvest, whether or not value is added, to prepare them for market on-site or for further processing and packaging elsewhere, including but not limited to: alfalfa and hay cubing; corn shelling; drying of corn, rice, hay, fruits or vegetables; pre-cooling and packaging of fresh or farm-dried fruits and vegetables; grain cleaning and custom grinding; custom grist mills; custom milling of flour, feed and grain; sorting, grading and packing of fruits and vegetables; canning, freezing, or preserving fruits and vegetables; tree nut hulling and shelling; and alcohol fuel production. Any of the above activities performed in the field with mobile equipment not involving permanent buildings are included under “Agricultural crop production.” It includes related accessory uses such as offices, laboratories, retail sales of agricultural products produced on the premises or off-site by the operator, retail sales of agriculture-related promotional and/or educational items, and facility tours. Does not include “wineries,” “commercial marijuana activity,” “commercial cannabis activity,” “marijuana cultivation,” or sorting and packing activities conducted within a permitted roadside stand. (D2)

“Airport or heliport” means an area of land, water or a structural surface that is used for the landing and takeoff of airplanes and/or helicopters, and any appurtenant areas or buildings that are used for maintenance, servicing, or storing of aircraft, and for services provided to pilots or passengers. (K1)

“Ambulance service” means the provision by a licensed ambulance provider of ground transportation of a sick or injured person in a specially designed and equipped vehicle which includes a trained ambulance attendant who is licensed or certified as required by state law. (J1)

“Animal raising” means the care and breeding of domestic agricultural animals such as chickens and other fowl, horses, goats, or cows. (D3)

Art school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Artisan food and beverage production and sales” means small scale production and/or preparation of food and/or beverages made on site with minimal automated processes involved and may include direct sales to consumers and product tasting. This definition includes uses such as small batch food producers and bakeries, small batch candy shops, cheese makers, and herbal remedies. The definition does not include production of beer, wine, or other alcoholic beverages. (B1)

Assembly, place of. See Club, lodge, or private meeting hall (C3) or Religious institution or facility. (C10)

“Assisted living, skilled nursing, or hospice facility” means a residential complex providing skilled nursing care on an intermittent, extended, or continuous basis to residents, with staff personnel and programs to assist residents with many activities of daily living. Units may or may not have kitchens, and meals can also be provided in a central location. (1) (H1)

“Athletic complex or ball field” means a field, outdoor court, outdoor swimming pool, stadium or group of these used for sporting activities such as baseball, softball, football, basketball, swimming, or other sports, and is not operated as a commercial enterprise. (G1)

“Auction or sales house” means a fully enclosed establishment where items are offered for sale through competitive bidding. It does not include foreclosure, real estate or personal property sales conducted upon the site of the estate, foreclosed or for sale property or property belonging

to the personal property owner. It does not include “Swap meet or flea market” or “Auction or sales yard.” (I2)

“Auction or sales yard” means an outdoor or open air facility where items are offered for sale through competitive bidding. Items typically include motor vehicles, heavy equipment, items of an industrial nature, livestock, or items not normally found within retail stores. It does not include “Swap meet or flea market.” It may also have an indoor component similar to an Auction or sales house. (I3)

“Auditorium” means a large room or building used for public gatherings typically open to the general public to watch and/or listen to a performance, speech, or concert. It does not include “Theater, live or movie.” (C1)

“Automated teller machine (ATM)” means a computer terminal that takes the place of a human bank teller and allows the user to access basic bank services, such as making deposits and cash withdrawals, from remote locations. (A1)

“Automobile and pick-up sales, new and used” means an open area that can include buildings, other than a street, used for the display, sale, or rental of new and used automobiles and pick-ups along with incidental repairs and servicing of automobiles or pick-ups. (I4)

“Automobile and pick-up sales, used only” means an open area or building, other than a street, used for the display, sale or rental of used automobiles and pick-ups and where no repair work is done except minor incidental repairs and servicing of automobiles or pick-ups to be displayed, sold or rented on the premises. (I5)

Automobile service station. See Fuel sales, retail, Motor vehicle repair or service, minor, and Motor vehicle repair service, major. (H6) (J18) (J19)

Automobile wrecking yard. See Junk yard, wrecking yard, or salvage facility. (K5)

Ball field. See Athletic complex or ball field. (G1)

“Bank or credit union, main branch” means an institution providing retail banking services that is the main branch in the city. This classification includes only those institutions engaged in the on-site circulation of money, including credit unions, but excluding a payday lender or check-cashing establishment. For administration, headquarters, or other offices of banks and credit unions without retail banking services with on-site circulation of money see Office, professional or commercial. (J2)

“Bank or credit union, secondary branch” means an institution providing retail banking services that is a secondary or satellite branch in the city and either does not provide loan officers on site or only provides merchant bank services. This classification includes only those institutions engaged in the on-site circulation of money, including credit unions, but excluding a payday lender or check-cashing establishment. For administration, headquarters, or other offices of banks and credit unions without retail banking services with on-site circulation of money see Office, professional or commercial. (J3)

“Bar, nightclub, or lounge” means an establishment that provides alcoholic beverages for consumption on the site and may or may not provide food service, and that may provide live entertainment and/or dancing. This use typically requires an ABC Type 40, 42, 48, 60, or 61 license. (B2)

“Barbershop, hair salon, nail care, massage therapy, or day spa” means an establishment that provides personal care treatments or massage therapy of hair, skin, nails, and/or face where overnight accommodations are not provided. This use includes the application of permanent facial makeup, but does not include other forms of tattooing or body art application. (J4)

“Bed and breakfast inn” means a transient lodging establishment that is predominantly residential in character, is primarily engaged in providing overnight or otherwise temporary lodging for the general public, and where a breakfast meal is customarily included in the lodging rate. Alcoholic beverages served to overnight guests typically requires an ABC Type 67 license. (2) (H2)

“Boarding house or rooming house” means a structure where residents typically rent by the room, and where meals are typically provided. This definition does not include assisted living, skilled nursing, or hospice facility, bed and breakfast inn, or residential care facility. (3) (H3)

“Boat, recreational vehicle (RV), and truck sales” means an open area or building, other than a street, used for the display, sale, or rental of new or used boats, campers, camper trailers, recreational vehicles, trucks over one-ton class, and other vehicles or sporting equipment of similar size, and where no repair work is done except minor incidental repairs and servicing of vehicles and equipment to be displayed, sold or rented on the premises. (I6)

“Brewery, winery, or distillery” is an establishment that manufactures beer, wine, distilled spirits or similar alcoholic beverages, including processing, storage, aging, packaging, bottling, and shipping. Consumption can occur on or off the site in accordance with the establishment’s ABC license restrictions, and can include tasting facilities and/or a restaurant. This use typically requires an ABC Type 01, 02, 03, or 04 license. (D4)

“Brewpub” means a restaurant that also brews limited amounts of beer (less than 5,000 barrels) for consumption on the site. This use typically requires an ABC Type 75 license. (B3)

“Building materials and supply or home improvement store” means an establishment selling a mix of lumber, building materials, tools, residential appliances, nursery items, and home furnishings. (I7)

“Bus, transit, or train station” means a terminal facility where transit vehicles load or unload passengers, along with supporting services such as ticket sales and waiting areas. Bus, transit, or train station does not include a transit stop along a route in the public right-of-way where no additional services are provided. (K2)

Business school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Business support service” means an establishment providing primarily other businesses with a mix of services that can include word processing, desktop publishing, spreadsheet design, telephone answering, mail receiving and forwarding, packing and shipping, bookkeeping, and photocopying, and can include indoor storage rental, and/or small office space rental when provided with these services. (E1)

“Call center” means an office used primarily for receiving or transmitting a large volume of requests by telephone to administer product support or information inquiries from consumers or to conduct telemarketing, solicitation of charitable or political donations, debt collection, or market research. (E2)

“Car wash, automatic or full service” means a facility for washing vehicles using conveyORIZED and/or mechanized equipment where the washing of the vehicle is performed by equipment, the facility’s employees, or both. (J5)

“Car wash, self-service” means a facility for washing vehicles where the user of the vehicle uses handheld equipment, typically coin-operated, to wash the vehicle. (J6)

“Card room” means an establishment providing legal gambling combined with card games, and can include a restaurant, bar, or other ancillary entertainment. (C2)

“Caretaker residence or quarters” is a residence that is accessory to a primary use of the site, for housing a persons or persons who are tasked with caring for or securing the site on a part-time or full-time basis. Second dwelling unit includes caretaker residence or quarters in residential zones. (A2)

“Carnival or circus” means a temporary outdoor amusement center, bazaar or fair, either involving use of special purpose equipment or conducted by professional operators, or both, and where activities include such things as rides, exhibitions, food service, sales, or small-scale games. Carnival or circus does not include a non-profit event sponsored by a local school or religious institution. (C4)

“Carpet cleaning and dyeing” means an establishment that provides for the cleaning and dyeing of rugs, carpet, and upholstery. (J7)

“Cemetery” means land and facilities used or intended to be used for the burial or interment of the dead, and includes a columbarium, crematorium, mausoleum and/or mortuary when operated in conjunction with and within the boundary of the facility. (F1)

Charter School. See School, charter, trade, vocational, art, business, or professional. (C13)

Check cashing establishment. See Payday lender or checking cashing establishment. (J20)

Child care center. See Day care facility. (A4) (F4) (F5) (F6)

“Club, lodge, or private meeting hall” means a large room or building used for public gatherings where membership or invitation is typically required to attend. It can include a dance floor, lodge rooms, conference rooms, dining rooms, drinking establishments for members and their guests only, and exhibit rooms. Alcoholic beverage service to members and their guests typically requires an ABC Type 51, 52, or 57 license. (C3)

“Cold storage or ice house” means a facility for the storage food or other items in an artificially cooled place for the purpose of preservation, and/or for producing large amounts of ice. (K3)

“College or university, private or public” means a school or group of schools that provides post-secondary education usually resulting in a degree. (C5)

Clinic, medical. See Urgent care center or other walk-in clinic. (E9)

“Commercial recreation facility, indoor” means indoor recreational facilities that are operated as a business and open to the general public for an entry fee or pay per use. Examples include indoor uses such as, but are not limited to, a bowling alley, bounce house, skating rink, batting cage, miniature golf, swimming pool, climbing wall, arcade, and similar uses. Food and beverage service can be provided as an ancillary use. (G2)

“Commercial recreation facility, outdoor” means outdoor recreational facilities that are operated as a business and open to the general public for an entry fee or pay per use. Examples include outdoor uses such as, but are not limited to, a batting cage, miniature golf, water slide, go-cart racing, and similar uses. Food and beverage service can be provided as an ancillary use. (G3)

Communications equipment building. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Community center or facility” means an assembly building used typically for non-profit social, recreational, and cultural activities. (F2)

“Community garden” means an area of land managed and maintained by an individual or group to grow and harvest food and horticultural products for personal or group consumption. The garden may be divided into separate garden plots for cultivation by one or more individuals or may be farmed collectively by members of the group. (F3)

“Construction materials recycling” means a yard or facility that collects leftover construction materials that may be recycled or reused as an alternative to disposal in landfill site. Examples of construction materials include lumber, drywall, masonry, cabinets, metals and appliances, cardboard and paper, asphalt roofing, plastic and vinyl, doors and windows, tubs, sinks, and toilets. (J8)

“Convenience store, with or without fuel sales” means an establishment with extended operating hours and in a convenient location, stocking a limited range of household goods and groceries. Retail fuel sales may or may not also be provided. (I8)

“Convention or conference center” means facilities designed and used for conventions, conferences, seminars, trade shows, product displays, and other events in which groups gather to promote and share common interests. Convention centers typically have at least one auditorium and may also contain concert halls, lecture halls, meeting rooms, and conference rooms, as well as accessory uses such as facilities for food preparation and serving and administrative offices. Convention or conference center does not include conference rooms that may be an ancillary use in a hotel and motel. (C6)

“Copy, printing, or mailing service” means an establishment providing printing, photocopying, engraving, binding, packaging, mailing and related services to both businesses and individuals. (J9)

“Cottage Food Operation” means a home-based business involving the preparation and/or packaging of certain foods in private-home kitchens for sale primarily by the resident family. (A3)

“Crematorium or columbarium” is a structure or building substantially exposed above ground intended to be used for the cremation and/or interment of the cremated remains of a deceased person or animal. (J10)

“Day care facility” means a facility providing supervision, feeding and nonmedical care of persons, usually but not necessarily children, for a time period of less than twenty-four (24) hours. Day care facilities are further divided into the following categories: up to eight (8) persons, nine (9) to fourteen (14) persons, and over fourteen (14) persons. (A4) (F4) (F5) (F6)

Day spa. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Drive-thru pick-up window, not in conjunction with a restaurant” means the ancillary use of a window or other opening in the wall of building through which goods or services are provided directly to customers in motor vehicles. Examples of non-restaurant establishments with this ancillary use can include banks, pharmacies, and dry cleaners. (A5)

“Dry cleaning or laundromat” means an establishment providing laundry, dry cleaning, and other related services for individual customers on a pick-up and drop-off basis or where with coin-operated washing and drying machines are available for customer use. (J11)

Duplex. See Multi-family dwelling. (10) (H9) (H10) (H11)

Dwelling, multiple-family. See Multi-family dwelling. (10) (11) (12) (H9) (H10) (H11)

Dwelling, single-family. See Single-family dwelling. (16) (17) (H15) (H16)

“Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank” means the assembly of above-ground buildings or equipment on a separate lot that is part of a system for the distribution or transmission of electric power, natural gas, domestic water, or communications. Wireless communication facilities are not included in this definition. (F7)

“Electric vehicle recharging facility” means one or more publicly available parking spaces served by electric vehicle service equipment, and is typically an ancillary use in a parking garage or parking lot. (A6)

Elevated pressure tank. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Emergency Shelter” means a facility providing housing with minimal supportive services for homeless persons that is limited to occupancy of six months or less where housing is not denied because of an inability to pay. (4) (H4)

“Employee housing” means a residential structure providing accommodations for six (6) or fewer farmworkers pursuant to Health and Safety Code Section 17021.5. (5) (H5)

“Equipment rental yard” means an establishment offering a wide variety of large equipment or tools for rent, much of which is stored outdoors when not being used. (J12)

“Exterminator or pest control service” means an establishment specializing in the elimination of vermin, insects, or other similar pests from a building or grounds, especially by the controlled application of toxic chemicals. (J13)

“Fairgrounds” means an area with indoor and outdoor facilities where fairs, circuses, or exhibitions are held. (F8)

“Farmers market” means a facility or area where several farmers or growers gather on a periodic basis to provide fresh fruits, vegetables, or other locally-grown agricultural products directly to consumers. (I10)

“Feed and seed store” means an establishment that provides feed, seed, and animal and agricultural supplies primarily in bulk quantities. (I11)

“Food catering” means an establishment that prepares and delivers food and beverages for off-site consumption, typically at a special event, without provision for on-site pickup or consumption. (J14)

“Food locker” means an establishment that rents lockers, compartments, or space for the storage of frozen food. A food locker may also include the preparation or dressing of animal carcasses for consumption, but does not include the slaughtering of animals. (K4)

“Food market” means an establishment that provides a wide variety of fresh produce and meat, canned and packaged food items, small household goods, and similar items that are typically consumed and used off premises. It can also contain a section where prepared foods are sold and consumed on site. (I12)

“Food produce stand” means an area or building set aside for the sale of agricultural produce that is grown primarily on the site. (I13)

“Fortune telling” means an establishment where people’s fortunes are predicted through the use of astrology, card reading, numerology, etc. (J15)

“Fuel distributing” means a facility that is a base of operations for the bulk distribution of gasoline, propane, butane, or other another site. (J16)

“Fuel sales, fleet or cardlock” means an establishment that is typically unattended and provides gasoline, propane, diesel fuel, and/or other liquid or gaseous fuels mainly for commercial fleet vehicles. (I14)

“Fuel sales, retail” means an establishment that provides gasoline, propane, diesel fuel, and/or other liquid or gaseous fuels directly to consumers. (I15)

“Funeral home or mortuary” means an establishment where deceased are prepared for burial or cremation, and funeral services may be conducted. It can include an area where funeral vehicles are stored and caskets and other funeral supplies are sold. (C7)

“Furniture store” means an establishment that provides large and small furniture for living spaces such as homes and offices. Items sold normally include beds, tables, chairs, sofas, desks, and shelves. Home appliances, outdoor/patio furniture, wall cabinets, garage storage units, and home furnishing accessories are items sold that are excluded from the definition of furniture store. (I16,~~I17~~,~~I18~~)

“Games of skill or amusement” means machines, devices or apparatus, the operation or use of which is made possible by the deposit or placement of any currency, plate, disc, slug or key into any slot or crevice, for the purpose or use as a game or amusement. This use does not include games, machines, or devices used for a purpose that is prohibited by law. (A8) (A9)

“Garden shop” means an establishment that provides live plants and related products mainly to residential consumers, with a portion of the establishment typically located outdoors. (~~H9~~ I17)

Gas regulator station. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

Gas station. See Fuel sales, retail. (I15)

“Golf course or country club” means one or more golf courses, with accessory facilities and uses that can include clubhouses with bar and restaurant, locker and shower facilities; driving ranges; “pro shops” for onsite sales of golfing equipment; and golf cart storage and sales facilities. (G4)

“Government office; local, state, or federal” means a facility owned or operated by a local, state, or federal government that provides services to the public such as employment assistance, public assistance, motor vehicle registration and licensing services and similar activities commonly accustomed to having sizeable assemblages of people waiting for service, whether pedestrian or vehicular. This use does not include a government-owned facility that is more specifically defined in this chapter, such as fairgrounds, cemetery, post office, or public safety facility. (F9)

“Guest house” means living quarters without a kitchen, located on the same premises with a main residence. (34)

Hair salon. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Hazardous waste facility” means all contiguous land and structures, other appurtenances and improvements on the land used for the treatment, transfer, storage, resource recovery, disposal or recycling of hazardous waste, and may consist of one or more treatment, transfer, storage, resource recovery, disposal or recycling hazardous waste management units, or combinations of these units. (See Health and Safety Code Section 25117.1.) (D5)

“Health or fitness facility, large” means a fitness center, gymnasium, health club or athletic club that typically charges a membership fee and includes any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G5)

“Health or Fitness Facility, small” means a fitness center, health club or athletic club that typically charges a membership fee and does not include any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G6)

Heliport. See Airport or heliport. (K1)

“Home occupation” means a commercial business activity conducted as an accessory use within a residence. (A10)

“Hospital, general or psychiatric” means a facility that provides medical, psychiatric, or surgical service for sick or injured persons, primarily on an in-patient basis, and including ancillary facilities for out-patient and emergency treatment, diagnostic services, training, research, administration and services to patients, employees, or visitors. (E5)

“Hotel or motel” means a building or group of buildings in one complex consisting of multiple guest rooms intended or designed to be occupied on a temporary basis, and typically providing ancillary services such as a restaurant, lounge, pool or exercise room, meeting rooms, and/or other personal services. Alcoholic beverages served to overnight guests outside of a restaurant or bar/lounge typically requires an ABC Type 70 license. (6) (H6)

“Industrial or manufacturing facility, heavy” means a facility that manufactures products from extracted or raw materials or recycled or secondary materials, or the bulk storage and handling of such products and materials. This use includes operations such as biomass energy conversion; production apparel manufacturing; photographic processing plants; leather and allied product manufacturing; wood product manufacturing; paper manufacturing; chemical manufacturing; plastics and rubber products manufacturing; nonmetallic mineral product manufacturing; primary

metal manufacturing; fabricated metal product manufacturing; and automotive and heavy equipment manufacturing. This use does not include Agricultural products processing. (D6)

“Industrial or manufacturing facility, light” means a facility that manufactures products from previously prepared materials completely within an enclosed building, and that produces minimal impacts on nearby properties. This use includes the manufacturing of finished parts or products primarily from previously prepared materials; commercial laundries and dry cleaning plants; monument works; printing, engraving, and publishing; machine and electrical shops; computer and electronic product manufacturing; furniture and related product manufacturing; and industrial services. The use also includes the preparation and/or packaging of food for off-site consumption. (D7)

“Junkyard, wrecking yard, or salvage facility” means a facility that accepts, collects, and stores junk, scrap, or salvable material, including junk metals or other scrap materials, and/or that stores, dismantles, wrecks, or allows parts removal of more than three (3) non-operating automobiles, other vehicles, or machinery for a period of more than thirty (30) days. (K5)

“Keeping of household pets” means the keeping, raising, and caring for domesticated animals that are not considered domestic agricultural animals by the definition of Animal raising, and typically including dogs, cats, birds, fish or other similar sized animals. Also, see Animal raising. (A11)

“Kennel or animal boarding” means any facility where four or more dogs, cats, or other small animals are kept overnight for profit, breeding, care, or exhibiting. This use does not include a pet store. (J17)

“Laboratory, general, medical, or dental” means a facility that conducts scientific or medical experiments, research, or teaching, typically within a completely enclosed building. (E4)

“Landscape nursery” means a facility that grows, maintains, and provides trees, plants, and other nursery products for transplant in another location typically to both retailer and wholesale customers. (~~I20~~ I18)

“Library, museum, or cultural facility” means a facility operated entirely on a public or nonprofit basis for the purpose of providing education, information, training, and/or entertainment of a civic or cultural nature. (C8)

“Linen, diaper or uniform supply service” means an establishment providing high volume laundry and garment services, including power laundries (family and commercial), garment pressing and dry cleaning, linen supply, diaper service, and industrial laundries. This use does not include dry cleaning or laundromat. (J18)

“Liquor store” means an establishment that provides for the sale of alcoholic beverages such as beer, wine, and/or distilled spirits for consumption off the site, along with other retail items. This use typically requires an ABC Type 20 or 21 license. Limited consumption on the site can occur only when the appropriate ABC license is obtained, typically an ABC Type 86 license. (~~I21~~ I19)

“Live/Work facility” means a building that combines a complete dwelling unit with a commercial or office work space, with both occupancies used by the same person or family. (H7)

Lodge. See Club, lodge, or private meeting hall (C3)

Lounge. See Bar, nightclub, or lounge. (B2)

Lumberyard. See Building materials and supply or home improvement store. (I7)

“Manufactured home” means a structure that was constructed on or after June 15, 1976, is transportable in one or more sections, is eight (8) body feet or more in width, or forty (40) body feet or more in length, in the traveling mode, or, when erected on site, is three hundred twenty (320) or more square feet, and is designed to be used as a single-family dwelling when connected to the required utilities. (7)

“Manufactured home sales yard” means an establishment that stores and provides manufactured homes, typically in an open setting with a sales office. (~~I22~~ I20)

Massage therapy. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Meat packing or slaughterhouse” means a facility used for the killing or dressing of animals, including cattle, sheep, swine, goats, horses, or poultry, and the storage, freezing, curing, or packaging of meat or meat products. (D8)

“Marijuana cultivation” means any activity involving the planting, growing, harvesting, drying, curing, grading, or trimming of marijuana. (A13)

“Marijuana dispensary or sales” means a facility that provides marijuana or marijuana products to a customer or patient. (~~I23~~ I21)

“Marijuana manufacture” means a facility that compounds, blends, extracts, infuses, or otherwise makes or prepares a marijuana product. (D8)

“Meat packing or slaughterhouse” means a facility that slaughters animals and/or packages animal meat for food. (D9)

“Microbrewery” means an establishment that produces small batches of beer for sale on or off of the site, and may or may not include food service. Typically, a microbrewery produces fewer than fifteen thousand (15,000) barrels of beer or ale per year. This use typically requires an ABC Type 23 license. (B4)

“Mining, quarry, or sand and gravel excavation” means an area of land where rock, ore, stone and similar materials are excavated and processed for sale for use off-site. (D10)

“Mini-warehouse or self-storage facility” means an establishment providing rental space, such as rooms, lockers, or containers for the storage of goods and materials, typically on a monthly basis. This use does not include Food locker or Warehouse or distribution center. (56) (K6)

“Mobilehome” means a structure that was constructed prior to June 15, 1976, is transportable in one or more sections, is eight (8) body feet or more in width, or forty (40) body feet or more in length, in the traveling mode, or, when erected on site, is three hundred (320) or more square feet, and is designed to be used as a single-family dwelling when connected to the required utilities. (8)

“Mobilehome park” means an area of land where two or more mobilehome sites are rented or leased, or offered for rent or lease, to accommodate mobilehomes or manufactured homes used as a residence. (9) (H8)

“Mobile vending or food truck” means a motorized vehicle that periodically parks to provide food or foodstuffs to customers. (A14)

Motel. See Hotel or motel. (H6)

“Motor vehicle repair or service, major” means an establishment that provides major repair or servicing of motor vehicles, such as body, chassis, engine, transmission, or exhaust repair or modification. (J19)

“Motor vehicle repair or service, minor” means an establishment that provides minor repair or servicing of motor vehicles, such as the replacement of tires or batteries, smog inspection, oil and filter change, wheel alignment, and fluid flushing, refill, or replacement. (J20)

“Multi-family dwelling” means a building or group of buildings in one complex with multiple separate housing units. A multi-family dwelling can have two units (a duplex,) three units (a triplex,) four units (a fourplex,) or five or more units. Multi-family dwelling includes a mixed use building that also provides separate space for commercial or office use, but does not include an attached single-family dwelling. (10) (11) (12) (H9) (H10) (H11)

Nail care. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“News, magazine, or flower stand, outdoor” means an establishment that provides newspapers, magazines, flowers, or other similar goods, typically to pedestrians passing by, in a permanent structure open to the outdoors. This use does not include sales from temporary booths or structures. (~~I24~~ I22)

Nightclub. See Bar, nightclub, or lounge. (B2)

“Office; medical, dental, or optometry” means an establishment that provides services, typically by appointment, dealing with human health including dental, chiropractic, medical, optometry, physical therapy, psychology, psychiatry, family counseling, or therapy. This use does not include Barbershop, hair salon, nail care, massage therapy, or day spa. (E6)

“Offices, professional or commercial” means an establishment that provides administrative, clerical, technical, professional or similar business services and typically where products or goods are not provided. Examples include escrow and title, insurance, mortgage, real estate, accounting, architecture, graphic design, finance, consulting, engineering, legal, and similar services. (E7)

“Optical retailer” means an establishment that provides prescription eyeglasses and contact lenses, and where optometry services are not provided on the site. Prescription eyeglasses and contact lenses may be made on the premises. (~~I25~~ I23)

“Outdoor advertising structure” means a structure of any kind or character, erected or maintained for outdoor advertising purposes, upon which a sign may be placed that advertises a use, product, or service that is not provided off-site. (A15)

“Outdoor storage” means the storage of goods or materials outside of any building or structure, but not including storage of a temporary or emergency nature. (A16)

“Park or playground” means an open area typically landscaped and containing play equipment that provides rest and recreation, usually owned by a public agency or homeowner’s association. (57) (G7)

“Parking facility, off-site” means an area, lot, or structure with one or more levels, other than a street or other public right-of-way, that provides for the parking of motor vehicles as a primary

use on the site. This use does not include parking areas or lots that are ancillary and specifically intended to provide parking for the primary use on the site. (K7)

“Pawn shop” means an establishment that provides secured loans to customers, with items of personal property used as collateral. (~~I26~~ I24)

“Payday lender or check cashing establishment” is an establishment that cashes checks, warrants, or money orders for a fee, and/or provides short term loans, usually at a high interest rate, that must be paid in full when the borrower receives their next pay check. This use does not include Bank or credit union. (J21)

“Pet grooming” is a personal service establishment that, for a fee, trims, cleans or curries domestic pets such as dogs and cats and which may sell pet supplies. This use does not include Kennel or animal boarding. (J22)

“Pet store” means an establishment where dogs, cats, or other small animals are kept and offered for sale. (~~I27~~ I25)

“Pharmacy” means an establishment that provides prescription drugs under the supervision of a pharmacist, and can also provide other retail products. (E8)

“Photography studio” means an establishment where customers can have their portraits taken professionally. (J23)

“Pool hall or billiard parlor” means an establishment where pool and/or billiard games are played for a fee. (C9)

“Post office” means a facility that accepts, processes, and sorts mail, operated by the United States Postal Service. (F10)

Private meeting hall. See Club, lodge, or private meeting hall (C3)

Professional school. See School, charter, trade, vocational, art, business, or professional. (C12)

Produce stand. See Food produce stand. (I13)

“Public corporation yard, utility yard, or vehicle and heavy equipment maintenance and storage yard” means a facility that provides for maintenance, servicing, or storage of fleet vehicles, equipment, or supplies, or for the dispatching of service vehicles; or distribution of supplies or construction materials required in connection with a business activity, public utility service, transportation service, government service, or similar activity. (F11)

“Public safety facility or station” means a facility that is a base for providing public safety and emergency services, including police, fire protection and emergency services. This use does not include Ambulance service. (F12)

Public service pumping station. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Recreational vehicle park” means a lot or area of land where two or more spaces are rented to users of recreational vehicles for overnight parking and use, and that typically provide support services, such as utility hookups and sewer dump facilities. (13) (H12)

“Recycling, large collection facility” means a facility located in an area of over five hundred (500) square feet that accepts recyclable materials from the public by donation, redemption, or purchase for temporary storage and transport to a processing and sorting facility. (J25)

“Recycling, processing or sorting facility” means a facility used for the collection, processing and preparation of recyclable material for efficient shipment, or to an end-user's specifications, by such means as bailing, briquetting, compacting, flattening, grinding, crushing, mechanical sorting, shredding, cleaning, and remanufacturing. (J26)

“Recycling, small collection facility” means facility located in an area of not more than five hundred (500) square feet that provides for the redemption of California CRV redeemable beverage containers by means of a kiosk, container, mobile unit, reverse vending machine or other collection method. (J24)

“Religious institution or facility” means a facility used primarily to gather for religious worship and related religious activities. (58) (C10)

“Repair shop, large appliance or equipment” means an establishment that restores or repairs major appliances or equipment that generally cannot be easily moved by a single person and is typically placed on the floor. This use typically provides all of its service on-site, and includes repair of large motorized equipment that are not vehicles. (J27)

“Repair shop, small appliance or equipment” means an establishment that restores or repairs small appliances or equipment that generally can be moved by one person and is typically repaired on a table or work bench. This use typically provides all of its service on-site, and includes services such as gunsmithing, lawnmower repair, and home computer repair. (J28)

“Research and development facility” means a facility that is primarily used for the research, design, development, and testing of biological, chemical, electrical, magnetic, mechanical, and/or optical components in advance of product manufacturing. This use does not involve the fabrication, mass manufacture, or processing of products. (D11)

“Residential care facility” means a single-family dwelling, group care facility, or similar facility licensed by the State of California for twenty-four (24) hour non-medical care of persons in need of personal services, supervision or assistance essential for sustaining the activities of daily living or for the protection of the individual. (14) (15) (H13)

“Residential dwelling located in the same building with office or commercial use” means a building that contains a mix of both residential dwelling units and space used for commercial or office uses. (H14)

“Restaurant, full service” means an establishment providing preparation and sale of a variety of food and beverages with full table service by wait staff. Takeout or delivery service and/or live entertainment may also be provided. If alcoholic beverages are served, this use typically requires an ABC Type 41 or 47 license. (B5)

“Restaurant, limited service with drive-thru pickup window” means an establishment providing preparation and sale of a variety of food and beverages for consumption on or off the site by ordering and paying at a counter or drive-thru window. Delivery service and/or live entertainment may also be provided. (B6)

“Restaurant, limited service without drive-thru pickup window” means an establishment providing preparation and sale of a variety of food and beverages by ordering and paying at a

counter. Takeout or delivery service and/or live entertainment may also be provided. Drive-thru pickup windows are not provided. If alcoholic beverages are served, this use typically requires an ABC Type 41 or 47 license. (B7)

“Retail sales store” means an establishment providing retail products. This use includes all retail sales establishments that are not more specifically defined in this chapter. (~~I28~~ I26)

“Retail sales solely via internet, direct mail, or telephone” means an establishment providing retail products for sale and delivery only via internet, direct mail, or telephone communication, with a floor space for storage of products of less than five thousand (5,000) square feet. This use does not include a Call center or a Warehouse or distribution center. If alcoholic beverages are sold, this use typically requires an ABC Type 85 license. (~~I29~~ I27)

Rooming house. See Boarding house or rooming house. (3) (H3)

“School, private (kindergarten to 12th grade)” means a facility owned and/or operated by a private entity that educates minors in courses of study required by the California Education Code. This use includes a kindergarten, elementary school, middle school, high school, special institution of education, or combination of these, and includes a technical, vocational, or art school only when the students are primarily minors. This use does not include home schooling at a residence. (59) (C11)

“School, public (kindergarten to 12th grade)” means a facility owned and/or operated by a publicly funded school district that educates minors in courses of study required by the California Education Code. This use includes a kindergarten, elementary school, middle school, high school, special institution of education, or combination of these, and includes a technical, vocational, or art school only when the students are primarily minors. This use does not include a charter school. (60) (C12)

“School; charter, trade, vocational, business, or professional” means a facility that is operated either with public funds under a charter contract or with private funds, and that offers specific educational instruction to children and/or adults. This use includes charter schools, secretarial schools, beauty and cosmetology schools, modeling schools, language schools, computer or electronics training schools, arts schools, and automotive repair schools, and similar specialized schools. (C13)

Scrap metal processing. See Junk yard, wrecking yard, or salvage yard. (K5)

“Secondhand or thrift store” means an establishment that accepts donations of secondhand items and clothing, and is typically operated for charitable purposes. (~~I30~~ I28)

Service station. See Fuel sales, retail, and Motor vehicle repair or service, minor. (I15) (J19)

“Shooting range, indoor” means an establishment that is used for archery or firearms practice in a fully-enclosed facility. (J29)

“Shooting range, outdoor” means an establishment that is used for archery or firearms practice, either wholly or partially outdoors. (J30)

“Single-family dwelling, attached” means a building with two residential dwelling units located on portions of two lots with a building firewall along the lot line, such that the dwelling units may be sold separately. (16) (H15)

Single-family dwelling, detached” means a building with one residential dwelling unit located on one lot. (17) (H16)

“Single-room occupancy (SRO)” means a residential facility of two or more separate individual rooms with typically less than five hundred (500) square feet of floor space, with or without separate kitchen or bathroom facilities for each room, rented on a weekly or monthly basis. Single-room occupancy does not include Hotel or motel. (18) (H17)

“Social service office, assistance center, or guidance center” means a facility that provides counseling, guidance, recuperative, or similar services for persons requiring rehabilitation assistance as a result of economic hardship, mental disability, alcoholism, detention, drug addiction, or similar conditions. This use does not include facilities that provide overnight stay. (F13)

“Specialty construction or trade service” means an establishment that provides construction, installation or maintenance services activities that are typically specialized trade activities, and where some of the service may be provided off-site. This use includes establishments that provide services such as plumbing, electrical work, painting, irrigation, heating/air conditioning, and masonry. This use does not include Repair shop or Motor vehicle repair or service. (J31)

“Storm drainage basin, with or without a park” means a facility that collects storm water from off-site locations into a sunken basin. The facility may be inaccessible to the public, or may be designed to provide partial public access for recreational use. (61) (F14)

“Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar” means a facility that provides group or individualized instruction in a specific activity typically related to the arts. This use does not include Health or fitness facility. (C14)

“Supportive housing” is defined in Section 50675.14 of the Health & Safety Code and has no limit on the length of stay, is linked to onsite or offsite services, and is occupied by a target population as defined in Health & Safety Code Section 53260 (i.e., low income persons with mental disabilities, AIDS, substance abuse or chronic health conditions or persons whose disabilities originated before the person turned 18). Services typically include assistance designed to meet the needs of the target population in retaining housing, living and working in the community, and/or improving health and may include case management, mental health treatment, and life skills. (19) (H18)

“Swap meet or flea market” means a facility that provides typically compartmentalized space, either indoors or outdoors, to vendors who sells or barter merchandise. This use does not include ‘Farmers market,’ ‘Auction or sales house,’ or ‘Auction or sales yard.’ ~~(I31)~~ (I29)

“Tailoring or clothing alterations” means an establishment that provides custom making or altering of clothing when not an ancillary use in a clothing store. (J32)

“Tattooing or body art” means an establishment that provides tattooing, body piercing, and other forms of body art allowed by the California Health and Safety Code, except that body art involving ear piercing and permanent cosmetic application are not included and are considered ancillary uses in other establishments. This use does not include any use that is more specifically defined in Section 17.62.020. (J33)

“Temporary materials or equipment storage yard” means a facility that is used to store, park, house, or prepare equipment, dirt, materials, or temporary offices or shops to support a construction or demolition activity occurring on another site. (A17)

“Temporary sales office” means a facility that provides temporary office space to support the sale of residences or other structures, and can include related parking. (A18)

“Theater, live or movie” means a facility with an auditorium for viewing movies, plays, acts, or other performances. (C15)

“Tobacco or smoke shop” means an establishment that provides tobacco products or tobacco related paraphernalia in an area greater than forty (40) percent of its total available retail floor space. (~~I32~~ I30)

Trade school. See School, charter, trade, vocational, art, business, or professional. (C13)

Transit station. See Bus, transit, or train station. (K2)

Travel center. See Truck stop or Travel center. (K7)

“Transitional housing” means buildings configured as rental housing developments, but operated under program requirements that call for the termination of assistance and recirculation of the assisted unit to another eligible program recipient at some predetermined future point in time, which shall be no less than six months. (20) (H19)

“Truck stop or travel center” means an establishment or group of establishments designed to operate together that provide fuel, overnight parking, lodging, food, convenience goods, or other services primarily to truckers and travelers. (K8)

“Trucking or transportation terminal” means a facility designed specifically for large trucks or other vehicles to load, unload, or transfer freight, cargo containers, or other items being shipped, along with associated fueling areas, maintenance facilities, and offices. (K9)

“Urgent care center or other walk-in clinic” means a facility that provides medical treatment of injuries or illnesses that do not require treatment typically provided in an emergency room, typically without an appointment. This use includes urgent care centers, free clinics, hospital-based health clinics, and community health clinics, but does not include ancillary retail clinics located within a retail store, food market, or pharmacy. (E9)

“Vehicle impound yard” means a facility that provides temporary storage of vehicles that have been removed or impounded from public or private property at the direction of a peace officer or because of local ordinance or judicial order. (K10)

“Vending machines” means a device that dispenses a product or service upon activation by the receiver of that product or service. Products can include items such as ice; food and beverages, movies and video games, lottery tickets, newspapers, or similar items, but does not include fueling pumps. (A19)

“Veterinary clinic or office” means a facility where animals are examined, diagnosed, or treated, but typically not kept overnight. (J34)

“Veterinary hospital” means a facility where animals are kept for observation, diagnosis, treatment, or medical care, and can include overnight surveillance. (J35)

Vocational school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Warehouse or distribution center” means a facility for storage of goods or materials that will eventually be redistributed to retailers, wholesalers, or directly to consumers. This use does not include Mini-warehouse or self-storage facility. (K11)

Winery. See Brewery or winery. (D4)

“Wireless Communication Facility” means an unstaffed facility that transmits and receives wireless telecommunications, and typically consists of an antenna array, connection cables, and equipment room, and an antenna support structure tower, or pole. (F15)

Chapter 17.98

DEFINITION OF TERMS

Sections:

- 17.98.010 Applicability**
17.98.020 Definition of terms.

17.98.010 Applicability

The terms, words, and phrases defined in this chapter shall apply to this title.

17.98.020 Definition of terms.

“Abutting” means two (2) or more parcels sharing a common boundary at least at one point.

“Abandoned” means failure to develop, maintain or use a building, structure or improvement or failure to conduct a use upon real property for a stated period of time.

“Access” means safe, adequate and usable ingress or egress to real property, structures or improvements.

“Action” means the decision made by the review authority on a land use application, including appropriate findings, environmental determination and conditions of approval, where applicable.

“Addition” means any construction which increases the size of a building or facility in terms of site coverage, height, length, width, or gross floor area.

“Alley” is a public thoroughfare for the use of pedestrians and/or vehicles, producing only a secondary means of access to the abutting property.

“Alteration” means any construction or physical change in the internal arrangement of rooms or the supporting members of a building or structure or change in the appearance of any building or structure.

“Antenna” means a device for transmitting or receiving radio, television or any other transmitted signal.

“Applicant” means owner(s) of property, or their agent(s) who are seeking privileges provided by this title.

“Attached” means any structure that has a wall or roof in common with another structure.

“Basement” means a portion of building partly or wholly underground and having more than one-half (1/2) of its height below the average level of the adjoining ground.

“Berm” means a mound or embankment of earth.

“Block” means a parcel of land surrounded by public streets, highways, freeways, railroad rights-of-way, flood control channels, creeks, washes, rivers or unsubdivided acreage or any combination thereof.

“Building” means a permanently located structure, having a roof, for the housing or enclosure of persons, possessions, or property of any kind. Mobile homes, travel trailers and other vehicles, even though permanently immobilized, shall not be deemed to be buildings.

“Building area” means the net portion of the lot remaining after deducting all required setbacks from the gross area of the lot.

“Building coverage” means the percent of lot area which may be covered by roof covered buildings, structures or improvements located on a lot.

“Building height” means the vertical distance between the average finished ground surface adjacent to the structure and to the highest point of the structure, excluding architectural features and appurtenances such as, but not limited to, chimneys, vents, antennas, elevators, and similar mechanical equipment.

“Building, main” means a building in which the principal use of the real property is conducted.

“Building setback area, front” means an area extending across the full width of the lot between the front lot line or the existing or future street right-of-way and a structural setback line parallel thereto. On corner lots, the shortest street frontage shall be the front building setback area.

“Building setback area, interior side” means an area extending from the required front building setback area or, where there is no required front building setback area, from the front lot line to the required rear building setback area or, where there is no required rear building setback area, to the rear lot line and from the interior side lot line to a setback line parallel thereto.

“Building setback area, rear” means an area extending across the full width of the lot between the rear lot line and a setback line parallel thereto.

“Building setback area, side” means a building setback area between the side lot line and a line parallel thereto and extending from the front building setback area to the rear building setback area.

“Building setback area, street side” means an area extending from the required front building setback area or, where there is no required front building setback area, from the front lot line to the rear lot line, and from the side street lot line, or the existing or future side street right-of-way (whichever is greater) to a structural setback line parallel thereto.

“Building site” means the ground area of a building together with all open spaces required by this title.

“Carport” means a permanent roofed structure not completely enclosed to be used for vehicle parking.

“City” means the City of Hanford.

“Commercial vehicle” means a vehicle customarily used a part of a business for the transportation of goods or people.

“Commission” means the Planning Commission of the City of Hanford.

“Conditional use” means a use that may locate within a zone only upon taking measures to address issues that may make the use detrimental to the public health, safety and welfare and will not impair the integrity and character of the zoned district.

“Conditional use permit (CUP)” means a discretionary entitlement which may be granted under the provisions of this title and which when granted authorizes a specific use to be made of a specific property, subject to compliance with all terms and conditions imposed on the entitlement.

“Construction commencement” means the start of construction of a substantial portion on-site and off-site structural improvements after a building permit has been issued.

“Council” means the City Council of the City of Hanford.

“County” means the County of Kings.

“Court” means an open, unoccupied space, other than a yard, unobstructed from ground to sky on the same lot with a building or buildings and which is bounded on two or more sides by the walls of a building.

“Days” means consecutive calendar days unless otherwise stated.

“Decibel (dB / dBA)” is a unit for describing the amplitude of sound, as it is heard by the human ear.

“Density” means the number of dwelling units per gross acre, unless otherwise stated, for residential uses.

“Density Bonus” means an increase in the allowable number of residences granted by the city or county in return for the project’s providing low- or moderate-income housing. A housing development that provides 20 percent of its units for lower-income households, ten percent of its units for very-low income households, or 50 percent of its units for seniors is entitled to a density bonus and other concessions (See California Government Code section 65915).

“Design” means the planning and engineering of the following: street alignments, grades and widths; drainage and sanitary facilities and utilities, including alignment and grades thereof; location and size of all required easements and rights-of-way; fire roads and fire breaks; lot size and configuration; traffic access; grading; land to be dedicated for park or recreational purposes; building, structures and improvements and other such specific physical requirements.

“Detached” means any building or structure that does not have a wall or roof in common with any other building or structure.

“Development” means any change or alteration of real property or its boundary lines, and including, without limitation, the placement or erection of any solid material, structure or improvement thereon; discharge or disposal of any dredged material or any gaseous liquid, solid or thermal waste; grading, removing, dredging, mining or extraction of any soil or materials; change in the density or intensity of use of land, including, but not limited to, subdivision pursuant to the Subdivision Map Act (commencing with Section 66410 of the Government Code), and any other division of land, including lot splits, except where the land division is brought about in connection with the purchase of such land by a public agency for public recreational use; change in the intensity of use of water, or of access thereto; construction, reconstruction, demolition or alteration of the size of any structure including any facility of any

private, public or municipal utility; and the removal of any major vegetation. As used in this title, “structure” includes but is not limited to any building, road, pipe, flume, conduit, siphon, aqueduct, telephone line, and electrical power transmission and distribution line. A “project,” as defined in Government Code Section 65931, is included with this definition.

“Development agreement” means a binding contract between a developer and a city or county establishing the conditions under which a particular development may occur. The local government “freezes” the regulations applicable to the site for an agreed upon period of time. (see California Government Code section 65864)

“Development permit” means a discretionary entitlement which may be granted under the provisions of this title and which when granted authorizes a specific use to be made of specific property, subject to compliance with all terms and conditions imposed on the entitlement.

“Display area” means the area of a building in a retail sales store used to display goods that are for sale.

“Driveway” means a permanently surfaced area providing direct access for vehicles between a street and a permitted off-street parking or loading area.

“Dwelling” or “Dwelling Unit” means a room or group of rooms (including sleeping, eating, cooking, and sanitation facilities, but not more than one kitchen), which constitutes an independent housekeeping unit, occupied or intended for occupancy by one household on a long-term basis.

“Easement” means a grant of property rights by the property owner to the public, or any specific person.

“Electric vehicle” means a vehicle that uses a plug-in battery to provide all or part of the motive power of the vehicle, including battery electric, plug-in hybrid electric, or plug-in fuel cell vehicle.

“Electric vehicle service equipment” means an electric component assembly or cluster of component assemblies designed specifically to charge batteries within electric vehicles by permitting the transfer of electric energy to a battery or other storage device in an electric vehicle.

“Establishment” means land, buildings, rooms, space, and/or equipment necessary for conducting business.

“Façade” means the exterior wall of a building exposed to public view or that wall viewed by persons not within the building.

“Family” is an individual or a group of persons living together who constitute a bona fide single-family housekeeping unit in a dwelling unit, not including a fraternity, sorority, club, or other group of persons occupying a hotel, lodging house or institution of any kind.

“Facility” means land, buildings, rooms, space, and/or equipment necessary for doing something.

“FAR (Floor Area Ratio)” is a measure of development intensity. FAR is the ratio of the floor area of a building to the area of its site. For instance, both a two-story building that covers an entire lot and a four-story building that covers 1/2 of a lot have a FAR of 2.

“Fence” means a barrier surrounding or located upon a parcel of real property or a portion thereof and intended to prevent escape or intrusion therefrom or to identify a boundary identity, including without limitation, screened, solid (ninety percent (90%) or more closed to air, light and vision), open (fifty percent (50%) or more), or temporary and which may be constructed from wood, metal or masonry material or any combination thereof.

“Floor area” means the gross area included within the surrounding exterior finish wall surface of a building or portion thereof, exclusive of courtyards.

“Furniture” means the things placed in a room which equips it for living. This normally includes beds, tables, chairs, sofas, desks, and shelves. Home appliances, outdoor/patio furniture, wall cabinets, garage storage units and home furnishing accessories are excluded from the definition of furniture.

“Garage” means an enclosed building, or a portion of an enclosed building used for the parking of vehicles.

“General Plan” means a document adopted by the City Council containing statement of policies, including text and diagrams, setting forth objectives, principles, standards, and plan proposals, for the future physical development of the City of Hanford.

“Glare” means the effect produced by brightness sufficient to cause annoyance, discomfort, or loss in visual performance and visibility.

“Grade” means the degree of rise or descent of a sloping surface.

“Grade, finished” means the final elevation of the ground surface after development.

“Grade, natural” means the elevation of the ground surface in its natural state before man-made alterations.

“Grading” means the stripping, cutting, filling, stockpiling of earth or land, including the land in its cut or filled condition.

“Gross acreage” means the total area within the lot lines of a lot or parcel of land before public streets, easements or other areas to be dedicated or reserved for public use are deducted from such lot or parcel, and does not include adjacent lands already dedicated for such purposes.

“Hazardous waste” means either of the following:

1. A waste, or combination of wastes, which because of its quantity, concentration or physical, chemical or infectious characteristics may either:
 - a. Cause, or significantly contribute to an increase in mortality or an increase in serious irreversible, or incapacitating reversible, illness, or
 - b. Pose a substantial present or potential hazard to human health or environment when improperly treated, stored, transported or disposed of, or otherwise managed;
2. A waste which meets any of the criteria for the identification of a hazardous waste adopted by the State Department of Health Services pursuant to Health and Safety Code Section 25117 or any other federal, state or local law or regulation;
3. Resource Conservation and Recovery Act hazardous wastes;

4. Unless expressly provided otherwise, the term “hazardous waste” shall be understood to also include extremely hazardous waste and acutely hazardous waste. (Health and Safety Code Section 25117.)

“Improvement” means any item which becomes part of, placed upon, or is affixed to real estate.

“Infill development site” means a parcel or group of parcels that make up a site that is vacant or underutilized and is surrounded by developed land or parcels on at least seventy-five (75) percent of its perimeter. Infill development sites include previously developed sites that may/will be redeveloped.

“Integrated shopping center” means a combination of three (3) or more business establishments permitted or conditional permitted in the zone district in which they are located where off-street parking, landscaping, lighting, or other features are developed, managed and maintained jointly.

“Kitchen” means any room, all or any part of which is designed and/or used for cooking and the preparation of food.

“Landscaping” means an area devoted to, or developed and maintained predominantly with, native or exotic plant materials including lawn, groundcover, trees, shrubs and other plant materials; artificial turf and other permeable surfaces; and also including accessory decorative outdoor landscape elements such as pools, fountains, paved or decorated surfaces (excluding driveways, parking, loading or storage areas), and sculptural elements.

“Land use” means a description of how land (real estate) is occupied or utilized.

“Loading Space” means an off-street space or berth on the same lot with a building or contiguous to a group of buildings for the temporary parking of a commercial vehicle while loading or unloading merchandise or materials.

“Lot” means a parcel, tract or area of land established by plat, subdivision, or as otherwise permitted by law, to be used, developed or built upon. The classifications of lots are:

1. “Corner” means a lot located at the intersection of two or more streets at an angle of not more than one hundred thirty-five (135) degrees. If the angle is greater than one hundred thirty-five (135) degrees, the lot shall be considered an interior lot.
2. “Flag” means a lot having access or an easement to a public or private street by a narrow, private right-of-way.
3. “Interior” means a lot abutting only one street.
4. “Key” means a lot with a side line that abuts the rear line of any one or more adjoining lots.
5. “Reverse corner” means a corner lot, the rear of which abuts the side of another lot.
6. “Through” means a lot having frontage on two generally parallel streets, with only one primary access. (See “Illustration of Terms.”).

“Lot area” means the net horizontal area within bounding lot lines after dedication.

“Lot coverage” means the area of a lot covered by buildings excluding eaves, projecting balconies, ground-level paving, landscaping, and open recreational facilities.

“Lot depth” is the horizontal distance between the midpoint of the front lot line and the midpoint of the rear lot line.

“Lot frontage” means the portion of the lot contiguous to the street.

“Lot line” means any boundary of a lot. The classifications of lot lines are:

1. “Front” means on an interior lot, the line separating the parcel from the street. On a corner lot, the shorter lot line abutting a street. (If the lot lines on a corner lot are equal in length, the front lot line shall be determined by the director). On a through lot, the lot line abutting the street providing the primary access to the lot.
2. “Interior” means any lot line not abutting a street.
3. “Rear” means a lot line, not intersecting a front lot line, which is most distant from and most closely parallel to the front lot line.

“Lot Width” means the horizontal distance between side lot lines, measured at the front setback line.

“Mall” means a large building or series of connected buildings containing a variety of retail stores, restaurants, and entertainment activities including, but not limited to, such activities as theaters, arcades, amusement rides, rock-climbing and other indoor recreation opportunities that serve a regional population.

“Median” means a paved or planted area separating a street or highway into two (2) or more lanes of opposite directions of travel.

“Nonconforming lot” means a lot, the area, frontage or dimensions of which do not conform to the provisions of this zoning code.

“Nonconforming structure” means a structure, lot or use which did conform to applicable laws when constructed or initiated, and which does not now conform to the provisions of this zoning code.

“Nonconforming use” means a use complying with applicable laws when established but which does not conform to the provisions of this zoning code.

“Open space” means any parcel or area of land or water essentially unimproved and set aside, dedicated, designated, or reserved for public or private use or enjoyment or for the use and enjoyment of owners and occupants of land adjoining or neighboring such open space. Does not include area covered by buildings or accessory structures (except recreational structures), paved areas (except recreational facilities), proposed and existing public and private streets or driveways, and school sites.

“Open space, common usable” means recreational or leisure space for the shared use of residents of a multi-unit development with no dimension less than 20-feet and may include gardens, playgrounds, courtyards, swimming pools, sitting areas, court games, recreation rooms, exercise rooms or gyms, spas, community rooms, lawn/turf used for open play, ponds, fountains, atriums, picnic areas, rooftop gardens or green roofs, or similar uses or facilities.

“Overhang” means the part of a roof or wall that extends beyond the façade of a lower wall.

“Overlay district” is a district established by this zoning code which may be applied to a lot or portion thereof only in combination with a base district.

“Parapet” means the extension of the main walls of a building above the roof level.

“Parcel” means a parcel of land under one ownership that has been legally subdivided or combined and is shown as a single parcel on the latest recorded map in the Kings County recorder’s office.

“Parking area” means any public or private land area designed and used for parking motor vehicles including parking lots, garages, private driveways, and legally designated areas of public streets.

“Parking lot” is an off-street, ground-level area, usually surfaced and improved, for the temporary storage of motor vehicles.

“Parking ratio” means the number of parking spaces provided per 1,000 square feet of floor area.

“Parking, shared” means a public or private parking area used jointly by two or more uses.

“Parking space” is the space marked for the parking of a motor vehicle within a public or private parking area.

“Parking structure or structured parking” means a multi-story car park (also called a parking garage or indoor parking) designed for car parking and where there are a number of floors or levels on which parking takes place.

“Parkway” means that portion of the public street right-of-way between the curb or curb line and the adjacent sidewalk or property line, as applicable, used for or which may be used for the purpose of planting and maintaining street trees, shrubs, hedges, or other plants. In some areas within the city, park strips may extend into a private property’s yard beyond the sidewalk. Park strips may be located on private property or may abut private property.

“Performance standards” means zoning regulations that permit uses based on a particular set of standards of operation rather than on particular type of use. Performance standards may provide specific criteria to limit noise, air pollution, emissions, odors, vibration, dust, dirt, glare, heat, fire hazards, wastes, traffic impacts, or visual impact of a use.

“Permit” means a written governmental permission issued by an authorized official, empowering the holder thereof to do some act not forbidden by law, but not allowed without such authorization.

“Person” means any individual, firm, co-partnership, joint venture, association, social club, fraternal organization, company, joint stock association, corporation, estate, trust, organization, business, business trust, public agency, school district, state of California, and its political subdivisions or instrumentalities, receiver, syndicate or any group or combination thereof, acting as a unit, including any trustee, receiver or assignee.

“Permitted use” means any use allowed in a land use zoning district and subject to the provisions applicable to that district.

“Planned unit development (PUD)” means the development of a parcel(s) or structure(s) with two or more different land uses such as, but not limited to a combination of residential, office, manufacturing, retail, public or entertainment in a single or physically integrated group of structures.

“Principal use” means the primary or predominate use of any lot, building or structure.

“Project” means the total development within the boundaries as defined on the development plan.

“Public right-of-way” means a strip of land acquired by reservation, dedication, prescription, voluntary purchase and sale, or condemnation and intended to be occupied by a road, trail, water line, sanitary sewer and/or any other public uses.

“Recreational vehicle” means a vehicle or trailer capable of human habitation or designed or used for recreational camping or travel use, whether self-propelled or mounted on or drawn by another vehicle, or any structure inspected, approved and designated a recreational vehicle and bearing the insignia of the state of California or any other state or federal agency having the authority to approve recreational vehicles. RVs include, without limitation, any of the following: camp trailer, as defined by the California Vehicle Code Section 324; house car, as defined by California Vehicle Code Section 362; trailer coach, as defined by California Vehicle Code Section 635; mobile home, as defined by California Vehicle Code Section 396; bus, as defined by California Vehicle Code Section 233, whether altered or unaltered or for commercial or private use; boat, watercraft, and/or trailer for a boat or watercraft; trailers designed to carry persons, property or animals on its own structure and to be drawn by a motor vehicle; and recreational vehicle, as defined by the California Health and Safety Code Section 18010.

“Recycling” means the process by which waste products are reduced to raw materials and transformed into new reused or reconstructed products which meet the quality standards necessary to be used in the market place.

“Review authority” means the person, committee, commission or council responsible for the review and/or final action on a land use entitlement.

“Right-of-way” means a strip of land acquired by purchase, reservation, dedication, forced dedication, prescription, or condemnation and intended to be occupied or occupied by a road, crosswalk, railroad, electric transmission lines, oil or gas pipeline, water line, sanitary storm sewer, and other similar uses.

“Rounding of quantities” means the consideration of distances, unit density, density bonus calculations, or other aspects of development or the physical environment expressed in numerical quantities which are fractions of whole numbers; the numbers are to be rounded to the nearest highest whole number when the fraction is .5 or more, and to the next lowest whole number when the fraction is .5, except as otherwise provided in this zoning code.

“Screened or screening” means shielded, concealed, and effectively hidden from view by a person standing at ground level on an abutting site, or outside the area, screened by a fence, wall, hedge, berm, or similar architectural or landscape feature that is at least 90% view obscuring.

“Setback” means the area between the setback line and property line.

“Setback line” is a line within a lot parallel to and measured from a corresponding lot line, forming the boundary of a required yard and governing the placement of structures and uses on the lot.

“Sign” means any letter or symbol made of cloth, metal, paint, paper, wood or other material of any kind whatsoever placed for advertising, identification or other similar purposes on the ground or on any wall, post, fence, building, structure, vehicle or on any place whatsoever.

“Site” the land or area that is the subject of a development project or use, and may include more than one lot or parcel.

“Site area” means the net horizontal area included within the boundary lines of a site, not including the area within the established right-of-way of a public street, future public street, or railroad, or any other area dedicated or to be dedicated for a public use.

“Site plan” means a plan, prepared to scale, showing accurately and with complete dimensioning all of the buildings, structures, and uses and the exact manner of development proposed for a specific parcel of land.

“Slope” means the degree of deviation of a surface from the horizontal, usually expressed in percentage or degrees.

“Solar facilities” means the airspace over a parcel that provides access for solar energy system to absorb energy from the sun.

“Specific plan” means a plan consisting of text, maps and other documents and exhibits regulating development within a defined area of the city, consistent with the General Plan and the provisions of Government Code Section 65450 et seq.

“Story” means that portion of a building included between the surface of any floor and the surface of any floor next above it, or if there be no floor above it, then the space between such floor and ceiling next above it.

“Street” means any public or private thoroughfare with a width of twenty feet (20’) or more which affords a primary means of access to abutting property.

“Street, private” means a street in private ownership, not dedicated as a public street, which provides the principal means of vehicular access to a property and not to be construed to mean driveways, alleys, or parking areas.

“Street, public” is a street owned and maintained by the City, the County, or the State. The term includes streets offered for dedication which have been improved or for which a bonded improvement agreement is in effect.

“Structural Alterations” means any change in the supporting members of a structure such as the bearing walls or partitions, columns, beams, or girders.

“Structure” means anything constructed or built. An edifice or building of any kind, or any piece of work artificially built up or composed of parts joined together in some definite manner.

“Structure, accessory” means a subordinate building which is incidental and not attached to the main building or use on the same lot. If an accessory building is attached to the main building or if the roof is a continuation of the main building roof, the accessory building shall be considered an addition to the main building. Includes structures regardless of whether a Building Permit is required, including, but not limited to, enclosed and unenclosed patios, barns, guesthouses, second dwelling units, garages, carports, storage buildings/sheds, trellis, gazebos, decks, and real or artificial rockscapes.

“Structure, temporary” means a structure without any foundation or footings and which is removed when the designated time period, activity, or use for which the temporary structure was erected has ceased.

“Target population” means persons with low incomes who have one or more disabilities, including mental illness, HIV or AIDS, substance abuse, or other chronic health condition, or individuals eligible for services provided pursuant to the Lanterman Developmental Disabilities Services Act (Division 4.5 (commencing with Section 4500) of the Welfare and Institutions Code) and may include, among other populations, adults, emancipated minors, families with children, elderly persons, young adults aging out of the foster care system, individuals exiting from institutional settings, veterans, and homeless people.

“Temporary structure” is a structure without any foundation or footings, and which is removed when the designated time period, activity, or use for which the temporary structure was erected has ceased.

“Temporary use” means a use established for a designated period of time, with the intent to discontinue the use at the end of the designated time period.

“Traffic safety sight area” means a space that is set aside on a corner lot in which all visual obstructions, such as structures and plantings, which inhibit visibility and thus cause a hazard to traffic and pedestrian safety are prohibited.

“Transient basis” means a continuous period of two (2) weeks or less.

“Underutilized land” means land with a structure or structures that occupy only a small portion of the land and is being used significantly below its potential use.

“Use” means the purpose (type or extent) for which land or a building is arranged, designed or intended or for which either land or a structure is occupied or maintained.

“Use initiation” means the implementation of a use on a parcel or occupancy of a structure, or construction of substantial site improvements after a building permit has been issued, subject to determination by the director.

“Use, accessory” means a use which is incidental to, and customarily associated with, a specified principal use and which meets the applicable conditions set forth in this ordinance.

“Use, allowed” means a use listed by the regulation of any particular district as a permitted use within that district and permitted therein as a matter of right when conducted in accord with the regulations established by this Ordinance.

“Use, conditional” means a use listed by the regulations of any particular district as a conditional use within that district and allowable therein, solely on a discretionary and conditional basis, subject to development/design review or to a Conditional Use Permit, and to all other regulations established by this Code.

“Use, principal” means a use which fulfills a primary function of a household, establishment, institution, or other entity.

“Use, temporary” means a use established for a fixed period of time with the intent to discontinue such use upon the expiration of the time period.

“Variance” means a discretionary entitlement which permits the departure from the strict application of the development standards contained in this zoning code.

“Vehicle” means self-propelled device by which persons or property may be moved upon a highway, excepting a device moved by human power or used exclusively upon stationary rails or tracks.

“Wildlands” means any area of land that is essentially unimproved, in a natural state of hydrology, vegetation and animal life, and not under cultivation.

“Yard” means an open space that lies between the principal or accessory building or buildings and the nearest lot line.

“Zero Lot Line” means the location of a building on a lot in such a manner that one or more of the building's sides rest directly on a lot line.

“Zoning certificate of occupancy” means a permit issued by the community development department which allows the occupancy of a structure which conforms to all applicable provisions of this chapter and any and all conditions or requirements issued by the city or any of its departments, or by any other federal, state or local agency or body.

“Zoning district” means a portion of the city within which certain uses of land and structures are defined, and regulations are specified.

**CITY OF HANFORD PLANNING COMMISSION
STAFF REPORT
May 14, 2019- Continued from Tuesday, April 23, 2019**

PROJECT: **Municipal Code Amendment No. 2019-01** is a request to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections, in order to permit the following uses in the C-R Regional Commercial zone district:

1. Amend the land use table in Section 17.08.030, deleting A20, ““Accessory or ancillary Office use; medical, dental, or optometry, that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use”;
2. Amend the land use table in Section 17.08.030 C5 to add “College or university, public or private,” as a permitted use, with a conditional use permit, in the C-R Regional Commercial zone district;
3. Amend the land use table in Section 17.08.030 C14 to add “Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar,” as a permitted use in the C-R Regional Commercial zone district;
4. Amend the land use table in Section 17.08.030 E1 to add “Business support service,” as a permitted use in the C-R Regional Commercial zone district;
5. Amend the land use table in Section 17.08.030 E4 to add “Laboratory; general, medical or dental,” as a conditionally permitted use in the C-R Regional Commercial zone district;
6. Amend the land use table in Section 17.08.030 E6 to add size breakdowns for “Office; medical, dental, or optometry” to permit and conditionally permit the use in multiple zone districts;
7. Amend the land use table in Section 17.08.030 E7 to add size breakdowns for “Office; professional or commercial” to permit or conditionally permit the use in multiple zone districts;
8. Amend the land use table in Section 17.08.030 G5 to add “Health or fitness facility, large” as a permitted use, with a conditional use permit, in the C-R Regional Commercial zone district;
9. Amend the land use table in Section 17.08.030 I16-I18 to allow “Furniture stores (without size restrictions)” as a permitted use in the C-R Regional Commercial, MX-C Corridor Mixed Use, and MX-D Downtown Mixed Use zone districts;
10. Amend the land use table in Section 17.08.030 J14 to add “Food catering,” as a permitted use in the C-N Neighborhood Commercial, C-R Regional Commercial, and MX-N Neighborhood Mixed Use zone district; and

Attachment: Staff Report - MCA 2019-01.docx (MCA 2019-01)

11. Amend the land use table in Section 17.08.030 to reflect deletions and additions of land uses, necessitating the renumbering of various land uses; and
12. Amend Chapter 17.96 Definitions of Land Uses to reflect deletions and additions of land uses, necessitating the renumbering of various land use definitions.

PROJECT PLANNER: Darlene R. Mata, Community Development Director

STAFF RECOMMENDATION

Staff is not recommending approval of all the requested amendments. Staff recommendation is described in the staff report and shown as attached to Resolution 2019-07. Staff recommends that the Planning Commission adopt Resolution 2019-07, recommending approval of Municipal Code Amendment No. 2019-01 to the City Council.

RECOMMENDED MOTION

1. I move to adopt Resolution 2019-07, recommending approval of Municipal Code Amendment No. 2019-01 to the City Council.

BACKGROUND INFORMATION

General Plan and Zoning Ordinance Update

In 2017, the City Council adopted the comprehensive update of the 2035 General Plan and subsequent Zoning Ordinance. The efforts to update the General Plan and Zoning Ordinance began in 2013 and included 16 meetings of the Citizens Advisory Committee – a group of citizens appointed by the City Council tasked with recommending a Draft General Plan Policy Document and Land Use Map to the legislative bodies and reviewing specific landowner requests for various land uses. A Joint Committee, comprised of the Planning Commission and City Council, also held six public meetings and a town hall to review the Zoning Ordinance Update.

The 2035 General Plan is a long range vision of the City of Hanford's future development through the year 2035. The General Plan is comprised of the General Plan Background Report and the General Plan Policy Document, which together make up the General Plan. The General Plan Background Report summarizes information on the issues addressed in the General Plan, focusing on existing conditions and trends as they existed in the year 2013, when the General Plan Update process began. The General Plan Policy Document includes goals, policies, maps, and tables that describe how Hanford plans to grow and develop during the Planning period, which is 2017 to 2035.

The Zoning Ordinance Update was prepared to be consistent with the 2035 General Plan Update, as required by State law. The Zoning Ordinance has been updated comprehensively upon the approval of each previous General Plan Update. Major updates to the Zoning Ordinance occurred in 1985, 1994, and 2002. As part of the Zoning Ordinance Update, a master table in Chapter 17.08 was added to identify permitted, conditional, administrative, and temporary uses allowed in the various districts. The addition of this matrix was a major change from the previous zoning

ordinances. Since adoption of the Zoning Ordinance update in 2017, the only text amendments to the matrix have been cannabis related.

Previous Requests

In 2014, Costco Wholesale requested to add “Optical Retailers, including eye examinations, within a department store” as a permitted use in the PC Planned Commercial zone district (as part of the General Plan Update, the PC Planned Commercial zone district no longer exists and is now the C-R Regional Commercial zone district). The request was denied by the City Council.

PROJECT DESCRIPTION

The applicant submitted Municipal Code Amendment No. 2019-01 in order to modify the permitted and conditionally permitted uses in the C-R Regional Commercial zone district. The uses listed below are not currently allowed uses in the C-R zone, and are requested to be allowed as follows:

#	Land Use	Applicant Proposal
Education, Religious, and Assembly Uses		
C5	College or university, public or private	C
C14	Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar	C
Office and Medical Uses		
E1	Business support service	P
E4	Laboratory; general, medical or dental	P
E6	Office; medical, dental, or optometry	P
E7	Office; professional or commercial	P
Public and Quasi-Public Uses		
F9	Government office; local, state, or federal	C
Recreation Uses		

G5	Health or fitness facility, large	P
Retail Uses		
I18	Furniture store with over 20,000 sq. ft. of floor space devoted to the display and sale of furniture	C
I20	Landscape nursery	P
Service Uses		
J3	Bank or credit union, secondary branch	P
J14	Food catering	C
J21	Payday lenders or check cashing establishment	C
J32	Tailoring or clothing alterations	P

The application is attached – **Attachment 1.**

PROJECT EVALUATION

Education, Religious, and Assembly Uses

C5) College or University, Public or Private

The applicant has requested to amend the land use table in Section 17.08.030 C5 to add “College or university, public or private,” as a permitted use with a conditional use permit in the C-R Regional Commercial zone district.

Staff Analysis: In accordance with the land use table in Section 17.08.050 C13, “School; charter, trade, vocational, art, business, or professional,” is already a permitted use with a conditional use permit in the C-R Regional Commercial zone district.

Definitions:

- “College or university, private or public” means a school or group of schools that provides post-secondary education usually resulting in a degree. (C5)
- “School; charter, trade, vocational, business, or professional,” means a facility that is operated either with public funds under a charter contract or with private funds, and that offers specific educational instruction to children and/or adults. This use includes charter

schools, secretarial schools, beauty and cosmetology schools, modeling schools, language schools, computer electronics training schools, art schools, and automotive repair schools, and similar specialized schools.” (C13)

In accordance with the General Plan, higher education and vocational schools are not limited to specific land-use designations:

6.9.3 Colleges

Policy P68 Higher Education

Encourage the development of private and public institutions of higher education.

Policy P69 College of Sequoias

Support and promote College of the Sequoias as a region-serving institution of higher education.

Policy P70 Vocational Training Centers

Encourage the expansion and development of vocational training centers and programs to support the growth of the Kings Industrial Park and other trades in the Hanford area.

Allowing “Colleges and universities, private or public” does not conflict with the purpose of the Regional Commercial land use designation.

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Staff Recommendation: Amend the land use table in Section 17.08.030 C5 to add “College or university, public or private,” as a conditional use in the C-R Regional Commercial zone district. The use is similar to an already allowed use within the zone district - School; charter, trade, vocational, business, or professional, and will not conflict with the purpose of the Regional Commercial land use designation. Requiring a conditional use permit for the use will allow discretionary review and approval of the use.

C14) Studio for Martial Arts, Music, Dance, Yoga, Exercise, Gymnastics or Similar

The applicant has requested to amend the land use table in Section 17.08.030 C14 to add “Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar,” as a conditionally permitted use in the C-R Regional Commercial zone district.

Staff Analysis: In accordance with the land use table in Section 17.08.050 G6, “Health or fitness facility, small,” is already a permitted use in the C-R Regional Commercial zone district.

Definitions:

- “Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar” means a facility that provides group or individualized instruction in a specific activity typically related to the arts. This use does not include Health or fitness facility. (C14)
- “Health or Fitness Facility, small” means a fitness center, health club or athletic club that typically charges a membership fee and does not include any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G6)

Allowing “Studios for martial arts, music, dance, yoga, exercise, gymnastics or similar” would not conflict with the purpose or typical uses in the Regional Commercial land use designation.

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Amend the land use table in Section 17.08.030 C14 to add “Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar,” as a permitted use in the C-R Regional Commercial zone district. The use is similar to an already allowed use within the zone district – Health or fitness facility, small, and will not conflict with the purpose of the Regional Commercial land use designation.

Office and Medical Uses

Currently, office uses are not permitted in the C-R Regional Commercial zone district.

The General Plan specifies the intent of the Corridor Mixed Use, Downtown Mixed Use, Office, and Office-Residential land use designations to provide for offices. Therefore, staff recommends offices over 6,000 square feet, would be limited to the MX-C Corridor Mixed Use, MX-D Downtown Mixed Use, O Office, and O-R Office-Residential zone districts.

3.6 Mixed Land Use

The intent of the mixed-use land use designations is to provide for a mixture of stores, services, restaurants, offices, and homes (dwelling units) in close proximity, thereby allowing residents to work and shop close to home and reduce the length and frequency of trips between home, work, shopping, and services. This contributes to opportunities to increase the use of public transit, reduce auto dependency, provide a wider range of

housing choices, and promote activity during more hours of the day. Both vertical and horizontal mixed-use developments are encouraged in the mixed use designations. The Hanford Zoning Ordinance provides the enforcement mechanism to implement the identified policies.

3.6.2 Corridor Mixed Use

Policy L65 Purpose of Corridor Mixed Use Land Use Designation

Establish the Corridor Mixed Use land use designation to promote a mix of commercial, office, and multi-family residential uses along transportation corridors at a scale compatible with adjacent residential neighborhood, with the intent of creating a pedestrian-friendly environment that encourages walking between uses.

Policy L66 Typical Uses in Corridor Mixed Use Land Use Designation

Define the uses allowed in the Corridor Mixed Use land use designation to include small- and medium- scale commercial providing primarily day-to-day goods and services, office, and multi-family dwellings along with horizontal and vertical mixed use developments that include these uses. Typical uses include duplexes, townhomes, apartments, markets, small retail shops, eating establishments, offices, service stations, medical and dental offices, convenience stores, dry cleaning and laundry services, beauty salons, and other similar uses. Both vertical and horizontal mixed-use developments are encouraged.

3.6.3 Downtown Mixed use

Policy L69 Purpose of Downtown Mixed Use Land Use Designation

Establish the Downtown Mixed Use land use designation as a unique pedestrian-oriented, multi-story, concentrated area of shopping, entertainment, eating establishments, high density housing, and offices primarily served by on-street or public parking concentrated in the historic center of Hanford to serve the entire community.

Policy L73 Offices in Downtown

Encourage local-serving offices to locate in the Downtown.

3.7.1 Office

Policy L74 Purpose of Office Land Use Designation

Establish the Office land use designation to support professional, non-retail businesses, along with medical and health care needs in a large campus-style setting as part of a resilient economic base.

Policy L75 Typical Uses in Office Land Use Designation

Define the uses allowed in the Office land use designation to include professional and medical businesses and institutions typically found in an office building or campus

environment. Typical uses include professional offices, medical offices, hospitals, and medical clinics.

3.7.2 Office Residential

Surrounding much of the historical downtown are older homes, some of which are in the process of converting from conventional single family units to offices. Many of these structures are large and have stunning architectural features that add significantly to the atmosphere of the downtown.

Policy L79 Purpose of Office Residential Land Use Designation

Establish the Office Residential land use designation to preserve and enhance existing residential structures by allowing them to convert to offices, bed and breakfast inns, or a combination of office and residential units.

Staff reviewed the ordinances for Visalia, Tulare and Clovis. These cities allow offices in the regional or community level commercial, however, the City of Hanford General Plan, as stated above, does not contain provisions for offices in the C-R zone. Although large scale offices should not be permitted based on the General Plan, some limited small offices may be appropriate to support the regional uses. Staff proposes to amend the land use table to divide office land uses into size categories:

- Offices less than 2,000 square feet;
- Offices between 2,000 – 6,000 square feet; and
- Offices over 6,000 square feet

Staff recommends small offices, under 2,000 sq. ft. be permitted in the C-R zone district, in addition to all zone districts offices are currently permitted in. Staff also recommends offices between 2,000 sq. ft. and 6,000 sq. ft. be permitted with approval of a conditional use permit. Offices over 6,000 square feet shall not be permitted uses in the C-R Regional Commercial zone district.

E1) Business Support Service

The applicant has requested to amend the land use table in Section 17.08.030 E1 to add "Business support service," as a permitted use in the C-R Regional Commercial zone district.

Staff Analysis: In accordance with the land use table in Section 17.08.030 J9, "Copy, printing or mailing service," is a permitted use in the C-R Regional Commercial zone district.

Definitions:

- "Business support service," means an establishment providing primarily other businesses with a mix of services that can include word processing, desktop publishing, spreadsheet design, telephone answering, mail receiving and forwarding, packing and shipping, bookkeeping, and photocopying, and can include indoor storage rental, and/or small office space rental when provided with these services.

- “Copy, printing, or mailing service,” means an establishment providing printing, photocopying, engraving, binding, packaging, mailing and related services to both businesses and individuals.

Staff Recommendation: Amend the land use in Section 17.08.030 E1 to add “Business support service,” as a permitted use in the C-R Regional Commercial zone district. The use is similar to an already allowed use within the zone district – Copy, printing, or mailing service, and will not conflict with the purpose of the Regional Commercial land use designation.

E4) Laboratory; General, Medical or Dental

The applicant has requested to amend the land use table in Section 17.08.030 E4 to add “Laboratory; general, medical or dental,” as a permitted use in the C-R Regional Commercial zone district.

In the C-R Regional Commercial zone districts, “Urgent care center(s) or other walk-in clinic(s) are permitted, with a conditional use permit.

Definitions:

- “Laboratory; general, medical, or dental,” means a facility that conducts scientific or medical experiments, research, or teaching, typically within a completely enclosed building.
- “Urgent care center or other walk-in clinic,” means a facility that provides medical treatment of injuries or illnesses that do not require treatment typically provided in an emergency, typically without an appointment. This use includes urgent care centers, free clinics, hospital based health clinics, and community health care clinics, but does not include ancillary retail clinics located within a retail store, food market, or pharmacy.”

Allowing “Laboratories; general, medical, or dental” does not conflict with the purpose of the Regional Commercial land use designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Staff Recommendation: Amend the land use table in Section 17.08.030 E4 to add “Laboratory; general, medical or dental,” as a permitted use, with a conditional use permit, in the C-R Regional Commercial zone district. The use is similar to an already allowed medical use within the zone district - Urgent care centers or other walk-in clinics - and will not conflict with the purpose of the Regional Commercial land use designation. Staff is supportive of the use with a conditional use permit. Requiring a conditional use permit for the use will allow discretionary review and approval of the use.

E6) Office; Medical, Dental, or Optometry

The applicant has requested to amend the land use table in Section 17.08.030 E6 to add “Office; medical, dental, or optometry,” as a permitted use in the C-R Regional Commercial zone district.

As mentioned earlier, office uses are currently not permitted in the C-R Regional Commercial zone district. Staff proposes to amend the land use table to divide office land uses into size categories:

- Offices less than 2,000 square feet;
- Offices between 2,000 – 6,000 square feet; and
- Offices over 6,000 square feet

Staff recommends small offices, in which under 2,000 sq. ft. be permitted in the C-R zone district, in addition to all zone districts offices are currently permitted. Staff also recommends offices between 2,000 sq. ft. and 6,000 sq. ft. be permitted, with approval of a conditional use permit. Offices over 6,000 square feet shall not be permitted uses in the C-R Regional Commercial zone district.

In the C-R Regional Commercial zone districts, “Urgent care center(s) or other walk-in clinic(s),” are permitted with, a conditional use permit.

Definitions:

- “Office; medical, dental, or optometry” means an establishment that provides services, typically by appointment, dealing with human health including dental, chiropractic, medical, optometry, physical therapy, psychology, psychiatry, family counseling, or therapy. This use does not include Barbershop, hair salon, nail care, massage therapy, or day spa.
- “Urgent care center or other walk-in clinic,” means a facility that provides medical treatment of injuries or illnesses that do not require treatment typically provided in an emergency, typically without an appointment. This use includes urgent care centers, free clinics, hospital based health clinics, and community health care clinics, but does not include ancillary retail clinics located within a retail store, food market, or pharmacy.”

Allowing “Offices; medical, dental, or optometry” does not conflict with the purpose of the Regional Commercial land use designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Staff Recommendation: The use is similar to an already allowed medical use within the zone district - Urgent care centers or other walk-in clinics - and will not conflict with the purpose of the

Regional Commercial land use designation. Amend the land use table in Section 17.08.030 E6, as follows:

Commercial, Office, and Industrial Use Table																
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed																
		Commercial Zones				Mixed Use Zones			Industrial and Office Zones			Other Zones				
	Land Uses	C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	Specific Land Use Standards (See identified Section)
E6	Office; medical, dental, or optometry	P		P		P	P	P	P	P						
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P						
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P						
	Over 6,000 sq. ft.	P		P		P	P	P	P	P						

E7) Office; Professional or Commercial

Staff recommends small offices, in which under 2,000 sq. ft., be permitted in the C-R zone district, in addition to all zone districts offices are currently permitted. Staff also recommends offices between 2,000 sq. ft. and 6,000 sq. ft. be permitted with approval of a conditional use permit. Offices over 6,000 square feet shall not be permitted uses in the C-R Regional Commercial zone district.

In the C-R Regional Commercial zone districts, “Call centers,” are permitted with a conditional use permit.

Definitions:

- “Offices, professional or commercial” means an establishment that provides administrative, clerical, technical, professional or similar business services and typically where products or goods are not provided. Examples include escrow and title, insurance, mortgage, real estate, accounting, architecture, graphic design, finance, consulting, engineering, legal, and similar services.
- “Call center” means an office used primarily for receiving or transmitting a large volume of requests by telephone to administer product support or information inquiries from

consumers or to conduct telemarketing, solicitation of charitable or political donations, debt collection, or market research.

Allowing “Offices; professional or commercial” does not conflict with the purpose of the Regional Commercial land use designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Staff Recommendation: The use of a professional or commercial offices is similar to a call center, which is a type of professional office, requiring a conditional use permit in the C-R Regional Commercial zone district, and will not conflict with the purpose of the Regional Commercial land use designation. Amend the land use table in Section 17.08.030 E7, as follows:

Commercial, Office, and Industrial Use Table													
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed													
	Land Uses	Commercial Zones				Mixed Use Zones			Industrial and Office Zones			Other Zones	
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP PF CO
E7	Office; professional or commercial	P		P		P	P	P	P	P			
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P			
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P			
	Over 6,000 sq. ft.	P		P		P	P	P	P	P			

Since staff is recommending the addition of office land uses to the C-R Regional Commercial zone districts, it would also be necessary to amend the land use table in Section 17.08.030, deleting A20, “Accessory or ancillary Office use; medical, dental, or optometry, that the Community Development Director determines is customarily associated with, and subordinate to,

a primary permitted use.” With the addition of office land uses to the C-R Regional Commercial zone district, accessory or ancillary office uses will be permitted outright and categorized under Section 17.08.030 A21, “Other accessory or ancillary use or structure that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.

Public and Quasi-Public Uses

F9) Government Office; Local, State, or Federal

The applicant requests to amend the Land Use table in Section 17.08.030 F9 to add “Government office; local, state, or federal,” as a permitted use, with a conditional use permit, in the C-R Regional Commercial zone district.

“Government office; local, state, or federal” means a facility owned or operated by a local, state, or federal government that provides services to the public such as employment assistance, public assistance, motor vehicle registration and licensing services and similar activities commonly accustomed to having sizeable assemblages of people waiting for service, whether pedestrian or vehicular. This use does not include a government-owned facility that is more specifically defined in this chapter, such as fairgrounds, cemetery, post office, or public safety facility.

In accordance with the Municipal Code Land Use table, government offices are limited to the Downtown Mixed Use, Office, and Public Facility zone district. The General Plan supports these designations by the following policies:

Policy L70 Typical Uses in Downtown Mixed Use Land Use Designation

Define the uses allowed in the Downtown Mixed Use land use designation to include a wide range of retail, financial, governmental, professional, business, service, dining, and entertainment activities, along with high density residential dwellings. Typical uses include small retail shops, eating and drinking establishments, townhomes, apartments, markets, professional services, convenience stores, beauty salons, and other similar uses. Vertical and horizontal mixed-use developments are encouraged.

Policy L126 Downtown Government Offices

Locate new local, State, and federal offices in the Downtown area to the greatest extent possible.

Policy P78 City Government in Downtown

Locate all City government departments with the exception of Public Works and Fire Departments in the Downtown area.

3.9.4 Public Facilities

This Public Facilities land use designation is applied to parcels that are publicly owned and/or house publicly operated non-educational facilities, and is intended to meet the public service needs of Hanford. Public Facilities include fire protection and police

facilities, waste water treatment facility, Kings County Government offices and jail, Municipal Airport, cemeteries, Kings County Fairgrounds, storm water collection basins, and City and County maintenance yards.

3.7.1 Office

Policy L74 Purpose of Office Land Use Designation

Establish the Office land use designation to support professional, non-retail businesses, along with medical and health care needs in a large campus-style setting as part of a resilient economic base.

Staff Recommendation: Locating government offices; local, state, or federal, would be in conflict with the General Plan and would not be an appropriate use for the C-R Regional Commercial zone district. Government offices shall remain limited to the MX-D Downtown Mixed Use, O Office, and PF Public Facility zone districts.

Recreation Uses

G5) Health or Fitness Facility, Large

The applicant has requested to amend the land use table in Section 17.08.030 G5 to add “Health or Fitness Facility, Large,” as a permitted use in the C-R Regional Commercial zone district.

Staff Analysis: In accordance with the land use table in Section 17.08.050 G6, “Health or fitness facility, small,” is already a permitted use in the C-R Regional Commercial zone district and G2, “Commercial recreation facility, indoor,” is a conditionally permitted use in the District.

Definitions:

- “Health or fitness facility, large” means a fitness center, gymnasium, health club or athletic club that typically charges a membership fee and includes any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G5)
- “Health or Fitness Facility, small” means a fitness center, health club or athletic club that typically charges a membership fee and does not include any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G6)
- “Commercial recreation facility, indoor” means indoor recreational facilities that are operated as a business and open to the general public for an entry fee or pay per use. Examples include indoor uses such as, but are not limited to, a bowling alley, bounce house, skating rink, batting cage, miniature golf, swimming pool, climbing wall, arcade, and similar uses. Food and beverage service can be provided as an ancillary use. (G2)

Allowing health or fitness facilities, large, would not conflict with the purpose or typical uses in the Regional Commercial land use designation.

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Amend the land use table in Section 17.08.030 G5 to add “Health or fitness facility, large,” as a permitted use with a conditional use permit in the C-R Regional Commercial zone district. The use is similar to an already allowed use within the zone district – Health or fitness facility, small, an allowed use with a conditional use permit – Commercial recreation facility, indoor, and will not conflict with the purpose of the Regional Commercial land use designation.

Retail Uses**I18) Furniture Store with over 20,000 Square Feet of Floor Space Devoted to the Display and Sale of Furniture**

The applicant requests to amend the land use table in Section 17.08.030 I18 of the Hanford Municipal Code to allow “Furniture store(s) with over 20,000 sq. ft. of floor space devoted to the display and sale of furniture,” as a permitted use with a conditional use permit in the C-R Regional Commercial zone district.

Definition: “Furniture store” means an establishment that provides large and small furniture for living spaces such as homes and offices. Items sold normally include beds, tables, chairs, sofas, desks, and shelves. Home appliances, outdoor/patio furniture, wall cabinets, garage storage units, and home furnishing accessories are items sold that are excluded from the definition of furniture store. (I16, I17, I18)

Currently, furniture stores are broken down into three different categories, as follows:

Commercial, Office, and Industrial Use Table P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed															
		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones		
	Land Uses	C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO
															Specific Land Use Standards (See identified Section)
I16	Furniture store with less than 15,000 <u>sq.ft.</u> of floor space devoted to the display and sale of furniture		P				P	P							
I17	Furniture store with 15,000 to 20,000 <u>sq.ft.</u> of floor space devoted to the display and sale of furniture		C				C	P							
I18	Furniture store with over than 20,000 <u>sq.ft.</u> of floor space devoted to the display and sale of furniture							P							

Background:

Under the previous Municipal Code 2002, “furniture stores,” were permitted in the CC Community Commercial zone district (comparable to today’s MX-C Corridor Mixed Use zone district) and the DC Downtown Commercial zone district (comparable to today’s MX-D Downtown Mixed Use zone district). “Furniture stores (used only),” was a permitted use in the SC Service Commercial zone district (comparable to today’s C-S Service Commercial zone district). As a part of the General Plan Update, size limitations were added to allow specific square footages of furniture sales and display in the C-R Regional Commercial, MX-C Corridor Mixed Use, and MX-D Downtown Commercial zone districts.

Staff recommends the size limitations for furniture stores be eliminated and furniture stores be added as permitted uses in the following zone districts: C-R Regional Commercial, MX-C Corridor Mixed Use, and MX-D Downtown Mixed Use. The General Plan does not contain any provisions which would preclude furniture from being allowed as proposed.

Commercial, Office, and Industrial Use Table														
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed														
Land Uses	Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones		
	C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO
I16 Furniture store		P				P	P							
I16 Furniture store with less than 15,000 sq. ft. of floor space devoted to the display and sale of furniture		P				P	P							
I17 Furniture store with 15,000 to 20,000 sq. ft. of floor space devoted to the display and sale of furniture		C				C	P							
I18 Furniture store with over than 20,000 sq. ft. of floor space devoted to the display and sale of furniture							P							

The eliminations of the size restrictions will result in the requirement to renumber the Retail Use category from I19 through I20, as well as their corresponding definition numbers.

I20) Landscape Nursery

The applicant has requested to amend the land use table in Section 17.08.030 I20 to add "Landscape nursery" as a permitted use in the C-R Regional Commercial zone district.

Currently, landscape nurseries are permitted in C-S Service Commercial and are permitted with a conditional use permit in the MX-C Corridor Mixed Use, I-L Light Industrial, I-H Heavy Industrial, and AP Airport Protection zone district.

A landscape nursery means a facility that grows, maintains, and provides trees, plants, and other nursery products for transplant in another location typically to both retailer and wholesale customers. (I20)

Often, landscape nurseries are located outdoors, which conflicts with the Section 17.18.150 General Provisions and Standards of the C-R Regional Commercial zone district, which states, “All businesses, services, and processes shall be conducted entirely within a completely enclosed permanently fixed structure.”

Staff Recommendation: The use conflicts with the Hanford Municipal Code Section 17.18.150 by providing an outdoor use, where all businesses services, and processes shall be conducted within a completely enclosed structure – therefore, staff does not support adding “landscape nursery,” as a permitted use in the C-R Regional Commercial zone district.

Service Uses

J3) Bank or credit union, secondary branch

The applicant has requested to amend the land use table in Section 17.08.030 J3 to add “Bank or credit union, secondary branch,” as a permitted use in the C-R Regional Commercial zone district.

Definition:

- “Bank or credit union, secondary branch” means an institution providing retail banking services that is a secondary or satellite branch in the city and either does not provide loan officers on site or only provides merchant bank services. This classification includes only those institutions engaged in the on-site circulation of money, including credit unions, but excluding a payday lender or check-cashing establishment. For administration, headquarters, or other offices of banks and credit unions without retail banking services with on-site circulation of money see Office, professional or commercial. (J3)

Staff Analysis: The use of a “Bank or credit union, secondary branch” is a day to day service, which, according to the General Plan, shall be prohibited in the Regional Commercial designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Locating “Banks and credit unions, secondary branches” would be in conflict with the General Plan and would not be an appropriate use for the C-R Regional Commercial zone district. “Banks and credit unions, secondary branches” shall remain limited to the C-N Neighborhood Commercial, MX-N Neighborhood Mixed Use, MX-C Corridor Mixed Use, and MX-D Downtown Mixed Use zone districts.

J14) Food Catering

The applicant has requested to amend the land use table in Section 17.04.030 J14 to add “Food catering” as a permitted use in the C-R Regional Commercial zone district.

Definition: Food catering” means an establishment that prepares and delivers food and beverages for off-site consumption, typically at a special event, without provision for on-site pickup or consumption. (J14)

Staff Analysis: Restaurants (Full service, limited service with drive-thru pick up window, and limited service without drive-thru pickup windows) are permitted in the C-R Regional Commercial zone district. The use is similar to an already allowed use within the zone, allowing food catering to be permitted in the C-R Regional Commercial zone district would not conflict with the General Plan for the Regional Commercial land use designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Amend the land use table in Section 17.04.030 J14 to allow “food catering” as a permitted use in the C-R Regional Commercial zone district.

J21) Payday Lenders and Check-Cashing Establishment

The applicant requests to amend the land use table in Section 17.08.030 J21 to allow, “Payday lenders or check cashing establishment” as a permitted use, with a conditional use permit, in the C-R Regional Commercial zone district.

Definition:

- Payday lender or check cashing establishment” is an establishment that cashes checks, warrants, or money orders for a fee, and/or provides short term loans, usually at a high

interest rate, that must be paid in full when the borrower receives their next pay check. This use does not include Bank or credit union. (J21)

Staff Analysis: The use of a “Payday lender or check cashing establishment,” is a day-to-day service, which, according to the General Plan shall be prohibited in the Regional Commercial designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Allowing “Payday lenders and check cashing establishments” would be in conflict with the General Plan and would not be an appropriate use for the C-R Regional Commercial zone district. Payday lenders and check-cashing establishment shall remain limited to permitted uses with a conditional use permit in the C-S Service Commercial, MX-C Corridor Mixed Use, and MX-D Downtown Mixed Use zone districts.

J32) Tailoring or Clothing Alterations

The applicant requests to amend the land use table in Section 17.08.030 J32 to allow, “Tailoring or clothing alterations,” as a permitted use in the C-R Regional Commercial zone district.

Definition:

- “Tailoring or clothing alterations” means an establishment that provides custom making or altering of clothing when not an ancillary use in a clothing store. (J32)

Staff Analysis: The use “Tailoring or clothing alterations” is a day-to-day service, which is according to the General Plan shall be prohibited in the Regional Commercial designation:

3.5.2 Regional Commercial

Policy L47 Purpose of Regional Commercial Land Use Designation

Establish the Regional Commercial land use designation to provide a variety of commercial goods, entertainment, and services in large format shopping centers for both the Hanford community and the larger region outside of Hanford.

Policy L48 Typical Uses in Regional Commercial Land Use Designation

Define the uses allowed in the Regional Commercial land use designation to include goods, entertainment, and services that benefit from the market synergy that occurs when the uses are located in close proximity to each other. Typical uses include retail sales in big box or large format buildings, shopping malls, eating establishments, and service stations. Prohibit uses that typically provide only day-to-day goods and services.

Staff Recommendation: Allowing tailoring and clothing alteration would be in conflict with the General Plan and would not be an appropriate use for the C-R Regional Commercial zone district. Tailoring and clothing alterations shall remain limited to permitted uses C-N Neighborhood Commercial, C-S Service Commercial, MX-N Neighborhood Commercial, MX-C Corridor Mixed Use, MX-D Downtown Mixed Use, and O-R Office Residential zone districts.

A copy of the proposed updates to the Land Use Table in Section 17.08.030 and the Land Use Definitions if attached – Attachment 2.

FINDINGS FOR APPROVAL

In accordance with Section 17.86.030, before a zone change or text amendment may be approved, all of the following findings shall be made by the reviewing authority:

1. That the amendment is internally consistent with the goals, objectives, and policies of the General Plan and Zoning Ordinance;

Analysis: That each amendment request has been individually evaluated for consistency with the General Plan and recommended for approval if deemed consistent with the goals, objectives, and policies of the General Plan and Zoning Ordinance.

2. That the amendment would not be detrimental to the public health, safety, or welfare of the community;

Analysis: That each use proposed is currently permitted within the City of Hanford and would not be detrimental to the public health, safety, or welfare of the community.

3. That the amendment would maintain the appropriate balance of land uses within the City; and

Analysis: That jobs-housing balance is achieved, by increasing opportunities for people to work and live in close proximity. The ratio is expressed as the number of jobs divided by the number of housing units. The jobs-housing balance is a general tool for analyzing where people work, where they live, and how effectively they can travel between the two. In the planning area, the existing jobs-housing balance ratio in 2013-2014 was 1.17. It is estimated that the implementation of the General Plan would increase the jobs-housing balance by 0.45 to 1.62, which would make the planning area a jobs-rich area. The proposed text amendments recommended for approval are all consistent with the General Plan and will not affect the City's ability to maintain an appropriate balance of land uses within the City.

4. That the anticipated land uses on the subject site would be compatible with existing and future surrounding uses.

Analysis: That each use was evaluated for consistency with the General Plan and Zoning Ordinance, in order to ensure the proposed uses would be compatible with existing and future land uses within their prospective districts.

ENVIRONMENTAL ASSESSMENT

Pursuant to Section 15061 (b) (3) of the California Environmental Quality Act (CEQA) guidelines, the project is exempt from environmental review. A Notice of Exemption has been prepared for the project in accordance with CEQA – **Attachment 3**.

PUBLIC COMMENTS

Noticing of the Municipal Code Amendment was published in the newspaper on April 12, 2019. The Community Development Department has not received comments on the project as of the preparation of this report.

Applicant

198-43 LLC
265 E River Park Circle; Suite 270
Fresno, CA 93720



CITY OF HANFORD

Application for: MUNICIPAL CODE (ZONE TEXT) AMENDMENT NO. 2019-01

City of Hanford
Community Development Department
317 N. Douty Street
Hanford, CA 93230
(559) 585-2580 FAX: (559) 583-1633

Application Fee: 6,771.00
Environmental Review Fee: _____
Other Fees: _____
Total Fees: _____
Receipt No. 14112284 Date: 2/22/19
Env. Rev. No. _____ File # 512-0117

The purpose of this review is to determine if the proposal conforms with the provisions of the Zoning Ordinance. When filing is done by mail, the applicant's signature must be notarized. The following information is necessary and incomplete applications will not be accepted or acted upon. Please follow these directions and PRINT OR TYPE all information. If the information requested is not applicable, write NA in the space provided. Feel free to use attachments to better illustrate or explain the project.

PART A: GENERAL INFORMATION

	OWNER	APPLICANT	AGENT/CONSULTANT
NAME	<u>198-43 LLC</u>		
ADDRESS	<u>265 E River Park Circle Ste 270</u>		
CITY	<u>Fresno CA 93720</u>		
PHONE	<u>559 696-9584</u>		

DESCRIPTION OF PROPOSED TEXT CHANGE: _____

SEE ATTACHED LIST OF LAND USES

PART B: PUBLIC HEARING REQUIREMENT

Notice of the public hearing shall be given not less than ten (10) days prior to the date of the public hearing by publication of a notice of the time and place of the hearing in a newspaper of general circulation published and circulated with the city. Noticing will be done by city staff.

PART C: REQUIRED FINDINGS

Please explain why or how the proposal meets the following statements (use separate sheet if additional space is required):

- A. The addition of the use to the list of zone uses will be in accordance with the purposes of the district in which the use is proposed.

THE ADDITIONAL USES ARE ALL
COMMERCIAL ENTERPRISES

- B. The use has the same basic characteristics as the present uses allowed in the district.

THE USES ALL REQUIRE
COMMERCIAL BUSINESS LICENSES

- C. The use will conform with the required conditions prescribed for the district.

YES; MAXIMUM BUILDING HEIGHT,
PARKING REQUIREMENTS, CITY SERVICES
SUCH AS WATER, SEWER, STORM WATER
HANDLING, TRASH PICK-UP

- D. The use will not be detrimental to the public health, safety or welfare.

NO THEY WILL NOT; POINT OF
FACT, MANY OF THE OTHER CITIES IN
THE SAN JOAQUIN VALLEY ACCOMMODATE
THESE USES IN A VERY SIMILAR
MANNER.

- E. The use will not generate a greater volume of vehicular traffic than any other use allowed in the district.

THE INSTITUTE OF TRANSPORTATION
ENGINEERS (8TH EDITION) CONFIRMS THAT
THE ADDITIONAL USES WILL NOT GENERATE
ANY MORE TRAFFIC THAN WHAT IS
EXPECTED FOR EXISTING REGIONAL COMMERCIAL
USES

- F. The use will not generate a greater amount of odor, dirt, smoke, noise, vibration, illumination, glare, unsightliness or any other objectionable influence or hazard than the amount normally created by any of the other uses permitted in the district.

AGREED


Signature of Applicant

s:\commdev\planning\municipalcodeamendment\MCA form.doc

Modify the City of Hanford's Municipal Code, Section 17.08.030, for Regional Commercial ("C-R"), as follows:

LAND USES

- | | |
|------|--|
| A 19 | "P" (Permitted by right) - VENDING MACHINES |
| C 5 | "C" (Conditional use permit required) - COLLEGE OR UNIVERSITY, PUBLIC OR PR |
| C 14 | "P" (Permitted by right) - STUDIO FOR MARTIAL ARTS, MUSIC, DANCE, YOGA, GYMNASIICS OR SIM |
| E 1 | "P" (Permitted by right) - BUSINESS SUPPORT SERVICE |
| E 4 | "P" (Permitted by right) - LABORATORY; GENERAL, MEDICAL OR DENTAL |
| E 6 | "P" (Permitted by right) - OFFICE; MEDICAL, DENTAL, OR OPTOMETRY |
| E 7 | "P" (Permitted by right) - OFFICE, PROFESSIONAL OR COMMERCIAL |
| F 9 | "C" (Conditional use permit required) - GOV'T OFFICE; LOCAL, STATE, OR FEI |
| G 5 | "P" (Permitted by right) - HEALTH OR FITNESS FACILITY, LARGE. |
| I 18 | "C" (Conditional use permit required) - FURNITURE STORE WITH OVER 20,000 OF FLOOR SPACE DEVOTED TO THE SALE DISPLAY OF FURNITU |
| I 20 | "P" (Permitted by right) - LANDSCAPE NURSERY |
| J 3 | "P" (Permitted by right) - BANK OR CREDIT UNION, SECONDARY BRANCH |
| J 14 | "C" (Conditional use permit required) - FOOD CATERING |
| J 21 | "C" (Conditional use permit required) - PAYDAY LENDERS OR CHECK-CASHING ESTABLISHM |
| J 32 | "P" (Permitted by right) - TAILORING OR CLOTHING ALTERATIONS |

Attachment: Attachment 1 - Application (MCA 2019-01)

Chapter 17.08

LAND USE TABLES

Sections:

- 17.08.010** **Land use restriction.**
- 17.08.020** **Residential land use table.**
- 17.08.030** **Commercial, office, and industrial land use table.**
- 17.08.040** **Addition of a use to land use tables.**

17.08.010 Land use restriction.

No structure, or any part thereof, shall be erected, enlarged, or reduced, nor shall any site or structure be used, designated, or intended to be used for any purpose or in any manner other than is included among the uses listed in the land use tables in this chapter as permitted, administratively permitted, or conditionally permitted in the zone district in which such structure, land, or site is located, except as otherwise authorized by this title.

17.08.020 Residential land use table.

A. The following table identifies which land uses are permitted by right, require a use permit, or are not allowed in the R-L-12, R-L-8, R-L-5, R-M, and R-H zones.

B. A “P” means that the use is permitted by right in that zone. A “C” means the use requires a conditional use permit in that zone. An “A” means the use requires an administrative use permit in that zone. A “T” means the use requires a temporary use permit in that zone. A blank box means the use is not allowed in that zone.

C. Land uses are grouped generally by type of use, and then listed alphabetically. The land use groups are Accessory and Support Uses; Residential Uses; and Other Uses. Use of the word “or” can mean either or both uses.

D. Land uses with specific land use standards shall meet the requirements found in the identified Section in the last column of the table.

Table 17.08.020

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
	Residential Uses						
1	Assisted living, skilled nursing, or hospice facility	C	C	C	C	C	
2	Bed and breakfast inn				C		17.60.040
3	Boarding house or rooming house			C	C	C	
4	Emergency shelter				C	C	
5	Employee housing for six (6) or fewer employees	P	P	P	P	P	
6	Hotel or motel						
7	Manufactured home on permanent foundation	A	A	A			17.60.090
8	Mobilehome, not within a mobilehome park						17.60.090
9	Mobilehome park				C		17.60.100
10	Multi-family dwelling, two (2) units per building (duplex)			C	P	P	17.10.020

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
11	Multi-family dwelling, three (3) or four (4) units per building (triplex or fourplex)			C	P	P	17.10.020
12	Multi-family dwelling, five (5) or more units per building				P	P	
13	Recreational vehicle park			C	C		
14	Residential care facility, up to six (6) persons	P	P	P	P	P	
15	Residential care facility, seven (7) or more persons	C	C	C	C	C	
16	Single-family dwelling, attached			P	P	P	
17	Single-family dwelling, detached	P	P	P	P	P	
18	Single-room occupancy (SRO)					C	
19	Supportive housing	P	P	P	P	P	
20	Transitional housing	P	P	P	P	P	
	Residential Accessory and Support Uses						

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
30	Accessory dwelling unit	A	A	A	A	A	17.60.030
31	Building ancillary to the main residential use	P	P	P	P	P	
32	Cottage food operation	A	A	A	A	A	17.60.050
33	Expansion of existing nonconforming residential use	C	C	C	C	C	
34	Guest house	P	P	P			
35	Home occupation	A	A	A	A	A	17.78
36	Keeping of household pets	P	P	P	P	P	Title 6
37	Raising of fruit, vegetables, and horticultural specialties for personal use	P	P	P	P	P	
38	Temporary caretaker's dwelling	T	T	T	T	T	
39	Temporary materials storage yard	T	T	T	T	T	
40	Temporary residential sales office	T	T	T	T	T	

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
41	Other accessory or ancillary use or structure that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P	P	P	P	P	
	Other Uses						
50	Community center or facility	C	C	C	C	C	
51	Day care, up to eight (8) children	P	P	P	P	P	17.60.060
52	Day care, nine (9) to fourteen (14) children	A	A	A	A	A	17.60.060
53	Day care, over fourteen (14) children	C	C	C	C	C	17.60.060
54	Gas and electric transmission lines, electrical transmission and distribution substation, gas regulator station, communications equipment building, public service pumping station or elevated pressure tank	A	A	A	A	A	
55	Golf course or country club	C	C	C			
56	Mini-warehouse or self-storage facility		C				17.60.095

Residential Zone Use Table							
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed							
Land Uses		Single-family Residential Zones			Multi-family Residential Zones		Specific Land Use Standards (See identified Section)
		R-L-12	R-L-8	R-L-5	R-M	R-H	
57	Park or playground	P	P	P	P	P	
58	Religious institution or facility	C	C	C	C	C	
59	School, private (kindergarten to 12 th grade)	C	C	C			
60	School, public (kindergarten to 12 th grade)	P	P	P			
61	Storm drainage basin, with or without a park	P	P	P	P	P	
62	Land uses listed in the Commercial, Office, and Industrial Zone Use Table (Section 17.10.040) that are not listed in this Residential Zone Use Table						

17.08.030 Commercial, Office, and Industrial Zone Use Table

A. The following table identifies which land uses are permitted by right, require a use permit, or are not allowed in the C-N, C-R, C-S, C-H, MX-N, MX-C, MX-D, O-R, O, I-L, I-H, AP, PF, and CO zones.

B. A “P” means that the use is permitted by right in that zone. A “C” means the use requires a conditional use permit in that zone. An “A” means the use requires an administrative use permit in that zone. A “T” means the use requires a temporary use permit in that zone. A blank box means the use is not allowed in that zone.

C. Land uses are grouped generally by type of use, and then listed alphabetically. The land use groups are Accessory and Support Uses; Eating and Drinking Establishment Uses; Education, Religious, and Assembly Uses; Manufacturing and Processing Uses; Office and Medical Uses; Public and Quasi-Public Uses; Recreation Uses; Residential Uses; Retail Uses; Service Uses; Transportation and Storage Uses; and Other Uses.

D. Land uses with specific land use standards shall meet the requirements found in the identified Section in the last column of the table.

Table 17.08.030

Commercial, Office, and Industrial Use Table															
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed															
Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones		
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO
	Accessory and Support Uses														
A1	Automated teller machine (ATM)	P	P	P	P	P	P	P		P	P	P		P	
A2	Caretaker residence or quarters					A	A	A	A		A	A	A		
A3	Cottage food operation					A	A	A	A						17.60.050

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A4	Day care primarily for children of employees on the same site as a permitted use	P	P	P	P	P	P	P	P	P	P	P	P	P		17.60.060
A5	Drive-thru pick-up window, not in conjunction with a restaurant	P	P	P	P	P	P	C								17.60.070
A6	Electric vehicle recharging facility	A	A	A	A	A	A	A		A	A	A		A		
A7	Food service primarily for employees on the same site as a permitted use	P	P	P	P	P	P	P		P	P	P	P	P		
A8	Games of skill or amusement, eight (8) or less	P	P	P	P	P	P	P			P			P		
A9	Games of skill or amusement, more than eight (8)	C	C	C	C	C	C	C			C			C		
A10	Home occupation					A	A	A	A				A			17.78
A11	Keeping of household pets					P	P	P	P				P			Title 6
A12	Keeping of large animals as pets												P			Title 6

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A13	Mobile vending or food truck	C	C	C	C	C	C	C		C	C	C				
A14	Outdoor advertising structure															
A15	Outdoor storage ancillary to and on the same site as a permitted use	P	P	P	P	P	P	P			P	P	P	P		17.60.120
A16	Temporary materials and/or equipment storage yard	T	T	T	T	T	T	T		T	T	T	T	P		
A17	Temporary sales office (including parking lot)					T	T	T								
A18	Vending machines	P	P	P	P	P	P	P		P	P	P	P	P		17.60.150
A19	Accessory or ancillary Office use; medical, dental, or optometry, that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P		P	P	P	P	P	P	P	P	P	P	P		

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
A20	Other accessory or ancillary use or structure that the Community Development Director determines is customarily associated with, and subordinate to, a primary permitted use.	P	P	P	P	P	P	P	P	P	P	P	P	P	P	
	Eating and Drinking Establishment Uses															
B1	Artisan food and beverage production and sales	P	P	P	P	P	P	P			P					
B2	Bar, nightclub, or lounge		C	C	C		C	C								
B3	Brewpub	C	P	P	C	C	P	P								
B4	Microbrewery		C	P	C		C	C								
B5	Restaurant, full service	P	P	P	P	P	P	P								
B6	Restaurant, limited service with drive-thru pickup window	P	P	P	P	P	P	P								

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
B7	Restaurant, limited service without drive-thru pickup window	P	P	P	P	P	P	P								
	Education, Religious and Assembly Uses															
C1	Auditorium						P	P						P		
C2	Card room			C												
C3	Club, lodge, or private meeting hall			P			P	P								
C4	Carnival or circus		T	T	T		T	T								
C5	College or university, public or private		C	C			C	C						P		
C6	Convention or conference center				P		P	P								
C7	Funeral home or mortuary			P			C		P	C						
C8	Library, museum, or cultural facility						P	P								
C9	Pool hall or billiard parlor			C			C									

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
C10	Religious institution or facility			P			C	C		C	C					
C11	School, private (kindergarten to 12 th grade)													C		
C12	School, public (kindergarten to 12 th grade)													P		
C13	School; charter, trade, vocational, art, business, or professional		C	P			C	C	C	C	C			P		
C14	Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar	P	P	P		P	P	P		P	P					
C15	Theater, live or movie		P					P								
	Manufacturing and Processing Uses															
D1	Agricultural crop production											P	P	P	P	
D2	Agricultural products packing, packaging, preparing or processing										C	P	C			

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
D3	Animal raising												P			
D4	Brewery, winery, or distillery										C	C				
D5	Hazardous waste facility											C				
D6	Industrial or manufacturing facility, heavy											P				
D7	Industrial or manufacturing facility, light										P	P				
D8	Cannabis cultivation, manufacture, distribution, transportation and laboratory testing											C				See Chapters 5.56 and 17.69
D9	Meat packing or slaughterhouse											C				
D10	Mining, quarry, or sand and gravel excavation											C	C			
D11	Research and development facility			P	C					P	P	C				
	Office and Medical Uses															

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
E1	Business support service		P	P			P	P	P	P						
E2	Call center		C		C					C						
E3	Communications broadcasting or media studio			P			C	P		P	C					
E4	Laboratory; general, medical or dental		C	P	C		P	C		P	C					
E5	Hospital, general or psychiatric									P				P		
E6	Office; medical, dental, or optometry	P		P		P	P	P	P	P						
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P						
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P						
	Over 6,000 sq. ft.	P		P		P	P	P	P	P						
E7	Office; professional or commercial	P		P		P	P	P	P	P						
	Under 2,000 sq. ft.	P	P	P		P	P	P	P	P						
	2,000 – 6,000 sq. ft.	P	C	P		P	P	P	P	P						

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
	Over 6,000 sq. ft.	P		P		P	P	P	P	P						
E8	Pharmacy	P	P	P		P	P	P		P						
E9	Urgent care center or other walk-in clinic	P	C	C		P	P	P		P						
	Public and Quasi-Public Uses															
F1	Cemetery													P		
F2	Community center or facility	P		P		P	P	P								
F3	Community garden			P		P	P	P		P			P	P		
F4	Day care, up to eight (8) persons					P	P	P	P							17.60.060
F5	Day care, nine (9) to fourteen (14) persons			C		A	A	A	A							17.60.060
F6	Day care, over fourteen (14) persons			C		C	C	C	C							17.60.060

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table																
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed																
Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
F7	Electrical distribution and transmission and substation, gas regulator station, communications equipment building, public service pumping station or elevated pressure tank	A	A	A	A	A	A	A	A	A	A	A	A	A	A	
F8	Fairgrounds													P		
F9	Government office; local, state, or federal							P		P				P		
F10	Post office						P	P		P				P		
F11	Public corporation yard, utility yard, or vehicle and heavy equipment maintenance and storage yard										C	P	P	P		
F12	Public safety facility or station	P	P		P	P	P	P			P		P	P		
F13	Social service office, assistance center, or guidance center							P		C						
F14	Storm drainage basin, with or without a park	P	P	P	P	P	P			P	P	P	P	P	P	

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
F15	Wireless communication facility (WCF)		C	P	P		C	C		C	P	P		P		17.62
	Recreation Uses															
G1	Athletic complex or ball field													P		
G2	Commercial recreation facility, indoor	C	C	P	P	C	P	C			C					
G3	Commercial recreation facility, outdoor				C						C	C	C	C		
G4	Golf course or country club												C	C		
G5	Health or fitness facility, large		C	P	C		P	P		C						
G6	Health or fitness facility, small	P	P	P	P	P	P	P		P	C					
G7	Park or playground						P						P	P		
	Residential Uses															
H1	Assisted living, skilled nursing, or hospice facility					C	C	C	C							

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
H2	Bed and breakfast inn				C		C	C	C							17.60.040
H3	Boarding or rooming house				C	C	P	P								
H4	Emergency shelter								P					P		
H5	Employee housing for six (6) or fewer employees					P	P	P	P							
H6	Hotel or motel		C	C	P		P	P								
H7	Live/work facility			P		P	P	P	P							
H8	Mobile home park															17.60.100
H9	Multi-family dwelling, two (2) units per building (duplex)					P	P	P	P							
H10	Multi-family dwelling, three (3) or four (4) units per building (triplex or fourplex)					P	P	P	C							

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
H11	Multi-family dwelling, five (5) or more units per building					P	P	P								
H12	Recreational vehicle park				C						C					
H13	Residential care facility					P	P	P	P							
H14	Residential dwelling located in same building with office or commercial use			C		P	P	P	P				P			
H15	Single-family dwelling, attached					P	P	P								
H16	Single-family dwelling, detached					P	P	P	P				P			
H17	Single-room occupancy (SRO)						P	P	P							
H18	Supportive housing					P	P	P	P				P			
H19	Transitional housing					P	P	P	P				P			
	Retail Uses															
I1	Adult entertainment establishment		A	A			A									17.62

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I2	Auction or sales house			P			P	P								
I3	Auction or sales yard			C							C					
I4	Automobile and pick-up sales, new and used			P	P			P								17.60.140
I5	Automobile and pick-up sales, used only			P	P											17.60.140
I6	Boat, recreational vehicle (RV), and truck sales			P	C											
I7	Building materials and supply or home improvement store		P	P			P	P			C					
I8	Convenience store, with or without fuel sales	P	P	P	P	P	P	P			C					
I9	Farm or construction equipment sales or service			P	C											
I10	Farmers market		A	A				A						A		
I11	Feed and seed store			P							P					
I12	Food market	P	P	P	P	P	P	P								

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I13	Food produce stand	A	A	A	A	A	A			A	A	A	A	A		
I14	Fuel sales, fleet or cardlock			P	P						P	P		P		
I15	Fuel sales, retail	P	P	P	P	P	P	P			C					
I16	Furniture store		P				P	P								
I16	Furniture store with less than 15,000 sq.ft. of floor space devoted to the display and sale of furniture		P				P	P								
I17	Furniture store with 15,000 to 20,000 sq.ft. of floor space devoted to the display and sale of furniture		C				C	P								
I18	Furniture store with over than 20,000 sq.ft. of floor space devoted to the display and sale of furniture							P								
I19 I17	Garden shop		P	P			P	P								

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I20 I18	Landscape nursery			P			C				C	C	C			
I21 I19	Liquor store	P	P	P	P	P	P	P								
I22 I20	Manufactured home sales yard			C									C			
I23 I21	Cannabis dispensary or sales															See Chapters 5.56 and 17.69
I24 I22	News, magazine or flower stand, outdoor				C			P								
I25 I23	Optical retailers		P				P	P								
I26 I24	Pawn shop			P				P								
I27 I25	Pet store	P	P	P		P	P	P								
I28 I26	Retail sales store	P	P	P	P	P	P	P								Also see Lines I16, I17, and I18 related to sales of furniture

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
I29 I27	Retail sales solely via internet, direct mail, or telephone			P			P		C	C						
I30 I28	Secondhand or thrift store			P			P									
I31 I29	Swap meet or flea market			C							C	C		C		
I32 I30	Tobacco or smoke shop		C	P	P		P	P								
	Service Uses															
J1	Ambulance service			P			P			C						
J2	Bank or credit union, main branch						P									
J3	Bank or credit union, secondary branch	P				P	P	P								
J4	Barber shop, hair salon, nail care, massage therapy, or day spa	P	P	P	P	P	P	P	C	C	C					
J5	Car wash, automatic or full service	C	C	P	P	C	P									
J6	Car wash, self-service			C	C		C									

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J7	Carpet cleaning and dyeing			P			C				P					
J8	Construction materials recycling											C		P		
J9	Copy, printing, or mailing service	P	P	P	P	P	P	P		P	P					
J10	Crematorium or columbarium			C			C				C					
J11	Dry cleaning or laundromat	P		P	P	P	P	P								
J12	Equipment rental yard			P							P					
J13	Exterminator or pest control service			P			P	C			P	P				
J14	Food catering	P	P	P		P	P	P	C							
J15	Fortunetelling			P							P					
J16	Fuel distributing			P							P	P				
J17	Kennel or animal boarding			P	P		C				C					
J18	Linen, diaper, or uniform supply service			P							P	P				

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J19	Motor vehicle repair or service, major			P	P		C				P	P				
J20	Motor vehicle repair or service, minor		C	P	P		P	C			P					
J21	Payday lenders or check cashing establishment			C			C	C								
J22	Pet grooming	C	C	P		C	P	C								
J23	Photography studio	P	P	P		P	P	P	C	P						
J24	Recycling, small collection facility (CRV only)	P	P	P	P	P	P	P			P			P		
J25	Recycling, large collection facility			C							P	P		P		
J26	Recycling, processing or sorting facility										C	C				
J27	Repair shop, large appliance or equipment			P			P	C								
J28	Repair shop, small appliance or equipment	C		P		C	P	P	C							
J29	Shooting range, indoor			C							C		C	C		
J30	Shooting range, outdoor															

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
J31	Specialty construction or trade service			P							P	P				
J32	Tailoring or clothing alterations	P		P		P	P	P	P							
J33	Tattooing or body art			C			C	P								
J34	Veterinary clinic or office		C	P			C			P						
J35	Veterinary hospital										C		C			
	Transportation and Storage Uses															
K1	Airport or heliport												P	P		
K2	Bus, transit, or train station							P						P		
K3	Cold storage or ice house			C							P	P	P			
K4	Food locker			P							P		P	P		
K5	Junk yard, wrecking yard, or salvage facility											C				
K6	Mini-warehouse or self-storage facility			P	C		C				C					

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table

P = Use is Permitted by Right C = Use Requires Conditional Use Permit
 A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit
 Blank = Use is Not Allowed

Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones			Specific Land Use Standards (See identified Section)
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO	
K7	Parking facility, off-site		C	C				C		C						
K8	Truck stop or travel center				C											
K9	Trucking or transportation terminal											P				
K10	Vehicle impound yard			C							P	P				
K11	Warehouse or distribution center										P	P				
	Other Uses															
L1	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that is permitted in the same zone	P	P	P	P	P	P	P	P	P	P	P	P	P	P	

Attachment: Attachment 2 - Land Use Table and Definitions (amended per MCA 2019-01) (MCA 2019-01)

Commercial, Office, and Industrial Use Table															
P = Use is Permitted by Right C = Use Requires Conditional Use Permit A = Use Requires Administrative Use Permit T = Use Requires Temporary Use Permit Blank = Use is Not Allowed															
Land Uses		Commercial Zones				Mixed Use Zones			Industrial and Office Zones				Other Zones		
		C-N	C-R	C-S	C-H	MX-N	MX-C	MX-D	O-R	O	I-L	I-H	AP	PF	CO
L2	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that requires an administrative use permit in the same zone	A	A	A	A	A	A	A	A	A	A	A	A	A	A
L3	Other uses not listed that are determined by the Community Development Director to be similar in nature to a listed use that requires a conditional use permit in the same zone	C	C	C	C	C	C	C	C	C	C	C	C	C	C

17.08.050 Addition of a use to land use tables.

Upon an application or on its own initiative and pursuant to Chapter 17.86, the City Council may add a use to the land use tables established in this chapter if the Council makes all of the following findings:

- A. That the addition of the use to the land use table will be in accordance with the purposes of this title and of the zone district or districts in which the use will be permitted;
- B. That the use has similar basic characteristics as the present uses allowed in the district;
- C. That the use will not generate a noticeably greater amount of odor, dirt, smoke, noise, vibration, illumination, glare, unsightliness or any other objectionable influence or hazard than

the amount normally created by any of the other uses permitted in the district or districts in which the use will be permitted.

D. That the establishment of the use in the zone district or districts in which it will be permitted will not be detrimental to the public health, safety or welfare;

Chapter 17.96

DEFINITION OF LAND USES

Sections:

17.96.010 Purpose.

17.96.020 Land use definitions.

17.96.010 Purpose.

The purpose of this chapter is to establish definitions for the identified land uses in this title.

17.96.020 Land use definitions.

The following land use definitions apply to this title. The item number in parenthesis at the end of the definition is not a part of the definition, but refers to the line item of that land use in Table 17.18.020 and Table 17.18.030.

“Accessory building or structure” means a structure which is subordinate to and the use of which is customarily incidental to, that of the main building, structure or use on the same site, including patio covers. If any accessory building is attached to the main building by a common wall or a connecting roof, such accessory building shall be deemed to be a part of the main building. (41) (A20)

“Accessory use” means a use incidental, related, appropriate and clearly subordinate to the main use of the site or building, and accessory use does not alter the principal use of the site. (41) (A20)

Adult day health care center. See Residential care facility. (H13)

“Adult entertainment establishment” means any adult bookstore, adult hotel or motel, adult motion picture arcade, adult motion picture theater, cabaret, sexual encounter establishment, adult model studio or any other business or establishment that offers its patrons services or entertainment characterized by an emphasis on matter depicting, describing or relating to "specified sexual activities" or "specified anatomical areas," but not including those uses or activities, the regulation of which is preempted by state law. (I1)

“Agricultural crop production” means the use of land for farming, horticulture, floriculture, viticulture, apiaries, tree and sod farms, animal and poultry husbandry, and accessory activities, including, but not limited to, storage, associated maintenance of equipment, harvesting of crops or feeding of animals and excluding dairying, stockyards, slaughtering or commercial food processing. Pursuant to Health and Safety Code Section 17021.6, any employee housing consisting of no more than thirty-six (36) beds in a group quarters or twelve (12) units or spaces designed for use by a single family or household shall be deemed an agricultural land use for zoning purposes. (D1)

“Agricultural products packing, packaging, preparing or processing” means a facility performing any processing or packaging of crops after harvest, whether or not value is added, to prepare them for market on-site or for further processing and packaging elsewhere, including but not limited to: alfalfa and hay cubing; corn shelling; drying of corn, rice, hay, fruits or vegetables; pre-cooling and packaging of fresh or farm-dried fruits and vegetables; grain cleaning and custom grinding; custom grist mills; custom milling of flour, feed and grain; sorting, grading and packing of fruits and vegetables; canning, freezing, or preserving fruits and vegetables; tree nut hulling and shelling; and alcohol fuel production. Any of the above activities performed in the field with mobile equipment not involving permanent buildings are included under “Agricultural crop production.” It includes related accessory uses such as offices, laboratories, retail sales of agricultural products produced on the premises or off-site by the operator, retail sales of agriculture-related promotional and/or educational items, and facility tours. Does not include “wineries,” “commercial marijuana activity,” “commercial cannabis activity,” “marijuana cultivation,” or sorting and packing activities conducted within a permitted roadside stand. (D2)

“Airport or heliport” means an area of land, water or a structural surface that is used for the landing and takeoff of airplanes and/or helicopters, and any appurtenant areas or buildings that are used for maintenance, servicing, or storing of aircraft, and for services provided to pilots or passengers. (K1)

“Ambulance service” means the provision by a licensed ambulance provider of ground transportation of a sick or injured person in a specially designed and equipped vehicle which includes a trained ambulance attendant who is licensed or certified as required by state law. (J1)

“Animal raising” means the care and breeding of domestic agricultural animals such as chickens and other fowl, horses, goats, or cows. (D3)

Art school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Artisan food and beverage production and sales” means small scale production and/or preparation of food and/or beverages made on site with minimal automated processes involved and may include direct sales to consumers and product tasting. This definition includes uses such as small batch food producers and bakeries, small batch candy shops, cheese makers, and herbal remedies. The definition does not include production of beer, wine, or other alcoholic beverages. (B1)

Assembly, place of. See Club, lodge, or private meeting hall (C3) or Religious institution or facility. (C10)

“Assisted living, skilled nursing, or hospice facility” means a residential complex providing skilled nursing care on an intermittent, extended, or continuous basis to residents, with staff personnel and programs to assist residents with many activities of daily living. Units may or may not have kitchens, and meals can also be provided in a central location. (1) (H1)

“Athletic complex or ball field” means a field, outdoor court, outdoor swimming pool, stadium or group of these used for sporting activities such as baseball, softball, football, basketball, swimming, or other sports, and is not operated as a commercial enterprise. (G1)

“Auction or sales house” means a fully enclosed establishment where items are offered for sale through competitive bidding. It does not include foreclosure, real estate or personal property sales conducted upon the site of the estate, foreclosed or for sale property or property belonging

to the personal property owner. It does not include “Swap meet or flea market” or “Auction or sales yard.” (I2)

“Auction or sales yard” means an outdoor or open air facility where items are offered for sale through competitive bidding. Items typically include motor vehicles, heavy equipment, items of an industrial nature, livestock, or items not normally found within retail stores. It does not include “Swap meet or flea market.” It may also have an indoor component similar to an Auction or sales house. (I3)

“Auditorium” means a large room or building used for public gatherings typically open to the general public to watch and/or listen to a performance, speech, or concert. It does not include “Theater, live or movie.” (C1)

“Automated teller machine (ATM)” means a computer terminal that takes the place of a human bank teller and allows the user to access basic bank services, such as making deposits and cash withdrawals, from remote locations. (A1)

“Automobile and pick-up sales, new and used” means an open area that can include buildings, other than a street, used for the display, sale, or rental of new and used automobiles and pick-ups along with incidental repairs and servicing of automobiles or pick-ups. (I4)

“Automobile and pick-up sales, used only” means an open area or building, other than a street, used for the display, sale or rental of used automobiles and pick-ups and where no repair work is done except minor incidental repairs and servicing of automobiles or pick-ups to be displayed, sold or rented on the premises. (I5)

Automobile service station. See Fuel sales, retail, Motor vehicle repair or service, minor, and Motor vehicle repair service, major. ~~(H6)~~ (J18) (J19)

Automobile wrecking yard. See Junk yard, wrecking yard, or salvage facility. (K5)

Ball field. See Athletic complex or ball field. (G1)

“Bank or credit union, main branch” means an institution providing retail banking services that is the main branch in the city. This classification includes only those institutions engaged in the on-site circulation of money, including credit unions, but excluding a payday lender or check-cashing establishment. For administration, headquarters, or other offices of banks and credit unions without retail banking services with on-site circulation of money see Office, professional or commercial. (J2)

“Bank or credit union, secondary branch” means an institution providing retail banking services that is a secondary or satellite branch in the city and either does not provide loan officers on site or only provides merchant bank services. This classification includes only those institutions engaged in the on-site circulation of money, including credit unions, but excluding a payday lender or check-cashing establishment. For administration, headquarters, or other offices of banks and credit unions without retail banking services with on-site circulation of money see Office, professional or commercial. (J3)

“Bar, nightclub, or lounge” means an establishment that provides alcoholic beverages for consumption on the site and may or may not provide food service, and that may provide live entertainment and/or dancing. This use typically requires an ABC Type 40, 42, 48, 60, or 61 license. (B2)

“Barbershop, hair salon, nail care, massage therapy, or day spa” means an establishment that provides personal care treatments or massage therapy of hair, skin, nails, and/or face where overnight accommodations are not provided. This use includes the application of permanent facial makeup, but does not include other forms of tattooing or body art application. (J4)

“Bed and breakfast inn” means a transient lodging establishment that is predominantly residential in character, is primarily engaged in providing overnight or otherwise temporary lodging for the general public, and where a breakfast meal is customarily included in the lodging rate. Alcoholic beverages served to overnight guests typically requires an ABC Type 67 license. (2) (H2)

“Boarding house or rooming house” means a structure where residents typically rent by the room, and where meals are typically provided. This definition does not include assisted living, skilled nursing, or hospice facility, bed and breakfast inn, or residential care facility. (3) (H3)

“Boat, recreational vehicle (RV), and truck sales” means an open area or building, other than a street, used for the display, sale, or rental of new or used boats, campers, camper trailers, recreational vehicles, trucks over one-ton class, and other vehicles or sporting equipment of similar size, and where no repair work is done except minor incidental repairs and servicing of vehicles and equipment to be displayed, sold or rented on the premises. (I6)

“Brewery, winery, or distillery” is an establishment that manufactures beer, wine, distilled spirits or similar alcoholic beverages, including processing, storage, aging, packaging, bottling, and shipping. Consumption can occur on or off the site in accordance with the establishment’s ABC license restrictions, and can include tasting facilities and/or a restaurant. This use typically requires an ABC Type 01, 02, 03, or 04 license. (D4)

“Brewpub” means a restaurant that also brews limited amounts of beer (less than 5,000 barrels) for consumption on the site. This use typically requires an ABC Type 75 license. (B3)

“Building materials and supply or home improvement store” means an establishment selling a mix of lumber, building materials, tools, residential appliances, nursery items, and home furnishings. (I7)

“Bus, transit, or train station” means a terminal facility where transit vehicles load or unload passengers, along with supporting services such as ticket sales and waiting areas. Bus, transit, or train station does not include a transit stop along a route in the public right-of-way where no additional services are provided. (K2)

Business school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Business support service” means an establishment providing primarily other businesses with a mix of services that can include word processing, desktop publishing, spreadsheet design, telephone answering, mail receiving and forwarding, packing and shipping, bookkeeping, and photocopying, and can include indoor storage rental, and/or small office space rental when provided with these services. (E1)

“Call center” means an office used primarily for receiving or transmitting a large volume of requests by telephone to administer product support or information inquiries from consumers or to conduct telemarketing, solicitation of charitable or political donations, debt collection, or market research. (E2)

“Car wash, automatic or full service” means a facility for washing vehicles using conveyORIZED and/or mechanized equipment where the washing of the vehicle is performed by equipment, the facility’s employees, or both. (J5)

“Car wash, self-service” means a facility for washing vehicles where the user of the vehicle uses handheld equipment, typically coin-operated, to wash the vehicle. (J6)

“Card room” means an establishment providing legal gambling combined with card games, and can include a restaurant, bar, or other ancillary entertainment. (C2)

“Caretaker residence or quarters” is a residence that is accessory to a primary use of the site, for housing a persons or persons who are tasked with caring for or securing the site on a part-time or full-time basis. Second dwelling unit includes caretaker residence or quarters in residential zones. (A2)

“Carnival or circus” means a temporary outdoor amusement center, bazaar or fair, either involving use of special purpose equipment or conducted by professional operators, or both, and where activities include such things as rides, exhibitions, food service, sales, or small-scale games. Carnival or circus does not include a non-profit event sponsored by a local school or religious institution. (C4)

“Carpet cleaning and dyeing” means an establishment that provides for the cleaning and dyeing of rugs, carpet, and upholstery. (J7)

“Cemetery” means land and facilities used or intended to be used for the burial or interment of the dead, and includes a columbarium, crematorium, mausoleum and/or mortuary when operated in conjunction with and within the boundary of the facility. (F1)

Charter School. See School, charter, trade, vocational, art, business, or professional. (C13)

Check cashing establishment. See Payday lender or checking cashing establishment. (J20)

Child care center. See Day care facility. (A4) (F4) (F5) (F6)

“Club, lodge, or private meeting hall” means a large room or building used for public gatherings where membership or invitation is typically required to attend. It can include a dance floor, lodge rooms, conference rooms, dining rooms, drinking establishments for members and their guests only, and exhibit rooms. Alcoholic beverage service to members and their guests typically requires an ABC Type 51, 52, or 57 license. (C3)

“Cold storage or ice house” means a facility for the storage food or other items in an artificially cooled place for the purpose of preservation, and/or for producing large amounts of ice. (K3)

“College or university, private or public” means a school or group of schools that provides post-secondary education usually resulting in a degree. (C5)

Clinic, medical. See Urgent care center or other walk-in clinic. (E9)

“Commercial recreation facility, indoor” means indoor recreational facilities that are operated as a business and open to the general public for an entry fee or pay per use. Examples include indoor uses such as, but are not limited to, a bowling alley, bounce house, skating rink, batting cage, miniature golf, swimming pool, climbing wall, arcade, and similar uses. Food and beverage service can be provided as an ancillary use. (G2)

“Commercial recreation facility, outdoor” means outdoor recreational facilities that are operated as a business and open to the general public for an entry fee or pay per use. Examples include outdoor uses such as, but are not limited to, a batting cage, miniature golf, water slide, go-cart racing, and similar uses. Food and beverage service can be provided as an ancillary use. (G3)

Communications equipment building. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Community center or facility” means an assembly building used typically for non-profit social, recreational, and cultural activities. (F2)

“Community garden” means an area of land managed and maintained by an individual or group to grow and harvest food and horticultural products for personal or group consumption. The garden may be divided into separate garden plots for cultivation by one or more individuals or may be farmed collectively by members of the group. (F3)

“Construction materials recycling” means a yard or facility that collects leftover construction materials that may be recycled or reused as an alternative to disposal in landfill site. Examples of construction materials include lumber, drywall, masonry, cabinets, metals and appliances, cardboard and paper, asphalt roofing, plastic and vinyl, doors and windows, tubs, sinks, and toilets. (J8)

“Convenience store, with or without fuel sales” means an establishment with extended operating hours and in a convenient location, stocking a limited range of household goods and groceries. Retail fuel sales may or may not also be provided. (I8)

“Convention or conference center” means facilities designed and used for conventions, conferences, seminars, trade shows, product displays, and other events in which groups gather to promote and share common interests. Convention centers typically have at least one auditorium and may also contain concert halls, lecture halls, meeting rooms, and conference rooms, as well as accessory uses such as facilities for food preparation and serving and administrative offices. Convention or conference center does not include conference rooms that may be an ancillary use in a hotel and motel. (C6)

“Copy, printing, or mailing service” means an establishment providing printing, photocopying, engraving, binding, packaging, mailing and related services to both businesses and individuals. (J9)

“Cottage Food Operation” means a home-based business involving the preparation and/or packaging of certain foods in private-home kitchens for sale primarily by the resident family. (A3)

“Crematorium or columbarium” is a structure or building substantially exposed above ground intended to be used for the cremation and/or interment of the cremated remains of a deceased person or animal. (J10)

“Day care facility” means a facility providing supervision, feeding and nonmedical care of persons, usually but not necessarily children, for a time period of less than twenty-four (24) hours. Day care facilities are further divided into the following categories: up to eight (8) persons, nine (9) to fourteen (14) persons, and over fourteen (14) persons. (A4) (F4) (F5) (F6)

Day spa. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Drive-thru pick-up window, not in conjunction with a restaurant” means the ancillary use of a window or other opening in the wall of building through which goods or services are provided directly to customers in motor vehicles. Examples of non-restaurant establishments with this ancillary use can include banks, pharmacies, and dry cleaners. (A5)

“Dry cleaning or laundromat” means an establishment providing laundry, dry cleaning, and other related services for individual customers on a pick-up and drop-off basis or where with coin-operated washing and drying machines are available for customer use. (J11)

Duplex. See Multi-family dwelling. (10) (H9) (H10) (H11)

Dwelling, multiple-family. See Multi-family dwelling. (10) (11) (12) (H9) (H10) (H11)

Dwelling, single-family. See Single-family dwelling. (16) (17) (H15) (H16)

“Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank” means the assembly of above-ground buildings or equipment on a separate lot that is part of a system for the distribution or transmission of electric power, natural gas, domestic water, or communications. Wireless communication facilities are not included in this definition. (F7)

“Electric vehicle recharging facility” means one or more publicly available parking spaces served by electric vehicle service equipment, and is typically an ancillary use in a parking garage or parking lot. (A6)

Elevated pressure tank. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Emergency Shelter” means a facility providing housing with minimal supportive services for homeless persons that is limited to occupancy of six months or less where housing is not denied because of an inability to pay. (4) (H4)

“Employee housing” means a residential structure providing accommodations for six (6) or fewer farmworkers pursuant to Health and Safety Code Section 17021.5. (5) (H5)

“Equipment rental yard” means an establishment offering a wide variety of large equipment or tools for rent, much of which is stored outdoors when not being used. (J12)

“Exterminator or pest control service” means an establishment specializing in the elimination of vermin, insects, or other similar pests from a building or grounds, especially by the controlled application of toxic chemicals. (J13)

“Fairgrounds” means an area with indoor and outdoor facilities where fairs, circuses, or exhibitions are held. (F8)

“Farmers market” means a facility or area where several farmers or growers gather on a periodic basis to provide fresh fruits, vegetables, or other locally-grown agricultural products directly to consumers. (I10)

“Feed and seed store” means an establishment that provides feed, seed, and animal and agricultural supplies primarily in bulk quantities. (I11)

“Food catering” means an establishment that prepares and delivers food and beverages for off-site consumption, typically at a special event, without provision for on-site pickup or consumption. (J14)

“Food locker” means an establishment that rents lockers, compartments, or space for the storage of frozen food. A food locker may also include the preparation or dressing of animal carcasses for consumption, but does not include the slaughtering of animals. (K4)

“Food market” means an establishment that provides a wide variety of fresh produce and meat, canned and packaged food items, small household goods, and similar items that are typically consumed and used off premises. It can also contain a section where prepared foods are sold and consumed on site. (I12)

“Food produce stand” means an area or building set aside for the sale of agricultural produce that is grown primarily on the site. (I13)

“Fortune telling” means an establishment where people’s fortunes are predicted through the use of astrology, card reading, numerology, etc. (J15)

“Fuel distributing” means a facility that is a base of operations for the bulk distribution of gasoline, propane, butane, or other another site. (J16)

“Fuel sales, fleet or cardlock” means an establishment that is typically unattended and provides gasoline, propane, diesel fuel, and/or other liquid or gaseous fuels mainly for commercial fleet vehicles. (I14)

“Fuel sales, retail” means an establishment that provides gasoline, propane, diesel fuel, and/or other liquid or gaseous fuels directly to consumers. (I15)

“Funeral home or mortuary” means an establishment where deceased are prepared for burial or cremation, and funeral services may be conducted. It can include an area where funeral vehicles are stored and caskets and other funeral supplies are sold. (C7)

“Furniture store” means an establishment that provides large and small furniture for living spaces such as homes and offices. Items sold normally include beds, tables, chairs, sofas, desks, and shelves. Home appliances, outdoor/patio furniture, wall cabinets, garage storage units, and home furnishing accessories are items sold that are excluded from the definition of furniture store. (I16, I17, I18)

“Games of skill or amusement” means machines, devices or apparatus, the operation or use of which is made possible by the deposit or placement of any currency, plate, disc, slug or key into any slot or crevice, for the purpose or use as a game or amusement. This use does not include games, machines, or devices used for a purpose that is prohibited by law. (A8) (A9)

“Garden shop” means an establishment that provides live plants and related products mainly to residential consumers, with a portion of the establishment typically located outdoors. (H9 I17)

Gas regulator station. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

Gas station. See Fuel sales, retail. (I15)

“Golf course or country club” means one or more golf courses, with accessory facilities and uses that can include clubhouses with bar and restaurant, locker and shower facilities; driving ranges; "pro shops" for onsite sales of golfing equipment; and golf cart storage and sales facilities. (G4)

“Government office; local, state, or federal” means a facility owned or operated by a local, state, or federal government that provides services to the public such as employment assistance, public assistance, motor vehicle registration and licensing services and similar activities commonly accustomed to having sizeable assemblages of people waiting for service, whether pedestrian or vehicular. This use does not include a government-owned facility that is more specifically defined in this chapter, such as fairgrounds, cemetery, post office, or public safety facility. (F9)

“Guest house” means living quarters without a kitchen, located on the same premises with a main residence. (34)

Hair salon. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Hazardous waste facility” means all contiguous land and structures, other appurtenances and improvements on the land used for the treatment, transfer, storage, resource recovery, disposal or recycling of hazardous waste, and may consist of one or more treatment, transfer, storage, resource recovery, disposal or recycling hazardous waste management units, or combinations of these units. (See Health and Safety Code Section 25117.1.) (D5)

“Health or fitness facility, large” means a fitness center, gymnasium, health club or athletic club that typically charges a membership fee and includes any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G5)

“Health or Fitness Facility, small” means a fitness center, health club or athletic club that typically charges a membership fee and does not include any of the following: indoor sauna, spa or hot tub facilities; a swimming pool, or a tennis, basketball or handball court. (G6)

Heliport. See Airport or heliport. (K1)

“Home occupation” means a commercial business activity conducted as an accessory use within a residence. (A10)

“Hospital, general or psychiatric” means a facility that provides medical, psychiatric, or surgical service for sick or injured persons, primarily on an in-patient basis, and including ancillary facilities for out-patient and emergency treatment, diagnostic services, training, research, administration and services to patients, employees, or visitors. (E5)

“Hotel or motel” means a building or group of buildings in one complex consisting of multiple guest rooms intended or designed to be occupied on a temporary basis, and typically providing ancillary services such as a restaurant, lounge, pool or exercise room, meeting rooms, and/or other personal services. Alcoholic beverages served to overnight guests outside of a restaurant or bar/lounge typically requires an ABC Type 70 license. (6) (H6)

“Industrial or manufacturing facility, heavy” means a facility that manufactures products from extracted or raw materials or recycled or secondary materials, or the bulk storage and handling of such products and materials. This use includes operations such as biomass energy conversion; production apparel manufacturing; photographic processing plants; leather and allied product manufacturing; wood product manufacturing; paper manufacturing; chemical manufacturing; plastics and rubber products manufacturing; nonmetallic mineral product manufacturing; primary

metal manufacturing; fabricated metal product manufacturing; and automotive and heavy equipment manufacturing. This use does not include Agricultural products processing. (D6)

“Industrial or manufacturing facility, light” means a facility that manufactures products from previously prepared materials completely within an enclosed building, and that produces minimal impacts on nearby properties. This use includes the manufacturing of finished parts or products primarily from previously prepared materials; commercial laundries and dry cleaning plants; monument works; printing, engraving, and publishing; machine and electrical shops; computer and electronic product manufacturing; furniture and related product manufacturing; and industrial services. The use also includes the preparation and/or packaging of food for off-site consumption. (D7)

“Junkyard, wrecking yard, or salvage facility” means a facility that accepts, collects, and stores junk, scrap, or salvable material, including junk metals or other scrap materials, and/or that stores, dismantles, wrecks, or allows parts removal of more than three (3) non-operating automobiles, other vehicles, or machinery for a period of more than thirty (30) days. (K5)

“Keeping of household pets” means the keeping, raising, and caring for domesticated animals that are not considered domestic agricultural animals by the definition of Animal raising, and typically including dogs, cats, birds, fish or other similar sized animals. Also, see Animal raising. (A11)

“Kennel or animal boarding” means any facility where four or more dogs, cats, or other small animals are kept overnight for profit, breeding, care, or exhibiting. This use does not include a pet store. (J17)

“Laboratory, general, medical, or dental” means a facility that conducts scientific or medical experiments, research, or teaching, typically within a completely enclosed building. (E4)

“Landscape nursery” means a facility that grows, maintains, and provides trees, plants, and other nursery products for transplant in another location typically to both retailer and wholesale customers. (I20 118)

“Library, museum, or cultural facility” means a facility operated entirely on a public or nonprofit basis for the purpose of providing education, information, training, and/or entertainment of a civic or cultural nature. (C8)

“Linen, diaper or uniform supply service” means an establishment providing high volume laundry and garment services, including power laundries (family and commercial), garment pressing and dry cleaning, linen supply, diaper service, and industrial laundries. This use does not include dry cleaning or laundromat. (J18)

“Liquor store” means an establishment that provides for the sale of alcoholic beverages such as beer, wine, and/or distilled spirits for consumption off the site, along with other retail items. This use typically requires an ABC Type 20 or 21 license. Limited consumption on the site can occur only when the appropriate ABC license is obtained, typically an ABC Type 86 license. (I21 I19)

“Live/Work facility” means a building that combines a complete dwelling unit with a commercial or office work space, with both occupancies used by the same person or family. (H7)

Lodge. See Club, lodge, or private meeting hall (C3)

Lounge. See Bar, nightclub, or lounge. (B2)

Lumberyard. See Building materials and supply or home improvement store. (I7)

“Manufactured home” means a structure that was constructed on or after June 15, 1976, is transportable in one or more sections, is eight (8) body feet or more in width, or forty (40) body feet or more in length, in the traveling mode, or, when erected on site, is three hundred twenty (320) or more square feet, and is designed to be used as a single-family dwelling when connected to the required utilities. (7)

“Manufactured home sales yard” means an establishment that stores and provides manufactured homes, typically in an open setting with a sales office. (~~I22~~ I20)

Massage therapy. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“Meat packing or slaughterhouse” means a facility used for the killing or dressing of animals, including cattle, sheep, swine, goats, horses, or poultry, and the storage, freezing, curing, or packaging of meat or meat products. (D8)

“Marijuana cultivation” means any activity involving the planting, growing, harvesting, drying, curing, grading, or trimming of marijuana. (A13)

“Marijuana dispensary or sales” means a facility that provides marijuana or marijuana products to a customer or patient. (~~I23~~ I21)

“Marijuana manufacture” means a facility that compounds, blends, extracts, infuses, or otherwise makes or prepares a marijuana product. (D8)

“Meat packing or slaughterhouse” means a facility that slaughters animals and/or packages animal meat for food. (D9)

“Microbrewery” means an establishment that produces small batches of beer for sale on or off of the site, and may or may not include food service. Typically, a microbrewery produces fewer than fifteen thousand (15,000) barrels of beer or ale per year. This use typically requires an ABC Type 23 license. (B4)

“Mining, quarry, or sand and gravel excavation” means an area of land where rock, ore, stone and similar materials are excavated and processed for sale for use off-site. (D10)

“Mini-warehouse or self-storage facility” means an establishment providing rental space, such as rooms, lockers, or containers for the storage of goods and materials, typically on a monthly basis. This use does not include Food locker or Warehouse or distribution center. (56) (K6)

“Mobilehome” means a structure that was constructed prior to June 15, 1976, is transportable in one or more sections, is eight (8) body feet or more in width, or forty (40) body feet or more in length, in the traveling mode, or, when erected on site, is three hundred (320) or more square feet, and is designed to be used as a single-family dwelling when connected to the required utilities. (8)

“Mobilehome park” means an area of land where two or more mobilehome sites are rented or leased, or offered for rent or lease, to accommodate mobilehomes or manufactured homes used as a residence. (9) (H8)

“Mobile vending or food truck” means a motorized vehicle that periodically parks to provide food or foodstuffs to customers. (A14)

Motel. See Hotel or motel. (H6)

“Motor vehicle repair or service, major” means an establishment that provides major repair or servicing of motor vehicles, such as body, chassis, engine, transmission, or exhaust repair or modification. (J19)

“Motor vehicle repair or service, minor” means an establishment that provides minor repair or servicing of motor vehicles, such as the replacement of tires or batteries, smog inspection, oil and filter change, wheel alignment, and fluid flushing, refill, or replacement. (J20)

“Multi-family dwelling” means a building or group of buildings in one complex with multiple separate housing units. A multi-family dwelling can have two units (a duplex,) three units (a triplex,) four units (a fourplex,) or five or more units. Multi-family dwelling includes a mixed use building that also provides separate space for commercial or office use, but does not include an attached single-family dwelling. (10) (11) (12) (H9) (H10) (H11)

Nail care. See Barbershop, hair salon, nail care, massage therapy, or day spa. (J4)

“News, magazine, or flower stand, outdoor” means an establishment that provides newspapers, magazines, flowers, or other similar goods, typically to pedestrians passing by, in a permanent structure open to the outdoors. This use does not include sales from temporary booths or structures. (~~I24~~ **I22**)

Nightclub. See Bar, nightclub, or lounge. (B2)

“Office; medical, dental, or optometry” means an establishment that provides services, typically by appointment, dealing with human health including dental, chiropractic, medical, optometry, physical therapy, psychology, psychiatry, family counseling, or therapy. This use does not include Barbershop, hair salon, nail care, massage therapy, or day spa. (E6)

“Offices, professional or commercial” means an establishment that provides administrative, clerical, technical, professional or similar business services and typically where products or goods are not provided. Examples include escrow and title, insurance, mortgage, real estate, accounting, architecture, graphic design, finance, consulting, engineering, legal, and similar services. (E7)

“Optical retailer” means an establishment that provides prescription eyeglasses and contact lenses, and where optometry services are not provided on the site. Prescription eyeglasses and contact lenses may be made on the premises. (~~I25~~ **I23**)

“Outdoor advertising structure” means a structure of any kind or character, erected or maintained for outdoor advertising purposes, upon which a sign may be placed that advertises a use, product, or service that is not provided off-site. (A15)

“Outdoor storage” means the storage of goods or materials outside of any building or structure, but not including storage of a temporary or emergency nature. (A16)

“Park or playground” means an open area typically landscaped and containing play equipment that provides rest and recreation, usually owned by a public agency or homeowner’s association. (57) (G7)

“Parking facility, off-site” means an area, lot, or structure with one or more levels, other than a street or other public right-of-way, that provides for the parking of motor vehicles as a primary

use on the site. This use does not include parking areas or lots that are ancillary and specifically intended to provide parking for the primary use on the site. (K7)

“Pawn shop” means an establishment that provides secured loans to customers, with items of personal property used as collateral. (~~I26~~ I24)

“Payday lender or check cashing establishment” is an establishment that cashes checks, warrants, or money orders for a fee, and/or provides short term loans, usually at a high interest rate, that must be paid in full when the borrower receives their next pay check. This use does not include Bank or credit union. (J21)

“Pet grooming” is a personal service establishment that, for a fee, trims, cleans or curries domestic pets such as dogs and cats and which may sell pet supplies. This use does not include Kennel or animal boarding. (J22)

“Pet store” means an establishment where dogs, cats, or other small animals are kept and offered for sale. (~~I27~~ I25)

“Pharmacy” means an establishment that provides prescription drugs under the supervision of a pharmacist, and can also provide other retail products. (E8)

“Photography studio” means an establishment where customers can have their portraits taken professionally. (J23)

“Pool hall or billiard parlor” means an establishment where pool and/or billiard games are played for a fee. (C9)

“Post office” means a facility that accepts, processes, and sorts mail, operated by the United States Postal Service. (F10)

Private meeting hall. See Club, lodge, or private meeting hall (C3)

Professional school. See School, charter, trade, vocational, art, business, or professional. (C12)

Produce stand. See Food produce stand. (I13)

“Public corporation yard, utility yard, or vehicle and heavy equipment maintenance and storage yard” means a facility that provides for maintenance, servicing, or storage of fleet vehicles, equipment, or supplies, or for the dispatching of service vehicles; or distribution of supplies or construction materials required in connection with a business activity, public utility service, transportation service, government service, or similar activity. (F11)

“Public safety facility or station” means a facility that is a base for providing public safety and emergency services, including police, fire protection and emergency services. This use does not include Ambulance service. (F12)

Public service pumping station. See Electric distribution and transmission substation, gas regulator station, communications equipment building, public service pumping station, or elevated pressure tank. (F7)

“Recreational vehicle park” means a lot or area of land where two or more spaces are rented to users of recreational vehicles for overnight parking and use, and that typically provide support services, such as utility hookups and sewer dump facilities. (I3) (H12)

“Recycling, large collection facility” means a facility located in an area of over five hundred (500) square feet that accepts recyclable materials from the public by donation, redemption, or purchase for temporary storage and transport to a processing and sorting facility. (J25)

“Recycling, processing or sorting facility” means a facility used for the collection, processing and preparation of recyclable material for efficient shipment, or to an end-user's specifications, by such means as bailing, briquetting, compacting, flattening, grinding, crushing, mechanical sorting, shredding, cleaning, and remanufacturing. (J26)

“Recycling, small collection facility” means facility located in an area of not more than five hundred (500) square feet that provides for the redemption of California CRV redeemable beverage containers by means of a kiosk, container, mobile unit, reverse vending machine or other collection method. (J24)

“Religious institution or facility” means a facility used primarily to gather for religious worship and related religious activities. (58) (C10)

“Repair shop, large appliance or equipment” means an establishment that restores or repairs major appliances or equipment that generally cannot be easily moved by a single person and is typically placed on the floor. This use typically provides all of its service on-site, and includes repair of large motorized equipment that are not vehicles. (J27)

“Repair shop, small appliance or equipment” means an establishment that restores or repairs small appliances or equipment that generally can be moved by one person and is typically repaired on a table or work bench. This use typically provides all of its service on-site, and includes services such as gunsmithing, lawnmower repair, and home computer repair. (J28)

“Research and development facility” means a facility that is primarily used for the research, design, development, and testing of biological, chemical, electrical, magnetic, mechanical, and/or optical components in advance of product manufacturing. This use does not involve the fabrication, mass manufacture, or processing of products. (D11)

“Residential care facility” means a single-family dwelling, group care facility, or similar facility licensed by the State of California for twenty-four (24) hour non-medical care of persons in need of personal services, supervision or assistance essential for sustaining the activities of daily living or for the protection of the individual. (14) (15) (H13)

“Residential dwelling located in the same building with office or commercial use” means a building that contains a mix of both residential dwelling units and space used for commercial or office uses. (H14)

“Restaurant, full service” means an establishment providing preparation and sale of a variety of food and beverages with full table service by wait staff. Takeout or delivery service and/or live entertainment may also be provided. If alcoholic beverages are served, this use typically requires an ABC Type 41 or 47 license. (B5)

“Restaurant, limited service with drive-thru pickup window” means an establishment providing preparation and sale of a variety of food and beverages for consumption on or off the site by ordering and paying at a counter or drive-thru window. Delivery service and/or live entertainment may also be provided. (B6)

“Restaurant, limited service without drive-thru pickup window” means an establishment providing preparation and sale of a variety of food and beverages by ordering and paying at a

counter. Takeout or delivery service and/or live entertainment may also be provided. Drive-thru pickup windows are not provided. If alcoholic beverages are served, this use typically requires an ABC Type 41 or 47 license. (B7)

“Retail sales store” means an establishment providing retail products. This use includes all retail sales establishments that are not more specifically defined in this chapter. (~~I28~~ **I26**)

“Retail sales solely via internet, direct mail, or telephone” means an establishment providing retail products for sale and delivery only via internet, direct mail, or telephone communication, with a floor space for storage of products of less than five thousand (5,000) square feet. This use does not include a Call center or a Warehouse or distribution center. If alcoholic beverages are sold, this use typically requires an ABC Type 85 license. (~~I29~~ **I27**)

Rooming house. See Boarding house or rooming house. (3) (H3)

“School, private (kindergarten to 12th grade)” means a facility owned and/or operated by a private entity that educates minors in courses of study required by the California Education Code. This use includes a kindergarten, elementary school, middle school, high school, special institution of education, or combination of these, and includes a technical, vocational, or art school only when the students are primarily minors. This use does not include home schooling at a residence. (59) (C11)

“School, public (kindergarten to 12th grade)” means a facility owned and/or operated by a publicly funded school district that educates minors in courses of study required by the California Education Code. This use includes a kindergarten, elementary school, middle school, high school, special institution of education, or combination of these, and includes a technical, vocational, or art school only when the students are primarily minors. This use does not include a charter school. (60) (C12)

“School; charter, trade, vocational, business, or professional” means a facility that is operated either with public funds under a charter contract or with private funds, and that offers specific educational instruction to children and/or adults. This use includes charter schools, secretarial schools, beauty and cosmetology schools, modeling schools, language schools, computer or electronics training schools, arts schools, and automotive repair schools, and similar specialized schools. (C13)

Scrap metal processing. See Junk yard, wrecking yard, or salvage yard. (K5)

“Secondhand or thrift store” means an establishment that accepts donations of secondhand items and clothing, and is typically operated for charitable purposes. (~~I30~~ **I28**)

Service station. See Fuel sales, retail, and Motor vehicle repair or service, minor. (I15) (J19)

“Shooting range, indoor” means an establishment that is used for archery or firearms practice in a fully-enclosed facility. (J29)

“Shooting range, outdoor” means an establishment that is used for archery or firearms practice, either wholly or partially outdoors. (J30)

“Single-family dwelling, attached” means a building with two residential dwelling units located on portions of two lots with a building firewall along the lot line, such that the dwelling units may be sold separately. (16) (H15)

Single-family dwelling, detached” means a building with one residential dwelling unit located on one lot. (17) (H16)

“Single-room occupancy (SRO)” means a residential facility of two or more separate individual rooms with typically less than five hundred (500) square feet of floor space, with or without separate kitchen or bathroom facilities for each room, rented on a weekly or monthly basis. Single-room occupancy does not include Hotel or motel. (18) (H17)

“Social service office, assistance center, or guidance center” means a facility that provides counseling, guidance, recuperative, or similar services for persons requiring rehabilitation assistance as a result of economic hardship, mental disability, alcoholism, detention, drug addiction, or similar conditions. This use does not include facilities that provide overnight stay. (F13)

“Specialty construction or trade service” means an establishment that provides construction, installation or maintenance services activities that are typically specialized trade activities, and where some of the service may be provided off-site. This use includes establishments that provide services such as plumbing, electrical work, painting, irrigation, heating/air conditioning, and masonry. This use does not include Repair shop or Motor vehicle repair or service. (J31)

“Storm drainage basin, with or without a park” means a facility that collects storm water from off-site locations into a sunken basin. The facility may be inaccessible to the public, or may be designed to provide partial public access for recreational use. (61) (F14)

“Studio for martial arts, music, dance, yoga, exercise, gymnastics or similar” means a facility that provides group or individualized instruction in a specific activity typically related to the arts. This use does not include Health or fitness facility. (C14)

“Supportive housing” is defined in Section 50675.14 of the Health & Safety Code and has no limit on the length of stay, is linked to onsite or offsite services, and is occupied by a target population as defined in Health & Safety Code Section 53260 (i.e., low income persons with mental disabilities, AIDS, substance abuse or chronic health conditions or persons whose disabilities originated before the person turned 18). Services typically include assistance designed to meet the needs of the target population in retaining housing, living and working in the community, and/or improving health and may include case management, mental health treatment, and life skills. (19) (H18)

“Swap meet or flea market” means a facility that provides typically compartmentalized space, either indoors or outdoors, to vendors who sells or barter merchandise. This use does not include ‘Farmers market,’ ‘Auction or sales house,’ or ‘Auction or sales yard.’ (~~I34~~ I29)

“Tailoring or clothing alterations” means an establishment that provides custom making or altering of clothing when not an ancillary use in a clothing store. (J32)

“Tattooing or body art” means an establishment that provides tattooing, body piercing, and other forms of body art allowed by the California Health and Safety Code, except that body art involving ear piercing and permanent cosmetic application are not included and are considered ancillary uses in other establishments. This use does not include any use that is more specifically defined in Section 17.62.020. (J33)

“Temporary materials or equipment storage yard” means a facility that is used to store, park, house, or prepare equipment, dirt, materials, or temporary offices or shops to support a construction or demolition activity occurring on another site. (A17)

“Temporary sales office” means a facility that provides temporary office space to support the sale of residences or other structures, and can include related parking. (A18)

“Theater, live or movie” means a facility with an auditorium for viewing movies, plays, acts, or other performances. (C15)

“Tobacco or smoke shop” means an establishment that provides tobacco products or tobacco related paraphernalia in an area greater than forty (40) percent of its total available retail floor space. (~~I32~~ I30)

Trade school. See School, charter, trade, vocational, art, business, or professional. (C13)

Transit station. See Bus, transit, or train station. (K2)

Travel center. See Truck stop or Travel center. (K7)

“Transitional housing” means buildings configured as rental housing developments, but operated under program requirements that call for the termination of assistance and recirculation of the assisted unit to another eligible program recipient at some predetermined future point in time, which shall be no less than six months. (20) (H19)

“Truck stop or travel center” means an establishment or group of establishments designed to operate together that provide fuel, overnight parking, lodging, food, convenience goods, or other services primarily to truckers and travelers. (K8)

“Trucking or transportation terminal” means a facility designed specifically for large trucks or other vehicles to load, unload, or transfer freight, cargo containers, or other items being shipped, along with associated fueling areas, maintenance facilities, and offices. (K9)

“Urgent care center or other walk-in clinic” means a facility that provides medical treatment of injuries or illnesses that do not require treatment typically provided in an emergency room, typically without an appointment. This use includes urgent care centers, free clinics, hospital-based health clinics, and community health clinics, but does not include ancillary retail clinics located within a retail store, food market, or pharmacy. (E9)

“Vehicle impound yard” means a facility that provides temporary storage of vehicles that have been removed or impounded from public or private property at the direction of a peace officer or because of local ordinance or judicial order. (K10)

“Vending machines” means a device that dispenses a product or service upon activation by the receiver of that product or service. Products can include items such as ice; food and beverages, movies and video games, lottery tickets, newspapers, or similar items, but does not include fueling pumps. (A19)

“Veterinary clinic or office” means a facility where animals are examined, diagnosed, or treated, but typically not kept overnight. (J34)

“Veterinary hospital” means a facility where animals are kept for observation, diagnosis, treatment, or medical care, and can include overnight surveillance. (J35)

Vocational school. See School, charter, trade, vocational, art, business, or professional. (C13)

“Warehouse or distribution center” means a facility for storage of goods or materials that will eventually be redistributed to retailers, wholesalers, or directly to consumers. This use does not include Mini-warehouse or self-storage facility. (K11)

Winery. See Brewery or winery. (D4)

“Wireless Communication Facility” means an unstaffed facility that transmits and receives wireless telecommunications, and typically consists of an antenna array, connection cables, and equipment room, and an antenna support structure tower, or pole. (F15)

Chapter 17.98

DEFINITION OF TERMS

Sections:

17.98.010 **Applicability**

17.98.020 **Definition of terms.**

17.98.010 Applicability

The terms, words, and phrases defined in this chapter shall apply to this title.

17.98.020 Definition of terms.

“Abutting” means two (2) or more parcels sharing a common boundary at least at one point.

“Abandoned” means failure to develop, maintain or use a building, structure or improvement or failure to conduct a use upon real property for a stated period of time.

“Access” means safe, adequate and usable ingress or egress to real property, structures or improvements.

“Action” means the decision made by the review authority on a land use application, including appropriate findings, environmental determination and conditions of approval, where applicable.

“Addition” means any construction which increases the size of a building or facility in terms of site coverage, height, length, width, or gross floor area.

“Alley” is a public thoroughfare for the use of pedestrians and/or vehicles, producing only a secondary means of access to the abutting property.

“Alteration” means any construction or physical change in the internal arrangement of rooms or the supporting members of a building or structure or change in the appearance of any building or structure.

“Antenna” means a device for transmitting or receiving radio, television or any other transmitted signal.

“Applicant” means owner(s) of property, or their agent(s) who are seeking privileges provided by this title.

“Attached” means any structure that has a wall or roof in common with another structure.

“Basement” means a portion of building partly or wholly underground and having more than one-half (1/2) of its height below the average level of the adjoining ground.

“Berm” means a mound or embankment of earth.

“Block” means a parcel of land surrounded by public streets, highways, freeways, railroad rights-of-way, flood control channels, creeks, washes, rivers or unsubdivided acreage or any combination thereof.

“Building” means a permanently located structure, having a roof, for the housing or enclosure of persons, possessions, or property of any kind. Mobile homes, travel trailers and other vehicles, even though permanently immobilized, shall not be deemed to be buildings.

“Building area” means the net portion of the lot remaining after deducting all required setbacks from the gross area of the lot.

“Building coverage” means the percent of lot area which may be covered by roof covered buildings, structures or improvements located on a lot.

“Building height” means the vertical distance between the average finished ground surface adjacent to the structure and to the highest point of the structure, excluding architectural features and appurtenances such as, but not limited to, chimneys, vents, antennas, elevators, and similar mechanical equipment.

“Building, main” means a building in which the principal use of the real property is conducted.

“Building setback area, front” means an area extending across the full width of the lot between the front lot line or the existing or future street right-of-way and a structural setback line parallel thereto. On corner lots, the shortest street frontage shall be the front building setback area.

“Building setback area, interior side” means an area extending from the required front building setback area or, where there is no required front building setback area, from the front lot line to the required rear building setback area or, where there is no required rear building setback area, to the rear lot line and from the interior side lot line to a setback line parallel thereto.

“Building setback area, rear” means an area extending across the full width of the lot between the rear lot line and a setback line parallel thereto.

“Building setback area, side” means a building setback area between the side lot line and a line parallel thereto and extending from the front building setback area to the rear building setback area.

“Building setback area, street side” means an area extending from the required front building setback area or, where there is no required front building setback area, from the front lot line to the rear lot line, and from the side street lot line, or the existing or future side street right-of-way (whichever is greater) to a structural setback line parallel thereto.

“Building site” means the ground area of a building together with all open spaces required by this title.

“Carport” means a permanent roofed structure not completely enclosed to be used for vehicle parking.

“City” means the City of Hanford.

“Commercial vehicle” means a vehicle customarily used a part of a business for the transportation of goods or people.

“Commission” means the Planning Commission of the City of Hanford.

“Conditional use” means a use that may locate within a zone only upon taking measures to address issues that may make the use detrimental to the public health, safety and welfare and will not impair the integrity and character of the zoned district.

“Conditional use permit (CUP)” means a discretionary entitlement which may be granted under the provisions of this title and which when granted authorizes a specific use to be made of a specific property, subject to compliance with all terms and conditions imposed on the entitlement.

“Construction commencement” means the start of construction of a substantial portion on-site and off-site structural improvements after a building permit has been issued.

“Council” means the City Council of the City of Hanford.

“County” means the County of Kings.

“Court” means an open, unoccupied space, other than a yard, unobstructed from ground to sky on the same lot with a building or buildings and which is bounded on two or more sides by the walls of a building.

“Days” means consecutive calendar days unless otherwise stated.

“Decibel (dB / dBA)” is a unit for describing the amplitude of sound, as it is heard by the human ear.

“Density” means the number of dwelling units per gross acre, unless otherwise stated, for residential uses.

“Density Bonus” means an increase in the allowable number of residences granted by the city or county in return for the project’s providing low- or moderate-income housing. A housing development that provides 20 percent of its units for lower-income households, ten percent of its units for very-low income households, or 50 percent of its units for seniors is entitled to a density bonus and other concessions (See California Government Code section 65915).

“Design” means the planning and engineering of the following: street alignments, grades and widths; drainage and sanitary facilities and utilities, including alignment and grades thereof; location and size of all required easements and rights-of-way; fire roads and fire breaks; lot size and configuration; traffic access; grading; land to be dedicated for park or recreational purposes; building, structures and improvements and other such specific physical requirements.

“Detached” means any building or structure that does not have a wall or roof in common with any other building or structure.

“Development” means any change or alteration of real property or its boundary lines, and including, without limitation, the placement or erection of any solid material, structure or improvement thereon; discharge or disposal of any dredged material or any gaseous liquid, solid or thermal waste; grading, removing, dredging, mining or extraction of any soil or materials; change in the density or intensity of use of land, including, but not limited to, subdivision pursuant to the Subdivision Map Act (commencing with Section 66410 of the Government Code), and any other division of land, including lot splits, except where the land division is brought about in connection with the purchase of such land by a public agency for public recreational use; change in the intensity of use of water, or of access thereto; construction, reconstruction, demolition or alteration of the size of any structure including any facility of any

private, public or municipal utility; and the removal of any major vegetation. As used in this title, “structure” includes but is not limited to any building, road, pipe, flume, conduit, siphon, aqueduct, telephone line, and electrical power transmission and distribution line. A “project,” as defined in Government Code Section 65931, is included with this definition.

“Development agreement” means a binding contract between a developer and a city or county establishing the conditions under which a particular development may occur. The local government “freezes” the regulations applicable to the site for an agreed upon period of time. (see California Government Code section 65864)

“Development permit” means a discretionary entitlement which may be granted under the provisions of this title and which when granted authorizes a specific use to be made of specific property, subject to compliance with all terms and conditions imposed on the entitlement.

“Display area” means the area of a building in a retail sales store used to display goods that are for sale.

“Driveway” means a permanently surfaced area providing direct access for vehicles between a street and a permitted off-street parking or loading area.

“Dwelling” or “Dwelling Unit” means a room or group of rooms (including sleeping, eating, cooking, and sanitation facilities, but not more than one kitchen), which constitutes an independent housekeeping unit, occupied or intended for occupancy by one household on a long-term basis.

“Easement” means a grant of property rights by the property owner to the public, or any specific person.

“Electric vehicle” means a vehicle that uses a plug-in battery to provide all or part of the motive power of the vehicle, including battery electric, plug-in hybrid electric, or plug-in fuel cell vehicle.

“Electric vehicle service equipment” means an electric component assembly or cluster of component assemblies designed specifically to charge batteries within electric vehicles by permitting the transfer of electric energy to a battery or other storage device in an electric vehicle.

“Establishment” means land, buildings, rooms, space, and/or equipment necessary for conducting business.

“Façade” means the exterior wall of a building exposed to public view or that wall viewed by persons not within the building.

“Family” is an individual or a group of persons living together who constitute a bona fide single-family housekeeping unit in a dwelling unit, not including a fraternity, sorority, club, or other group of persons occupying a hotel, lodging house or institution of any kind.

“Facility” means land, buildings, rooms, space, and/or equipment necessary for doing something.

“FAR (Floor Area Ratio)” is a measure of development intensity. FAR is the ratio of the floor area of a building to the area of its site. For instance, both a two-story building that covers an entire lot and a four-story building that covers 1/2 of a lot have a FAR of 2.

“Fence” means a barrier surrounding or located upon a parcel of real property or a portion thereof and intended to prevent escape or intrusion therefrom or to identify a boundary identity, including without limitation, screened, solid (ninety percent (90%) or more closed to air, light and vision), open (fifty percent (50%) or more), or temporary and which may be constructed from wood, metal or masonry material or any combination thereof.

“Floor area” means the gross area included within the surrounding exterior finish wall surface of a building or portion thereof, exclusive of courtyards.

“Furniture” means the things placed in a room which equips it for living. This normally includes beds, tables, chairs, sofas, desks, and shelves. Home appliances, outdoor/patio furniture, wall cabinets, garage storage units and home furnishing accessories are excluded from the definition of furniture.

“Garage” means an enclosed building, or a portion of an enclosed building used for the parking of vehicles.

“General Plan” means a document adopted by the City Council containing statement of policies, including text and diagrams, setting forth objectives, principles, standards, and plan proposals, for the future physical development of the City of Hanford.

“Glare” means the effect produced by brightness sufficient to cause annoyance, discomfort, or loss in visual performance and visibility.

“Grade” means the degree of rise or descent of a sloping surface.

“Grade, finished” means the final elevation of the ground surface after development.

“Grade, natural” means the elevation of the ground surface in its natural state before man-made alterations.

“Grading” means the stripping, cutting, filling, stockpiling of earth or land, including the land in its cut or filled condition.

“Gross acreage” means the total area within the lot lines of a lot or parcel of land before public streets, easements or other areas to be dedicated or reserved for public use are deducted from such lot or parcel, and does not include adjacent lands already dedicated for such purposes.

“Hazardous waste” means either of the following:

1. A waste, or combination of wastes, which because of its quantity, concentration or physical, chemical or infectious characteristics may either:
 - a. Cause, or significantly contribute to an increase in mortality or an increase in serious irreversible, or incapacitating reversible, illness, or
 - b. Pose a substantial present or potential hazard to human health or environment when improperly treated, stored, transported or disposed of, or otherwise managed;
2. A waste which meets any of the criteria for the identification of a hazardous waste adopted by the State Department of Health Services pursuant to Health and Safety Code Section 25117 or any other federal, state or local law or regulation;
3. Resource Conservation and Recovery Act hazardous wastes;

4. Unless expressly provided otherwise, the term “hazardous waste” shall be understood to also include extremely hazardous waste and acutely hazardous waste. (Health and Safety Code Section 25117.)

“Improvement” means any item which becomes part of, placed upon, or is affixed to real estate.

“Infill development site” means a parcel or group of parcels that make up a site that is vacant or underutilized and is surrounded by developed land or parcels on at least seventy-five (75) percent of its perimeter. Infill development sites include previously developed sites that may/will be redeveloped.

“Integrated shopping center” means a combination of three (3) or more business establishments permitted or conditional permitted in the zone district in which they are located where off-street parking, landscaping, lighting, or other features are developed, managed and maintained jointly.

“Kitchen” means any room, all or any part of which is designed and/or used for cooking and the preparation of food.

“Landscaping” means an area devoted to, or developed and maintained predominantly with, native or exotic plant materials including lawn, groundcover, trees, shrubs and other plant materials; artificial turf and other permeable surfaces; and also including accessory decorative outdoor landscape elements such as pools, fountains, paved or decorated surfaces (excluding driveways, parking, loading or storage areas), and sculptural elements.

“Land use” means a description of how land (real estate) is occupied or utilized.

“Loading Space” means an off-street space or berth on the same lot with a building or contiguous to a group of buildings for the temporary parking of a commercial vehicle while loading or unloading merchandise or materials.

“Lot” means a parcel, tract or area of land established by plat, subdivision, or as otherwise permitted by law, to be used, developed or built upon. The classifications of lots are:

1. “Corner” means a lot located at the intersection of two or more streets at an angle of not more than one hundred thirty-five (135) degrees. If the angle is greater than one hundred thirty-five (135) degrees, the lot shall be considered an interior lot.
2. “Flag” means a lot having access or an easement to a public or private street by a narrow, private right-of-way.
3. “Interior” means a lot abutting only one street.
4. “Key” means a lot with a side line that abuts the rear line of any one or more adjoining lots.
5. “Reverse corner” means a corner lot, the rear of which abuts the side of another lot.
6. “Through” means a lot having frontage on two generally parallel streets, with only one primary access. (See “Illustration of Terms.”).

“Lot area” means the net horizontal area within bounding lot lines after dedication.

“Lot coverage” means the area of a lot covered by buildings excluding eaves, projecting balconies, ground-level paving, landscaping, and open recreational facilities.

“Lot depth” is the horizontal distance between the midpoint of the front lot line and the midpoint of the rear lot line.

“Lot frontage” means the portion of the lot contiguous to the street.

“Lot line” means any boundary of a lot. The classifications of lot lines are:

1. “Front” means on an interior lot, the line separating the parcel from the street. On a corner lot, the shorter lot line abutting a street. (If the lot lines on a corner lot are equal in length, the front lot line shall be determined by the director). On a through lot, the lot line abutting the street providing the primary access to the lot.
2. “Interior” means any lot line not abutting a street.
3. “Rear” means a lot line, not intersecting a front lot line, which is most distant from and most closely parallel to the front lot line.

“Lot Width” means the horizontal distance between side lot lines, measured at the front setback line.

“Mall” means a large building or series of connected buildings containing a variety of retail stores, restaurants, and entertainment activities including, but not limited to, such activities as theaters, arcades, amusement rides, rock-climbing and other indoor recreation opportunities that serve a regional population.

“Median” means a paved or planted area separating a street or highway into two (2) or more lanes of opposite directions of travel.

“Nonconforming lot” means a lot, the area, frontage or dimensions of which do not conform to the provisions of this zoning code.

“Nonconforming structure” means a structure, lot or use which did conform to applicable laws when constructed or initiated, and which does not now conform to the provisions of this zoning code.

“Nonconforming use” means a use complying with applicable laws when established but which does not conform to the provisions of this zoning code.

“Open space” means any parcel or area of land or water essentially unimproved and set aside, dedicated, designated, or reserved for public or private use or enjoyment or for the use and enjoyment of owners and occupants of land adjoining or neighboring such open space. Does not include area covered by buildings or accessory structures (except recreational structures), paved areas (except recreational facilities), proposed and existing public and private streets or driveways, and school sites.

“Open space, common usable” means recreational or leisure space for the shared use of residents of a multi-unit development with no dimension less than 20-feet and may include gardens, playgrounds, courtyards, swimming pools, sitting areas, court games, recreation rooms, exercise rooms or gyms, spas, community rooms, lawn/turf used for open play, ponds, fountains, atriums, picnic areas, rooftop gardens or green roofs, or similar uses or facilities.

“Overhang” means the part of a roof or wall that extends beyond the façade of a lower wall.

“Overlay district” is a district established by this zoning code which may be applied to a lot or portion thereof only in combination with a base district.

“Parapet” means the extension of the main walls of a building above the roof level.

“Parcel” means a parcel of land under one ownership that has been legally subdivided or combined and is shown as a single parcel on the latest recorded map in the Kings County recorder’s office.

“Parking area” means any public or private land area designed and used for parking motor vehicles including parking lots, garages, private driveways, and legally designated areas of public streets.

“Parking lot” is an off-street, ground-level area, usually surfaced and improved, for the temporary storage of motor vehicles.

“Parking ratio” means the number of parking spaces provided per 1,000 square feet of floor area.

“Parking, shared” means a public or private parking area used jointly by two or more uses.

“Parking space” is the space marked for the parking of a motor vehicle within a public or private parking area.

“Parking structure or structured parking” means a multi-story car park (also called a parking garage or indoor parking) designed for car parking and where there are a number of floors or levels on which parking takes place.

“Parkway” means that portion of the public street right-of-way between the curb or curb line and the adjacent sidewalk or property line, as applicable, used for or which may be used for the purpose of planting and maintaining street trees, shrubs, hedges, or other plants. In some areas within the city, park strips may extend into a private property’s yard beyond the sidewalk. Park strips may be located on private property or may abut private property.

“Performance standards” means zoning regulations that permit uses based on a particular set of standards of operation rather than on particular type of use. Performance standards may provide specific criteria to limit noise, air pollution, emissions, odors, vibration, dust, dirt, glare, heat, fire hazards, wastes, traffic impacts, or visual impact of a use.

“Permit” means a written governmental permission issued by an authorized official, empowering the holder thereof to do some act not forbidden by law, but not allowed without such authorization.

“Person” means any individual, firm, co-partnership, joint venture, association, social club, fraternal organization, company, joint stock association, corporation, estate, trust, organization, business, business trust, public agency, school district, state of California, and its political subdivisions or instrumentalities, receiver, syndicate or any group or combination thereof, acting as a unit, including any trustee, receiver or assignee.

“Permitted use” means any use allowed in a land use zoning district and subject to the provisions applicable to that district.

“Planned unit development (PUD)” means the development of a parcel(s) or structure(s) with two or more different land uses such as, but not limited to a combination of residential, office, manufacturing, retail, public or entertainment in a single or physically integrated group of structures.

“Principal use” means the primary or predominate use of any lot, building or structure.

“Project” means the total development within the boundaries as defined on the development plan.

“Public right-of-way” means a strip of land acquired by reservation, dedication, prescription, voluntary purchase and sale, or condemnation and intended to be occupied by a road, trail, water line, sanitary sewer and/or any other public uses.

“Recreational vehicle” means a vehicle or trailer capable of human habitation or designed or used for recreational camping or travel use, whether self-propelled or mounted on or drawn by another vehicle, or any structure inspected, approved and designated a recreational vehicle and bearing the insignia of the state of California or any other state or federal agency having the authority to approve recreational vehicles. RVs include, without limitation, any of the following: camp trailer, as defined by the California Vehicle Code Section 324; house car, as defined by California Vehicle Code Section 362; trailer coach, as defined by California Vehicle Code Section 635; mobile home, as defined by California Vehicle Code Section 396; bus, as defined by California Vehicle Code Section 233, whether altered or unaltered or for commercial or private use; boat, watercraft, and/or trailer for a boat or watercraft; trailers designed to carry persons, property or animals on its own structure and to be drawn by a motor vehicle; and recreational vehicle, as defined by the California Health and Safety Code Section 18010.

“Recycling” means the process by which waste products are reduced to raw materials and transformed into new reused or reconstructed products which meet the quality standards necessary to be used in the market place.

“Review authority” means the person, committee, commission or council responsible for the review and/or final action on a land use entitlement.

“Right-of-way” means a strip of land acquired by purchase, reservation, dedication, forced dedication, prescription, or condemnation and intended to be occupied or occupied by a road, crosswalk, railroad, electric transmission lines, oil or gas pipeline, water line, sanitary storm sewer, and other similar uses.

“Rounding of quantities” means the consideration of distances, unit density, density bonus calculations, or other aspects of development or the physical environment expressed in numerical quantities which are fractions of whole numbers; the numbers are to be rounded to the nearest highest whole number when the fraction is .5 or more, and to the next lowest whole number when the fraction is .5, except as otherwise provided in this zoning code.

“Screened or screening” means shielded, concealed, and effectively hidden from view by a person standing at ground level on an abutting site, or outside the area, screened by a fence, wall, hedge, berm, or similar architectural or landscape feature that is at least 90% view obscuring.

“Setback” means the area between the setback line and property line.

“Setback line” is a line within a lot parallel to and measured from a corresponding lot line, forming the boundary of a required yard and governing the placement of structures and uses on the lot.

“Sign” means any letter or symbol made of cloth, metal, paint, paper, wood or other material of any kind whatsoever placed for advertising, identification or other similar purposes on the ground or on any wall, post, fence, building, structure, vehicle or on any place whatsoever.

“Site” the land or area that is the subject of a development project or use, and may include more than one lot or parcel.

“Site area” means the net horizontal area included within the boundary lines of a site, not including the area within the established right-of-way of a public street, future public street, or railroad, or any other area dedicated or to be dedicated for a public use.

“Site plan” means a plan, prepared to scale, showing accurately and with complete dimensioning all of the buildings, structures, and uses and the exact manner of development proposed for a specific parcel of land.

“Slope” means the degree of deviation of a surface from the horizontal, usually expressed in percentage or degrees.

“Solar facilities” means the airspace over a parcel that provides access for solar energy system to absorb energy from the sun.

“Specific plan” means a plan consisting of text, maps and other documents and exhibits regulating development within a defined area of the city, consistent with the General Plan and the provisions of Government Code Section 65450 et seq.

“Story” means that portion of a building included between the surface of any floor and the surface of any floor next above it, or if there be no floor above it, then the space between such floor and ceiling next above it.

“Street” means any public or private thoroughfare with a width of twenty feet (20’) or more which affords a primary means of access to abutting property.

“Street, private” means a street in private ownership, not dedicated as a public street, which provides the principal means of vehicular access to a property and not to be construed to mean driveways, alleys, or parking areas.

“Street, public” is a street owned and maintained by the City, the County, or the State. The term includes streets offered for dedication which have been improved or for which a bonded improvement agreement is in effect.

“Structural Alterations” means any change in the supporting members of a structure such as the bearing walls or partitions, columns, beams, or girders.

“Structure” means anything constructed or built. An edifice or building of any kind, or any piece of work artificially built up or composed of parts joined together in some definite manner.

“Structure, accessory” means a subordinate building which is incidental and not attached to the main building or use on the same lot. If an accessory building is attached to the main building or if the roof is a continuation of the main building roof, the accessory building shall be considered an addition to the main building. Includes structures regardless of whether a Building Permit is required, including, but not limited to, enclosed and unenclosed patios, barns, guesthouses, second dwelling units, garages, carports, storage buildings/sheds, trellis, gazebos, decks, and real or artificial rockscapes.

“Structure, temporary” means a structure without any foundation or footings and which is removed when the designated time period, activity, or use for which the temporary structure was erected has ceased.

“Target population” means persons with low incomes who have one or more disabilities, including mental illness, HIV or AIDS, substance abuse, or other chronic health condition, or individuals eligible for services provided pursuant to the Lanterman Developmental Disabilities Services Act (Division 4.5 (commencing with Section 4500) of the Welfare and Institutions Code) and may include, among other populations, adults, emancipated minors, families with children, elderly persons, young adults aging out of the foster care system, individuals exiting from institutional settings, veterans, and homeless people.

“Temporary structure” is a structure without any foundation or footings, and which is removed when the designated time period, activity, or use for which the temporary structure was erected has ceased.

“Temporary use” means a use established for a designated period of time, with the intent to discontinue the use at the end of the designated time period.

“Traffic safety sight area” means a space that is set aside on a corner lot in which all visual obstructions, such as structures and plantings, which inhibit visibility and thus cause a hazard to traffic and pedestrian safety are prohibited.

“Transient basis” means a continuous period of two (2) weeks or less.

“Underutilized land” means land with a structure or structures that occupy only a small portion of the land and is being used significantly below its potential use.

“Use” means the purpose (type or extent) for which land or a building is arranged, designed or intended or for which either land or a structure is occupied or maintained.

“Use initiation” means the implementation of a use on a parcel or occupancy of a structure, or construction of substantial site improvements after a building permit has been issued, subject to determination by the director.

“Use, accessory” means a use which is incidental to, and customarily associated with, a specified principal use and which meets the applicable conditions set forth in this ordinance.

“Use, allowed” means a use listed by the regulation of any particular district as a permitted use within that district and permitted therein as a matter of right when conducted in accord with the regulations established by this Ordinance.

“Use, conditional” means a use listed by the regulations of any particular district as a conditional use within that district and allowable therein, solely on a discretionary and conditional basis, subject to development/design review or to a Conditional Use Permit, and to all other regulations established by this Code.

“Use, principal” means a use which fulfills a primary function of a household, establishment, institution, or other entity.

“Use, temporary” means a use established for a fixed period of time with the intent to discontinue such use upon the expiration of the time period.

“Variance” means a discretionary entitlement which permits the departure from the strict application of the development standards contained in this zoning code.

“Vehicle” means self-propelled device by which persons or property may be moved upon a highway, excepting a device moved by human power or used exclusively upon stationary rails or tracks.

“Wildlands” means any area of land that is essentially unimproved, in a natural state of hydrology, vegetation and animal life, and not under cultivation.

“Yard” means an open space that lies between the principal or accessory building or buildings and the nearest lot line.

“Zero Lot Line” means the location of a building on a lot in such a manner that one or more of the building's sides rest directly on a lot line.

“Zoning certificate of occupancy” means a permit issued by the community development department which allows the occupancy of a structure which conforms to all applicable provisions of this chapter and any and all conditions or requirements issued by the city or any of its departments, or by any other federal, state or local agency or body.

“Zoning district” means a portion of the city within which certain uses of land and structures are defined, and regulations are specified.

Notice of Exemption 2019-19

To: ☐ Office of Planning and Research
P.O. Box 3044, Room 212
Sacramento, CA 95812-3044

☒ County Clerk
County of Kings
Kings County Government Center
Hanford, CA 93230

From: City of Hanford
317 North Douty Street
Hanford, CA 93230

Project Title: Municipal Code Amendment 2019-01

Project Location – City of Hanford

Project Location – City: Hanford **Project Location – County:** Kings County

Description of Nature, Purpose and Beneficiaries of Project: **MUNICIPAL CODE AMENDMENT NO. 2019-01:** a request by 198-43, LLC to amend Title 17, Section 17.08.030 – Commercial, Office, and Industrial Zone Use Table of the Hanford Municipal Code by adding sections in order to permit or permit with a conditional use permit, the following uses in the C-R Regional Commercial zone district: colleges; exercise studios; large health facilities; business support services; medical offices; professional and commercial offices; laboratories; furniture stores; and food catering

Name of Public Agency Approving Project: City of Hanford, Planning Division

Name of Person or Agency Carrying Out Project: 198-43, LLC

Exempt Status: **(check one)**

- ☐ Ministerial (Sec. 21080(b)(1); 152698);
☐ Declared Emergency (Sec. 21080(b)(3); 15269 (a));
☐ Emergency Project (Sec. 21080(b)(4); 15269(b)(c));
☐ Categorical Exemption: State type and section number:
☒ Statutory Exemption. State code number: 15061(b)(3) General Rule

Reasons why project is exempt:

The City of Hanford determined the project to be exempt from environmental review pursuant to Section 15061(b)(3) of the California Environmental Quality Act (CEQA). Section 15061(b)(3) states that where it can be seen with certainty that there is no possibility that the activity in question may have a significant effect on the environment, the activity is not subject to CEQA. No significant environmental impacts would occur as a result of the proposed ordinance.

Lead Agency

Contact Person: Darlene R. Mata Area Code/ Telephone: (559) 585-2590

Signature: _____ Date: May 14, 2018 Title: Community Development Director

☒ Signed by Lead Agency Date received for filing at OPR: _____
☐ Signed by Applicant

Attachment: Attachment 3 - Notice of Exemption 2019-19 (MCA 2019-01)